DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
OFFICE ENGINEER
1727 30th Street MS-43
P.O. BOX 168041
SACRAMENTO, CA 95816-8041
FAX (916) 227-6214
www.dot.ca.gov/hq/esc/oe

Serious Drought.
Help save water!

September 1, 2016

04-Ala-205-0.0/1.0
04-Ala-580-0.0/8.0, 26.1/30.3
10-SJ-580-13.5/15.4
04-3G59U4
Project ID 0415000066
ACIM-000C(438)E

Addendum No. 5

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN ALAMEDA AND SAN JOAQUIN COUNTIES ON ROUTE 580 FROM PATTERSON PASS ROAD OVERCROSSING TO GREENVILLE OVERHEAD AND FROM EDEN CANYON ROAD UNDERCROSSING TO STROBRIDGE AVENUE UNDERCROSSING AND ON ROUTE 205 FROM SAN JOAQUIN COUNTY LINE TO MIDWAY ROAD UNDERCROSSING to revise the project plans, the *Notice to Bidders and Special Provisions*, the *Bid* book, and the Federal Minimum Wages with Modification Number 10 dated 08/26/2016.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Wednesday, September 14, 2016.

Project plan sheets 46, 47, 50, 59, 60, 61, 62, 63, 64, 65, 75, 152, 214, 244, 260, 261, 262, 263, 264, 268, 386, 463, 465, 467, 468, 469, 471, 472, and 476 are replaced and attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 37-2.05B(2)(f), the first paragraph is replaced as follows:

"Screening for asphalt rubber seal coat must comply with the 3/8-inch grading."

In the *Bid* book, in the "Bid Item List," Items 29, 55, 77, 82, 89, 96, 141, and 160 are replaced.

In the *Bid* book, in the "Bid Item List," Item 152 is deleted.

04-Ala-205-0.0/1.0
04-Ala-580-0.0/8.0, 26.1/30.3
10-SJ-580-13.5/15.4
04-3G59U4
Project ID 0415000066
ACIM-000C(438)E

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file, attachments and the modified wage rates are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/04/04-3G59U4

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

for BIJAN SARTIPI
District Director

Attachments

BID ITEM LIST
04-3G59U4

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21	130680	TEMPORARY SILT FENCE	LF	4,000		
22	130710	TEMPORARY CONSTRUCTION ENTRANCE	EA	8		
23	130730	STREET SWEEPING	LS	LUMP SUM	LUMP SUM	
24	130900	TEMPORARY CONCRETE WASHOUT	LS	LUMP SUM	LUMP SUM	
25	141103	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE (HAZARDOUS WASTE)	LF	91,900		
26	141120	TREATED WOOD WASTE	LB	388,000		
27	150203	ABANDON CULVERT (EA)	EA	3		
28	150310	RAPID SETTING CONCRETE (PATCH)	CF	170		
29	150606	REMOVE FENCE (TYPE BW)	LF	340		
30	150661	REMOVE GUARDRAIL	LF	30,300		
31	150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	LF	173,000		
32	150722	REMOVE PAVEMENT MARKER	EA	96,400		
33	150742	REMOVE ROADSIDE SIGN	EA	14		
34	150770	REMOVE ASPHALT CONCRETE PAVEMENT (SQFT)	SQFT	168,000		
35	150771	REMOVE ASPHALT CONCRETE DIKE	LF	62,200		
36	031338	ABANDON EDGE DRAIN CLEANOUT AND VENT	EA	47		
37	031339	REMOVE EDGE DRAIN	LF	35,900		
38	150809	REMOVE CULVERT (LF)	LF	250		
39	150820	REMOVE INLET	EA	9		
40	150854	REMOVE CONCRETE PAVEMENT (CY)	CY	9,820		

REPLACED PER ADDENDUM NO. 5 DATED SEPTEMBER 1, 2016

BID ITEM LIST
04-3G59U4

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
41	150857	REMOVE ASPHALT CONCRETE SURFACING	SQFT	49,831		
42	152430	ADJUST INLET	EA	130		
43	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	712,000		
44	153120	REMOVE CONCRETE (LF)	LF	16		
45	153215	REMOVE CONCRETE (CURB AND GUTTER)	LF	240		
46	153221	REMOVE CONCRETE BARRIER	LF	7,840		
47	153223	REMOVE UNSOUND CONCRETE	CF	170		
48	153225	PREPARE CONCRETE BRIDGE DECK SURFACE	SQFT	50,335		
49	153227	FURNISH POLYESTER CONCRETE OVERLAY	CF	3,857		
50 (F)	153228	PLACE POLYESTER CONCRETE OVERLAY	SQFT	54,645		
51	153229	REMOVE CONCRETE BARRIER (TYPE K)	LF	100		
52	045329	REMOVE CONCRETE BARRIER (TYPE 60D MODIFIED)	LF	1,396		
53	153240	REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK) (CY)	CY	3.3		
54	155003	CAP INLET	EA	1		
55	155231	CULVERT SLURRY-CEMENT BACKFILL	CY	3,650		
56	156585	REMOVE CRASH CUSHION	EA	1		
57	160102	CLEARING AND GRUBBING (LS)	LS	LUMP SUM	LUMP SUM	
58	170101	DEVELOP WATER SUPPLY	LS	LUMP SUM	LUMP SUM	
59	190101	ROADWAY EXCAVATION	CY	9,690		
60 (F)	192049	STRUCTURE EXCAVATION (SOLDIER PILE WALL)	CY	103		

REPLACED PER ADDENDUM NO. 5 DATED SEPTEMBER 1, 2016

BID ITEM LIST
04-3G59U4

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61 (F)	193006	STRUCTURE BACKFILL (SLURRY CEMENT)	CY	1,726		
62 (F)	193029	STRUCTURE BACKFILL (SOLDIER PILE WALL)	CY	17		
63 (F)	193030	PERVIOUS BACKFILL MATERIAL	CY	499		
64 (F)	193116	CONCRETE BACKFILL (SOLDIER PILE WALL)	CY	131		
65 (F)	193119	LEAN CONCRETE BACKFILL	CY	57		
66	194001	DITCH EXCAVATION	CY	1,690		
67	031340	LIGHTWEIGHT AGGREGATE IMPORTED BORROW	CY	740		
68	198010	IMPORTED BORROW (CY)	CY	5,000		
69	198210	SUBGRADE ENHANCEMENT GEOTEXTILE, CLASS B3	SQYD	2,000		
70	210010	MOVE-IN/MOVE-OUT (EROSION CONTROL)	EA	12		
71	210300	HYDROMULCH	SQFT	94,900		
72	210350	FIBER ROLLS	LF	138,000		
73	210430	HYDROSEED	SQFT	94,900		
74	250401	CLASS 4 AGGREGATE SUBBASE	CY	180		
75	260203	CLASS 2 AGGREGATE BASE (CY)	CY	680		
76	280000	LEAN CONCRETE BASE	CY	350		
77	280015	LEAN CONCRETE BASE RAPID SETTING	CY	5,550		
78	280200	REPLACE BASE	CY	240		
79	360200	BASE BOND BREAKER	SQYD	2,500		
80	370120	ASPHALT-RUBBER BINDER	TON	180		

REPLACED PER ADDENDUM NO. 5 DATED SEPTEMBER 1, 2016

BID ITEM LIST
04-3G59U4

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
81	375035	PRECOATED SCREENINGS	TON	2,100		
82	390132	HOT MIX ASPHALT (TYPE A)	TON	195,000		
83	390135	HOT MIX ASPHALT (LEVELING)	TON	20,400		
84	390137	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	TON	73,700		
85	390403	RUBBERIZED HOT MIX ASPHALT-OPEN GRADED HIGH BINDER(OPEN GRADED FRICTION COURSE)	TON	28,900		
86	391006	ASPHALT BINDER (GEOSYNTHETIC PAVEMENT INTERLAYER)	TON	330		
87	393005	GEOSYNTHETIC PAVEMENT INTERLAYER (PAVING MAT)	SQYD	303,000		
88	394053	SHOULDER RUMBLE STRIP (HMA,GROUND-IN INDENTATIONS)	STA	835		
89	394074	PLACE HOT MIX ASPHALT DIKE (TYPE C)	LF	2,410		
90	394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	LF	49,700		
91	394077	PLACE HOT MIX ASPHALT DIKE (TYPE F)	LF	15,800		
92	394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQYD	220		
93	397005	TACK COAT	TON	1,970		
94	031341	PRECAST JOINTED CONCRETE PAVEMENT	CY	6,540		
95	411105	INDIVIDUAL SLAB REPLACEMENT (RSC)	CY	4,700		
96	413000	CRACK AND SEAT	SQYD	278,000		
97	045330	STEEL SOLDIER PILE (W 24 X 146)	LF	726		
98	490406	36" DRILLED HOLE	LF	718		
99	498052	60" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	53		
100 (F)	510060	STRUCTURAL CONCRETE, RETAINING WALL	CY	41		

REPLACED PER ADDENDUM NO. 5 DATED SEPTEMBER 1, 2016

BID ITEM LIST
04-3G59U4

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
141	800007	FENCE (TYPE BW, 5-STRAND, METAL POST)	LF	340		
142	031344	CONCRETE BARRIER MARKER	EA	180		
143	820107	DELINEATOR (CLASS 1)	EA	210		
144	820118	GUARD RAILING DELINEATOR	EA	300		
145	820134	OBJECT MARKER (TYPE P)	EA	54		
146	820151	OBJECT MARKER (TYPE L-1)	EA	47		
147	832007	MIDWEST GUARDRAIL SYSTEM (WOOD POST)	LF	30,900		
148	832070	VEGETATION CONTROL (MINOR CONCRETE)	SQYD	11,400		
149	839302	SINGLE THRIE BEAM BARRIER (WOOD POST)	LF	3,660		
150	839311	DOUBLE THRIE BEAM BARRIER (WOOD POST)	LF	480		
151 (F)	839521	CABLE RAILING	LF	141		
152	BLANK					
153	839543	TRANSITION RAILING (TYPE WB-31)	EA	28		
154	839581	END ANCHOR ASSEMBLY (TYPE SFT)	EA	23		
155	839584	ALTERNATIVE IN-LINE TERMINAL SYSTEM	EA	20		
156	839585	ALTERNATIVE FLARED TERMINAL SYSTEM	EA	25		
157	839591	CRASH CUSHION, SAND FILLED	EA	1		
158	839701	CONCRETE BARRIER (TYPE 60)	LF	520		
159 (F)	839702	CONCRETE BARRIER (TYPE 60A)	LF	135		
160	839703	CONCRETE BARRIER (TYPE 60C)	LF	25,900		

REPLACED PER ADDENDUM NO. 5 DATED SEPTEMBER 1, 2016