

**\*\* WARNING \*\* WARNING \*\* WARNING \*\* WARNING \*\***

**This document is intended for informational purposes only.**

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.



STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION

---

**NOTICE TO CONTRACTORS  
AND  
SPECIAL PROVISIONS  
FOR CONSTRUCTION ON STATE HIGHWAY IN  
LOS ANGELES COUNTY IN LOS ANGELES ON ROUTE 5  
FROM 0.2 KM NORTH OF BOYLE AVENUE OVERCROSSING  
TO EUCLID AVENUE UNDERCROSSING SOUTH AND ON  
ROUTE 60 FROM ROUTE 60/5 SEPARATION  
TO EUCLID AVENUE UNDERCROSSING NORTH**

**DISTRICT 07, ROUTES 5, 60**

---

**For Use in Connection with Standard Specifications Dated JULY 1999, Standard Plans Dated JULY 1999, and Labor  
Surcharge and Equipment Rental Rates.**

---

**CONTRACT NO. 07-053514  
07-LA-5,60-25.4/27.2,R0.7/R1.6**

**Federal Aid Project  
ACIM-005-2(901)E  
ACNH-P060(122)E**

**Bids Open: January 9, 2003  
Dated: December 2, 2002**

**OSD**

# TABLE OF CONTENTS

NOTICE TO CONTRACTORS .....	1
COPY OF ENGINEER'S ESTIMATE .....	3
SPECIAL PROVISIONS .....	8
SECTION 1. SPECIFICATIONS AND PLANS .....	8
AMENDMENTS TO JULY 1999 STANDARD SPECIFICATIONS .....	8
SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS .....	43
2-1.01 GENERAL .....	43
2-1.015 FEDERAL LOBBYING RESTRICTIONS .....	43
2-1.02 DISADVANTAGED BUSINESS ENTERPRISE (DBE) .....	43
2-1.02A DBE GOAL FOR THIS PROJECT .....	45
2-1.02B SUBMISSION OF DBE INFORMATION .....	45
SECTION 3. AWARD AND EXECUTION OF CONTRACT .....	46
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES .....	47
SECTION 5. GENERAL .....	47
SECTION 5-1. MISCELLANEOUS .....	47
5-1.01 PLANS AND WORKING DRAWINGS .....	47
5-1.011 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK .....	47
5-1.012 DIFFERING SITE CONDITIONS .....	47
5-1.013 LINES AND GRADES .....	47
5-1.015 LABORATORY .....	47
5-1.017 CONTRACT BONDS .....	48
5-1.019 COST REDUCTION INCENTIVE .....	48
5-1.02 LABOR NONDISCRIMINATION .....	48
5-1.022 PAYMENT OF WITHHELD FUNDS .....	48
5-1.03 INTEREST ON PAYMENTS .....	48
5-1.031 FINAL PAYMENT AND CLAIMS .....	49
5-1.04 PUBLIC SAFETY .....	49
5-1.05 TESTING .....	50
5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES .....	50
5-1.07 YEAR 2000 COMPLIANCE .....	50
5-1.075 BUY AMERICA REQUIREMENTS .....	51
5-1.08 SUBCONTRACTOR AND DBE RECORDS .....	51
5-1.083 DBE CERTIFICATION STATUS .....	51
5-1.086 PERFORMANCE OF DBE SUBCONTRACTORS AND SUPPLIERS .....	51
5-1.09 SUBCONTRACTING .....	52
5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS .....	52
5-1.102 PROMPT PAYMENT OF WITHHELD FUNDS TO SUBCONTRACTORS .....	53
5-1.103 RECORDS .....	53
5-1.11 PARTNERING .....	53
5-1.12 AREAS FOR CONTRACTOR'S USE .....	53
5-1.13 PAYMENTS .....	54
5-1.14 MIGRATORY BIRD ACT REQUIREMENTS .....	54
5-1.15 SOUND CONTROL REQUIREMENTS .....	55
5-1.16 ACCESS TO THE WORK AREA .....	55
5-1.17 RELATIONS WITH CITY OF LOS ANGELES .....	55
5-1.18 AERIALY DEPOSITED LEAD .....	55
SECTION 6. (BLANK) .....	56
SECTION 7. (BLANK) .....	56
SECTION 8. MATERIALS .....	56
SECTION 8-1. MISCELLANEOUS .....	56
8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS .....	56
8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS .....	62
8-1.03 STATE-FURNISHED MATERIALS .....	67

8-1.04	SLAG AGGREGATE.....	67
8-1.05	ENGINEERING FABRICS.....	67
SECTION 8-2.	CONCRETE.....	67
8-2.01	PORTLAND CEMENT CONCRETE.....	67
SECTION 8-3.	WELDING.....	69
8-3.01	WELDING.....	69
	GENERAL.....	69
	WELDING QUALITY CONTROL.....	70
	PAYMENT.....	73
SECTION 9.	DESCRIPTION OF BRIDGE WORK.....	73
SECTION 10.	CONSTRUCTION DETAILS.....	74
SECTION 10-1.	GENERAL.....	74
10-1.00	CONSTRUCTION PROJECT INFORMATION SIGNS.....	74
10-1.01	ORDER OF WORK.....	75
10-1.02	WATER POLLUTION CONTROL.....	76
	RETENTION OF FUNDS.....	76
	WATER POLLUTION CONTROL PROGRAM PREPARATION, APPROVAL AND AMENDMENTS.....	77
	COST BREAK-DOWN.....	78
	WPCP IMPLEMENTATION.....	81
	MAINTENANCE.....	82
	REPORTING REQUIREMENTS.....	82
	PAYMENT.....	82
10-1.03	TEMPORARY SUPPORTS.....	83
	TEMPORARY SUPPORT DESIGN AND DRAWINGS.....	83
	TEMPORARY SUPPORT DESIGN CRITERIA.....	84
	SPECIAL LOCATIONS.....	84
	TEMPORARY SUPPORT CONSTRUCTION.....	85
	REMOVING TEMPORARY SUPPORTS.....	85
	PAYMENT.....	85
10-1.04	TEMPORARY FENCE (TYPE CL-1.8).....	86
10-1.05	PRESERVATION OF PROPERTY.....	86
10-1.06	RELIEF FROM MAINTENANCE AND RESPONSIBILITY.....	86
10-1.07	COOPERATION.....	86
10-1.08	PROGRESS SCHEDULE (CRITICAL PATH METHOD).....	87
	DEFINITIONS.....	87
	GENERAL REQUIREMENTS.....	87
	COMPUTER SOFTWARE.....	88
	NETWORK DIAGRAMS, REPORTS AND DATA.....	88
	BASELINE SCHEDULE.....	88
	UPDATE SCHEDULE.....	88
	FINAL UPDATE SCHEDULE.....	89
	RETENTION.....	89
	PAYMENT.....	89
10-1.09	OBSTRUCTIONS.....	89
10-1.10	DUST CONTROL.....	90
10-1.11	MOBILIZATION.....	90
10-1.12	CONSTRUCTION AREA TRAFFIC CONTROL DEVICES.....	90
10-1.13	CONSTRUCTION AREA SIGNS.....	90
10-1.14	MAINTAINING TRAFFIC.....	91
10-1.15	CLOSURE REQUIREMENTS AND CONDITIONS.....	99
	CLOSURE SCHEDULE.....	99
	CONTINGENCY PLAN.....	99
	LATE REOPENING OF CLOSURES.....	99
	COMPENSATION.....	99
10-1.16	TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE.....	99
	STATIONARY LANE CLOSURE.....	100
	MOVING LANE CLOSURE.....	100
	PAYMENT.....	101

10-1.17	TEMPORARY PAVEMENT DELINEATION.....	101
	GENERAL.....	101
	TEMPORARY LANELINE DELINEATION.....	101
	TEMPORARY EDGELINE DELINEATION.....	102
	TEMPORARY TRAFFIC STRIPE (TAPE).....	102
	TEMPORARY PAVEMENT MARKERS.....	103
	MEASUREMENT AND PAYMENT.....	103
10-1.18	BARRICADE.....	103
10-1.19	PORTABLE CHANGEABLE MESSAGE SIGN.....	104
10-1.20	TEMPORARY RAILING.....	104
10-1.21	CHANNELIZER.....	104
10-1.22	TEMPORARY CRASH CUSHION MODULE.....	104
10-1.23	EXISTING HIGHWAY FACILITIES.....	106
	REMOVE CHAIN LINK FENCE.....	106
	REMOVE METAL BEAM GUARD RAILING.....	106
	REMOVE PAVEMENT MARKER.....	106
	REMOVE CONCRETE MASONRY BLOCK WALL.....	106
	REMOVE RETAINING WALL.....	106
	REMOVE THERMOPLASTIC TRAFFIC STRIPE.....	106
	REMOVE DRAINAGE FACILITY.....	107
	REMOVE ROADSIDE SIGN.....	107
	RECONSTRUCT PROPERTY SIDE YARD WALLS OR FENCES.....	108
	ADJUST MANHOLE TO GRADE.....	108
	BRIDGE REMOVAL (PORTION).....	108
	CLEAN BRIDGE DECK.....	110
	REMOVE CONCRETE.....	110
	REMOVE CONCRETE BARRIER.....	110
10-1.24	CLEARING AND GRUBBING.....	111
10-1.25	EARTHWORK.....	111
10-1.26	CONTROLLED LOW STRENGTH MATERIAL.....	111
10-1.27	MATERIAL CONTAINING AERIALY DEPOSITED LEAD.....	112
	LEAD COMPLIANCE PLAN.....	113
	EXCAVATION AND TRANSPORTATION PLAN.....	113
	DUST CONTROL.....	114
	MATERIAL TRANSPORTATION.....	114
	DISPOSAL.....	114
	MEASUREMENT AND PAYMENT.....	114
10-1.28	EXTEND IRRIGATION CROSSOVERS.....	114
10-1.29	AGGREGATE BASE.....	115
10-1.30	ASPHALT CONCRETE.....	115
10-1.31	PILING.....	115
	GENERAL.....	115
	CAST-IN-DRILLED-HOLE CONCRETE PILES.....	116
	MEASUREMENT AND PAYMENT (PILING).....	125
10-1.32	CONCRETE STRUCTURES.....	125
	GENERAL.....	125
	CONCRETE BARRIER SLABS.....	125
	FALSEWORK.....	126
	DECK CLOSURE POURS.....	127
	DECK CRACK TREATMENT.....	127
	MEASUREMENT AND PAYMENT.....	129
10-1.33	PAVING NOTCH EXTENSION.....	129
10-1.34	SOUND WALL.....	130
	SOUND WALL (MASONRY BLOCK), SOUND WALL (RETAINING WALL) (MASONRY BLOCK), AND SOUND WALL (BARRIER) (MASONRY BLOCK).....	130
	ACCESS GATES.....	131
	MEASUREMENT AND PAYMENT.....	132
10-1.35	DRILL AND BOND DOWEL (EPOXY CARTRIDGE).....	132

10-1.36	DRILL AND BOND DOWELS .....	133
10-1.37	SEALING JOINTS .....	133
10-1.38	REINFORCEMENT .....	133
	ULTIMATE BUTT SPLICES.....	133
	SERVICE BUTT SPLICES .....	137
	EPOXY-COATED REINFORCEMENT.....	139
	MEASUREMENT AND PAYMENT.....	139
10-1.39	WATERPROOFING.....	139
10-1.40	TREAT BRIDGE DECKS .....	140
10-1.41	ROADSIDE SIGNS .....	143
10-1.42	INSTALL SIGN OVERLAY.....	143
10-1.43	REINFORCED CONCRETE PIPE .....	143
10-1.44	SLOPE PROTECTION.....	143
10-1.45	MISCELLANEOUS IRON AND STEEL .....	143
10-1.46	MISCELLANEOUS METAL (BRIDGE).....	144
10-1.47	CHAIN LINK WALK GATE.....	144
10-1.48	METAL BEAM GUARD RAILING (WOOD POST).....	144
	TERMINAL SYSTEM (TYPE SRT).....	144
10-1.49	CONCRETE BARRIER .....	145
10-1.50	THERMOPLASTIC TRAFFIC STRIPE .....	145
10-1.51	PAVEMENT MARKERS.....	145
SECTION 10-2	HIGHWAY PLANTING AND IRRIGATION SYSTEMS.....	145
10-2.01	GENERAL.....	145
	PROGRESS INSPECTIONS .....	145
	COST BREAK-DOWN .....	146
10-2.02	EXISTING HIGHWAY PLANTING.....	150
	MAINTAIN EXISTING PLANTS .....	150
	REMOVE EXISTING PLANTS FOR TRENCHING.....	150
	PRUNE EXISTING PLANTS .....	150
10-2.03	EXISTING HIGHWAY IRRIGATION FACILITIES .....	150
	LOCATE EXISTING CROSSOVERS AND CONDUITS .....	150
	CHECK AND TEST EXISTING IRRIGATION FACILITIES .....	150
	MAINTAIN EXISTING IRRIGATION FACILITIES.....	151
	REMOVE EXISTING IRRIGATION FACILITIES .....	151
10-2.04	HIGHWAY PLANTING .....	151
	HIGHWAY PLANTING MATERIALS.....	151
	ROADSIDE CLEARING.....	152
	PESTICIDES.....	152
	PREPARING PLANTING AREAS.....	153
	PREPARE HOLES.....	153
	PLANTING.....	153
	PLANT ESTABLISHMENT WORK .....	153
10-2.05	IRRIGATION SYSTEMS .....	154
	VALVE BOXES .....	154
	ELECTRIC AUTOMATIC IRRIGATION COMPONENTS.....	154
	IRRIGATION SYSTEMS FUNCTIONAL TEST.....	155
	PIPE.....	156
	SPRINKLERS .....	156
	NOZZLE LINE INSTALLATION .....	156
	WYE STRAINERS .....	156
	FINAL IRRIGATION SYSTEM CHECK.....	156
SECTION 10-3	SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS .....	157
10-3.01	DESCRIPTION.....	157
10-3.02	ABBREVIATIONS AND GLOSSARY .....	158
	Abbreviations: .....	158
	Glossary:.....	160
10-3.03	COST BREAK-DOWN .....	161
10-3.04	MAINTAINING EXISTING AND TEMPORARY ELECTRICAL SYSTEMS.....	162

MAINTAINING EXISTING COMMUNICATION SYSTEM ROUTING FACILITIES.....	162
10-3.05 LIGHTING (TEMPORARY).....	162
10-3.06 COMMUNICATION SYSTEM ROUTING.....	163
COMMUNICATION SYSTEM ROUTING (MODIFY).....	163
10-3.07 CONDUIT.....	164
COMMUNICATION CONDUIT.....	165
10-3.08 WARNING TAPE.....	166
10-3.09 COLORED CEMENT BACKFILL.....	166
10-3.10 0.5 MM PLASTIC SHEET.....	166
SIZE 103 COMMUNICATION CONDUIT (BRIDGE).....	166
BRIDGE METAL SUPPORTS.....	167
10-3.11 SIZE 53 INNERDUCT.....	167
10-3.12 PULL BOXES.....	168
COMMUNICATION PULL BOXES.....	168
10-3.13 CONDUCTORS AND WIRING.....	169
TWISTED PAIR CABLE.....	169
10-3.14 TWISTED PAIR SPLICE CLOSURE.....	170
10-3.15 FIBER OPTIC CABLE.....	171
DEFINITIONS.....	171
FIBER OPTIC OUTSIDE PLANT CABLE.....	172
LABELING.....	175
CABLE INSTALLATION.....	178
SPLICING.....	178
SPLICE CLOSURES.....	179
SPLICE TRAYS.....	179
PASSIVE CABLE ASSEMBLIES AND COMPONENTS.....	179
FIBER OPTIC CABLE TERMINATIONS.....	180
FIBER OPTIC TESTING.....	181
10-3.16 SERVICE.....	186
10-3.17 NUMBERING ELECTRICAL EQUIPMENT.....	186
10-3.18 LUMINAIRES.....	186
10-3.19 PHOTOELECTRIC CONTROLS.....	186
10-3.20 WORKS AT EXISTING EAST LOS ANGELES (ELA) HUB BUILDING.....	186
ACCESS TO EXISTING EAST LOS ANGELES (ELA) HUB BUILDING.....	186
10-3.21 SYSTEM TESTING, SYSTEM DOCUMENTATION AND FINAL ACCEPTANCE.....	187
SYSTEM TESTING.....	187
SYSTEM DOCUMENTATION.....	190
FINAL ACCEPTANCE.....	191
10-3.22 COMMUNICATION SYSTEM ROUTING CUTOVER.....	191
10-3.23 REMOVING, DISPOSING OR SALVAGING ELECTRICAL EQUIPMENT.....	192
10-3.24 DISPOSING OF ELECTRICAL EQUIPMENT.....	192
10-3.25 PAYMENT.....	192
SECTION 11. (BLANK).....	193
SECTION 12. (BLANK).....	193
SECTION 13. (BLANK).....	193
SECTION 14 FEDERAL REQUIREMENTS FOR FEDERAL-AID CONSTRUCTION PROJECTS.....	194
FEDERAL REQUIREMENT TRAINING SPECIAL PROVISIONS.....	213

# STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to those indicated below. The Revised Standard Plans (RSP) and New Standard Plans (NSP) which apply to this contract are included as individual sheets of the project plans.

A10A	Abbreviations
A10B	Symbols
A20A	Pavement Markers and Traffic Lines, Typical Details
A20B	Pavement Markers and Traffic Lines, Typical Details
A20C	Pavement Markers and Traffic Lines, Typical Details
A20D	Pavement Markers and Traffic Lines, Typical Details
A24A	Pavement Markings - Arrows
A24B	Pavement Markings - Arrows
RSP A35A	Portland Cement Concrete Pavement (Undoweled Transverse Joints)
RSP A73C	Delineators, Channelizers and Barricades
A77A	Metal Beam Guard Railing – Typical Wood Post With Wood Block
A77B	Metal Beam Guard Railing - Standard Hardware
A77C	Metal Beam Guard Railing – Wood Post and Wood Block Details
A77D	Metal Beam Guard Railing – Typical Layouts
A77E	Metal Beam Guard Railing – Typical Layouts
A77F	Metal Beam Guard Railing – Typical Embankment Widening for End Treatments
A85	Chain Link Fence
A87	Curbs, Dikes and Driveways
D73	Drainage Inlets
D74B	Drainage Inlets
D75A	Pipe Inlets
D75B	Pipe Inlets
D75C	Pipe Inlets
D77A	Grate Details
D93B	Drainage Inlet Riser Connections
H1	Planting and Irrigation - Abbreviations
H2	Planting and Irrigation - Symbols
H3	Planting and Irrigation Details
H4	Planting and Irrigation Details
H5	Planting and Irrigation Details
H6	Planting and Irrigation Details
H7	Planting and Irrigation Details
H8	Planting and Irrigation Details
T1A	Temporary Crash Cushion, Sand Filled (Unidirectional)
T1B	Temporary Crash Cushion, Sand Filled (Bidirectional)
RSP T2	Temporary Crash Cushion, Sand Filled (Shoulder Installations)
T3	Temporary Railing (Type K)
T4	Temporary Traffic Screen
T7	Construction Project Funding Identification Signs
T10	Traffic Control System for Lane Closure On Freeways and Expressways
T10A	Traffic Control System for Lane and Complete Closures On Freeways and Expressways
T14	Traffic Control System for Ramp Closure
B0-5	Bridge Details
B2-3	400 mm Cast-In-Drilled Hole-Concrete Pile
RSP B3-1	Retaining Wall Type 1 - H=1200 Through 9100 mm
RSP B3-8	Retaining Wall Details No. 1
B6-21	Joint Seals (Maximum Movement Rating = 50 mm)
B7-1	Box Girder Details
RSP B11-53	Concrete Barrier Type 25

RSP B11-56	Concrete Barrier Type 736
B14-3	Communication and Sprinkler Control Conduits (Conduit Less Than size 103)
ES-1A	Signal, Lighting and Electrical Systems - Symbols and Abbreviations
ES-1B	Signal, Lighting and Electrical Systems - Symbols and Abbreviations
ES-2A	Signal, Lighting and Electrical Systems - Service Equipment
ES-2C	Signal, Lighting and Electrical Systems - Service Equipment Notes, Type III Series
ES-2E	Signal, Lighting and Electrical Systems - Service Equipment and Typical Wiring Diagram Type III-B Series
RSP ES-6A	Lighting Standards - Types 15, 21 and 22
RSP ES-6B	Lighting Standards - Types 15 AND 21, Barrier Rail Mounted Details
RSP ES-6C	Lighting Standards - Type 15 Slip Base Insert
ES-6E	Lighting Standards - Types 30 and 31
RSP ES-6F	Lighting Standards - Type 30 and 31 Base Plate Details
ES-8	Signal, Lighting and Electrical Systems - Pull Box Details
ES-9A	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-9B	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-9C	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-9D	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-9E	Signal, Lighting and Electrical Systems - Electrical Details, Structure Installations
ES-9F	Signal, Lighting and Electrical Systems - Flush Soffit Luminaire Modification Details, Structure Installations
ES-10	Signal, Lighting and Electrical Systems - Isolux Diagrams
ES-11	Signal, Lighting and Electrical Systems - Foundation Installations
ES-13A	Signal, Lighting and Electrical Systems - Splicing Details
ES-13B	Signal, Lighting and Electrical Systems - Wiring Details and Fuse Ratings



**DEPARTMENT OF TRANSPORTATION**

---

**NOTICE TO CONTRACTORS**

---

**CONTRACT NO. 07-053514**  
**07-LA-5,60-25.4/27.2,R0.7/R1.6**

Sealed proposals for the work shown on the plans entitled:

**STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROJECT PLANS FOR CONSTRUCTION ON STATE HIGHWAY IN LOS ANGELES COUNTY IN LOS ANGELES ON ROUTE 5 FROM 0.2 KM NORTH OF BOYLE AVENUE OVERCROSSING TO EUCLID AVENUE UNDERCROSSING SOUTH AND ON ROUTE 60 FROM ROUTE 60/5 SEPARATION TO EUCLID AVENUE UNDERCROSSING NORTH**

will be received at the Department of Transportation, 3347 Michelson Drive, Suite 100, Irvine, CA 92612-1692, until 2 o'clock p.m. on January 9, 2003, at which time they will be publicly opened and read in Room C - 1116 at the same address.

Proposal forms for this work are included in a separate book entitled:

**STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROPOSAL AND CONTRACT FOR CONSTRUCTION ON STATE HIGHWAY IN LOS ANGELES COUNTY IN LOS ANGELES ON ROUTE 5 FROM 0.2 KM NORTH OF BOYLE AVENUE OVERCROSSING TO EUCLID AVENUE UNDERCROSSING SOUTH AND ON ROUTE 60 FROM ROUTE 60/5 SEPARATION TO EUCLID AVENUE UNDERCROSSING NORTH**

General work description: Masonry block sound walls to be constructed.

This project has a goal of 19 percent disadvantaged business enterprise (DBE) participation. No prebid meeting is scheduled for this project.

**THIS PROJECT IS SUBJECT TO THE "BUY AMERICA" PROVISIONS OF THE SURFACE TRANSPORTATION ASSISTANCE ACT OF 1982 AS AMENDED BY THE INTERMODAL SURFACE TRANSPORTATION EFFICIENCY ACT OF 1991.**

Bids are required for the entire work described herein.

At the time this contract is awarded, the Contractor shall possess either a Class A license or a combination of Class C licenses which constitutes a majority of the work.

This contract is subject to state contract nondiscrimination and compliance requirements pursuant to Government Code, Section 12990.

Project plans, special provisions, and proposal forms for bidding this project can only be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, MS #26, Transportation Building, 1120 N Street, Sacramento, California 95814, FAX No. (916) 654-7028, Telephone No. (916) 654-4490. Use FAX orders to expedite orders for project plans, special provisions and proposal forms. FAX orders must include credit card charge number, card expiration date and authorizing signature. Project plans, special provisions, and proposal forms may be seen at the above Department of Transportation office and at the offices of the District Directors of Transportation at Irvine, Oakland, and the district in which the work is situated. Standard Specifications and Standard Plans are available through the State of California, Department of Transportation, Publications Unit, 1900 Royal Oaks Drive, Sacramento, CA 95815, Telephone No. (916) 445-3520.

Cross sections for this project are not available.

The successful bidder shall furnish a payment bond and a performance bond.

The Department of Transportation hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, disadvantaged business enterprises will be afforded full opportunity to submit bids in response to this invitation.

The U.S. Department of Transportation (DOT) provides a toll-free "hotline" service to report bid rigging activities. Bid rigging activities can be reported Mondays through Fridays, between 8:00 a.m. and 5:00 p.m., eastern time, Telephone No. 1-800-424-9071. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the "hotline" to report these activities. The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

Pursuant to Section 1773 of the Labor Code, the general prevailing wage rates in the county, or counties, in which the work is to be done have been determined by the Director of the California Department of Industrial Relations. These wages are set forth in the General Prevailing Wage Rates for this project, available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated, and available from the California Department of Industrial Relations' internet web site at: <http://www.dir.ca.gov>. The Federal minimum wage rates for this project as predetermined by the United States Secretary of Labor are available through the California Department of Transportation's Electronic Project Document Distribution Site on the internet at <http://hqidoc1.dot.ca.gov/>. Addenda to modify the Federal minimum wage rates, if necessary, will be issued to holders of "Proposal and Contract" books. Future effective general prevailing wage rates which have been predetermined and are on file with the California Department of Industrial Relations are referenced but not printed in the general prevailing wage rates.

If there is a difference between the minimum wage rates predetermined by the United States Secretary of Labor and the general prevailing wage rates determined by the Director of the California Department of Industrial Relations for similar classifications of labor, the Contractor and subcontractors shall pay not less than the higher wage rate. The Department will not accept lower State wage rates not specifically included in the Federal minimum wage determinations. This includes "helper" (or other classifications based on hours of experience) or any other classification not appearing in the Federal wage determinations. Where Federal wage determinations do not contain the State wage rate determination otherwise available for use by the Contractor and subcontractors, the Contractor and subcontractors shall pay not less than the Federal minimum wage rate which most closely approximates the duties of the employees in question.

DEPARTMENT OF TRANSPORTATION

Deputy Director Transportation Engineering

Dated December 2, 2002

ASF

**COPY OF ENGINEER'S ESTIMATE**  
**(NOT TO BE USED FOR BIDDING PURPOSES)**

**07-053514**

Item	Item Code	Item	Unit of Measure	Estimated Quantity
1	071322	TEMPORARY FENCE (TYPE CL-1.8)	M	620
2	049206	TEMPORARY SUPPORT, LOCATION A	LS	LUMP SUM
3	049207	TEMPORARY SUPPORT, LOCATION B	LS	LUMP SUM
4	074017	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM
5	074020	WATER POLLUTION CONTROL	LS	LUMP SUM
6 (S)	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
7 (S)	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
8 (S)	120120	TYPE III BARRICADE	EA	32
9 (S)	120151	TEMPORARY TRAFFIC STRIPE (TAPE)	M	2120
10 (S)	120165	CHANNELIZER (SURFACE MOUNTED)	EA	110
11	120300	TEMPORARY PAVEMENT MARKER	EA	530
12	129000	TEMPORARY RAILING (TYPE K)	M	1110
13 (S)	129100	TEMPORARY CRASH CUSHION MODULE	EA	72
14	030442	REMOVE CONCRETE MASONRY BLOCK WALL	M	26
15 (S)	150608	REMOVE CHAIN LINK FENCE	M	620
16 (S)	150662	REMOVE METAL BEAM GUARD RAILING	M	550
17 (S)	150704	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE	M	290
18 (S)	150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	M	1080
19 (S)	150722	REMOVE PAVEMENT MARKER	EA	520
20	150742	REMOVE ROADSIDE SIGN	EA	5

Item	Item Code	Item	Unit of Measure	Estimated Quantity
21	150806	REMOVE PIPE	M	79
22	150820	REMOVE INLET	EA	11
23	150829	REMOVE RETAINING WALL	M3	10
24	152440	ADJUST MANHOLE TO GRADE	EA	2
25	153214	REMOVE CONCRETE CURB	M	15
26	030443	REMOVE CONCRETE GUTTER	M	62
27 (S)	030444	REMOVE CONCRETE BARRIER (TYPE 1A)	M	4
28	153235	CLEAN BRIDGE DECK	M2	76
29	157561	BRIDGE REMOVAL (PORTION), LOCATION A	LS	LUMP SUM
30	157562	BRIDGE REMOVAL (PORTION), LOCATION B	LS	LUMP SUM
31	157563	BRIDGE REMOVAL (PORTION), LOCATION C	LS	LUMP SUM
32	157564	BRIDGE REMOVAL (PORTION), LOCATION D	LS	LUMP SUM
33	160101	CLEARING AND GRUBBING	LS	LUMP SUM
34	190101	ROADWAY EXCAVATION	M3	870
35	190105	ROADWAY EXCAVATION (TYPE Z-2) (AERIALY DEPOSITED LEAD)	M3	950
36	190110	LEAD COMPLIANCE PLAN	LS	LUMP SUM
37 (F)	192003	STRUCTURE EXCAVATION (BRIDGE)	M3	148
38	192037	STRUCTURE EXCAVATION (RETAINING WALL)	M3	200
39	193001	STRUCTURE BACKFILL	M3	52
40 (F)	193003	STRUCTURE BACKFILL (BRIDGE)	M3	33

Item	Item Code	Item	Unit of Measure	Estimated Quantity
41	193013	STRUCTURE BACKFILL (RETAINING WALL)	M3	160
42 (S)	200001	HIGHWAY PLANTING	LS	LUMP SUM
43 (S)	200002	ROADSIDE CLEARING	LS	LUMP SUM
44 (S)	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM
45 (S)	208000	IRRIGATION SYSTEM	LS	LUMP SUM
46 (S)	208910	EXTEND 250 MM CONDUIT	M	5
47 (S)	030445	NOZZLE LINE (20 MM)	M	80
48	260301	CLASS 3 AGGREGATE BASE	M3	150
49	390103	ASPHALT CONCRETE (TYPE B)	TONN	2390
50	394040	PLACE ASPHALT CONCRETE DIKE (TYPE A)	M	10
51 (S)	490655	400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	130
52 (S)	490657	600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	110
53 (S)	498024	400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (BARRIER)	M	1880
54 (F)	510053	STRUCTURAL CONCRETE, BRIDGE	M3	118
55 (F)	510072	STRUCTURAL CONCRETE, BARRIER SLAB	M3	113
56 (F)	510133	CLASS 2 CONCRETE (RETAINING WALL)	M3	40
57	510501	MINOR CONCRETE	M3	18
58 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	28
59	510800	PAVING NOTCH EXTENSION	M3	0.3
60	511106	DRILL AND BOND DOWEL	M	133

Item	Item Code	Item	Unit of Measure	Estimated Quantity
61	511109	DRILL AND BOND DOWEL (EPOXY CARTRIDGE)	EA	329
62 (F)	030446	SOUND WALL (RETAINING WALL) (MASONRY BLOCK)	M2	70
63 (F)	517961	SOUND WALL (BARRIER) (MASONRY BLOCK)	M2	2780
64 (F)	518002	SOUND WALL (MASONRY BLOCK)	M2	2525
65 (S-F)	520102	BAR REINFORCING STEEL (BRIDGE)	KG	36 000
66 (S-F)	520103	BAR REINFORCING STEEL (RETAINING WALL)	KG	2324
67 (S-F)	520110	BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE)	KG	4800
68 (S-F)	540101	ASPHALT MEMBRANE WATERPROOFING	M2	38
69 (F)	540102	TREAT BRIDGE DECK	M2	76
70	540109	FURNISH BRIDGE DECK TREATMENT MATERIAL (LOW ODOR)	L	31
71	568001	INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD)	EA	3
72	568007	INSTALL SIGN OVERLAY	EA	4
73	030447	METAL (WALL MOUNTED SIGN)	EA	2
74	650069	450 MM REINFORCED CONCRETE PIPE	M	46
75	650075	600 MM REINFORCED CONCRETE PIPE	M	20
76	721011	ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	M3	7
77	729010	ROCK SLOPE PROTECTION FABRIC	M2	35
78 (S-F)	750001	MISCELLANEOUS IRON AND STEEL	KG	1600
79 (S-F)	750501	MISCELLANEOUS METAL (BRIDGE)	KG	910
80 (S)	802589	1.5 M CHAIN LINK GATE (TYPE CL-1.8)	EA	2

Item	Item Code	Item	Unit of Measure	Estimated Quantity
81 (S)	832003	METAL BEAM GUARD RAILING (WOOD POST)	M	30
82	839565	TERMINAL SYSTEM (TYPE SRT)	EA	1
83	030448	CONCRETE BARRIER (TYPE 736 SV)	M	660
84	030449	CONCRETE BARRIER (TYPE 736A MODIFIED)	M	4
85 (F)	030450	CONCRETE BARRIER (TYPE 736 MODIFIED)	M	282
86 (S)	840561	100 MM THERMOPLASTIC TRAFFIC STRIPE	M	1430
87 (S)	840563	200 MM THERMOPLASTIC TRAFFIC STRIPE	M	60
88 (S)	840570	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M)	M	1390
89 (S)	850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	420
90 (S)	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	140
91 (S)	030451	LIGHTING AND SIGN ILLUMINATION (TEMPORARY)	LS	LUMP SUM
92 (S-F)	049208	COMMUNICATION CONDUIT (BRIDGE)	M	104
93 (S)	030454	COMMUNICATION SYSTEM ROUTING (MODIFY)	LS	LUMP SUM
94 (S)	861504	MODIFY LIGHTING AND SIGN ILLUMINATION	LS	LUMP SUM
95	999990	MOBILIZATION	LS	LUMP SUM

**STATE OF CALIFORNIA**  
**DEPARTMENT OF TRANSPORTATION**

---

**SPECIAL PROVISIONS**

**Annexed to Contract No. 07-053514**

**SECTION 1. SPECIFICATIONS AND PLANS**

The work embraced herein shall conform to the provisions in the Standard Specifications dated July 1999, and the Standard Plans dated July 1999, of the Department of Transportation insofar as the same may apply, and these special provisions.

In case of conflict between the Standard Specifications and these special provisions, the special provisions shall take precedence over and shall be used in lieu of the conflicting portions.

**AMENDMENTS TO JULY 1999 STANDARD  
SPECIFICATIONS**

**UPDATED JUNE 13, 2002**

Amendments to the Standard Specifications set forth in these special provisions shall be considered as part of the Standard Specifications for the purposes set forth in Section 5-1.04, "Coordination and Interpretation of Plans, Standard Specifications and Special Provisions," of the Standard Specifications. Whenever either the term "Standard Specifications is amended" or the term "Standard Specifications are amended" is used in the special provisions, the text or table following the term shall be considered an amendment to the Standard Specifications. In case of conflict between such amendments and the Standard Specifications, the amendments shall take precedence over and be used in lieu of the conflicting portions.

**SECTION 2: PROPOSAL REQUIREMENTS AND CONDITIONS**

Issue Date: June 6, 2002

Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," of the Standard Specifications is amended to read:

**2-1.03 Examination of Plans, Specifications, Contract, and Site of Work**

- The bidder shall examine carefully the site of the work contemplated, the plans and specifications, and the proposal and contract forms therefor. The submission of a bid shall be conclusive evidence that the bidder has investigated and is satisfied as to the general and local conditions to be encountered, as to the character, quality and scope of work to be performed, the quantities of materials to be furnished and as to the requirements of the proposal, plans, specifications and the contract.
- The submission of a bid shall also be conclusive evidence that the bidder is satisfied that the character, quality and quantity of surface and subsurface materials or obstacles to be encountered insofar as this information was reasonably ascertainable from an inspection of the site and the records of exploratory work done by the Department as shown in the bid documents, as well as from the plans and specifications made a part of the contract.
- Where the Department has made investigations of site conditions including subsurface conditions in areas where work is to be performed under the contract, or in other areas, some of which may constitute possible local material sources, bidders or contractors may, upon written request, inspect the records of the Department as to those investigations subject to and upon the conditions hereinafter set forth.

- Where there has been prior construction by the Department or other public agencies within the project limits, records of the prior construction that are currently in the possession of the Department and which have been used by, or are known to, the designers and administrators of the project will be made available for inspection by bidders or contractors, upon written request, subject to the conditions hereinafter set forth. The records may include, but are not limited to, as-built drawings, design calculations, foundation and site studies, project reports and other data assembled in connection with the investigation, design, construction and maintenance of the prior projects.
- Inspection of the records of investigations and project records may be made at the office of the district in which the work is situated, or in the case of records of investigations related to structure work, at the Transportation Laboratory in Sacramento, California.
- When a log of test borings or other record of geotechnical data obtained by the Department's investigation of surface and subsurface conditions is included with the contract plans, it is furnished for the bidders' or Contractor's information and its use shall be subject to the conditions and limitations set forth in this Section 2-1.03.
- In some instances, information considered by the Department to be of possible interest to bidders or contractors has been compiled as "Materials Information." The use of the "Materials Information" shall be subject to the conditions and limitations set forth in this Section 2-1.03 and Section 6-2, "Local Materials."
- When cross sections are not included with the plans, but are available, bidders or contractors may inspect the cross sections and obtain copies for their use, at their expense.
- When cross sections are included with the contract plans, it is expressly understood and agreed that the cross sections do not constitute part of the contract, do not necessarily represent actual site conditions or show location, character, dimensions and details of work to be performed, and are included in the plans only for the convenience of bidders and their use is subject to the conditions and limitations set forth in this Section 2-1.03.
- When contour maps were used in the design of the project, the bidders may inspect those maps, and if available, they may obtain copies for their use.
- The availability or use of information described in this Section 2-1.03 is not to be construed in any way as a waiver of the provisions of the first paragraph in this Section 2-1.03 and bidders and contractors are cautioned to make independent investigations and examinations as they deem necessary to be satisfied as to conditions to be encountered in the performance of the work and, with respect to possible local material sources, the quality and quantity of material available from the property and the type and extent of processing that may be required in order to produce material conforming to the requirements of the specifications.
- The Department assumes no responsibility for conclusions or interpretations made by a bidder or contractor based on the information or data made available by the Department. The Department does not assume responsibility for representation made by its officers or agents before the execution of the contract concerning surface or subsurface conditions, unless that representation is expressly stated in the contract.
- No conclusions or interpretations made by a bidder or contractor from the information and data made available by the Department will relieve a bidder or contractor from properly fulfilling the terms of the contract.

## **SECTION 5: CONTROL OF WORK**

Issue Date: December 31, 2001

Section 5-1.02A, "Trench Excavation Safety Plans," of the Standard Specifications is amended to read:

### **5-1.02A Excavation Safety Plans**

- The Construction Safety Orders of the Division of Occupational Safety and Health shall apply to all excavations. For all excavations 1.5 m or more in depth, the Contractor shall submit to the Engineer a detailed plan showing the design and details of the protective systems to be provided for worker protection from the hazard of caving ground during excavation. The detailed plan shall include any tabulated data and any design calculations used in the preparation of the plan. Excavation shall not begin until the detailed plan has been reviewed and approved by the Engineer.
- Detailed plans of protective systems for which the Construction Safety Orders require design by a registered professional engineer shall be prepared and signed by an engineer who is registered as a Civil Engineer in the State of California, and shall include the soil classification, soil properties, soil design calculations that demonstrate adequate stability of the protective system, and any other design calculations used in the preparation of the plan.
- No plan shall allow the use of a protective system less effective than that required by the Construction Safety Orders.
- If the detailed plan includes designs of protective systems developed only from the allowable configurations and slopes, or Appendices, contained in the Construction Safety Orders, the plan shall be submitted at least 5 days before the Contractor intends to begin excavation. If the detailed plan includes designs of protective systems developed from tabulated

data, or designs for which design by a registered professional engineer is required, the plan shall be submitted at least 3 weeks before the Contractor intends to begin excavation.

- Attention is directed to Section 7-1.01E, "Trench Safety."

### **SECTION 19: EARTHWORK**

Issue Date: December 31, 2001

The third paragraph of Section 19-1.02, "Preservation of Property," of the Standard Specifications is amended to read:

- In addition to the provisions in Sections 5-1.02, "Plans and Working Drawings," and 5-1.02A, "Excavation Safety Plans," detailed plans of the protective systems for excavations on or affecting railroad property will be reviewed for adequacy of protection provided for railroad facilities, property, and traffic. These plans shall be submitted at least 9 weeks before the Contractor intends to begin excavation requiring the protective systems. Approval by the Engineer of the detailed plans for the protective systems will be contingent upon the plans being satisfactory to the railroad company involved.

### **SECTION 42: GROOVE AND GRIND PAVEMENT**

Issue Date: December 31, 2001

The last sentence of the first subparagraph of the third paragraph in Section 42-2.02, "Construction," of the Standard Specifications is amended to read:

After grinding has been completed, the pavement shall conform to the straightedge and profile requirements specified in Section 40-1.10, "Final Finishing."

### **SECTION 49: PILING**

Issue Date: December 31, 2001

Section 49-1.05, "Driving Equipment," of the Standard Specifications is amended by adding the following paragraph after the seventh paragraph:

- The use of followers or underwater hammers for driving piles will be permitted if authorized in writing by the Engineer. When a follower or underwater hammer is used, its efficiency shall be verified by furnishing the first pile in each bent or footing sufficiently long and driving the pile without the use of a follower or underwater hammer.

The first and second paragraphs in Section 49-4.01, "Description," of the Standard Specifications are amended to read:

- Cast-in-place concrete piles shall consist of one of the following:

- A. Steel shells driven permanently to the required bearing value and penetration and filled with concrete.
- B. Steel casings installed permanently to the required penetration and filled with concrete.
- C. Drilled holes filled with concrete.
- D. Rock sockets filled with concrete.

- The drilling of holes shall conform to the provisions in these specifications. Concrete filling for cast-in-place concrete piles is designated by compressive strength and shall have a minimum 28-day compressive strength of 25 MPa. At the option of the Contractor, the combined aggregate grading for the concrete shall be either the 25-mm maximum grading, the 12.5-mm maximum grading, or the 9.5-mm maximum grading. Concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," and Section 51, "Concrete Structures." Reinforcement shall conform to the provisions in Section 52, "Reinforcement."

The fourth paragraph in Section 49-4.03, "Drilled Holes," of the Standard Specifications is amended to read:

- After placing reinforcement and prior to placing concrete in the drilled hole, if caving occurs or deteriorated foundation material accumulates on the bottom of the hole, the bottom of the drilled hole shall be cleaned. The Contractor shall verify that the bottom of the drilled hole is clean.

The third paragraph in Section 49-6.02, "Payment," of the Standard Specifications is amended to read:

- The contract price paid per meter for cast-in-drilled-hole concrete piling shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all work involved in drilling holes, disposing of material resulting from drilling holes, temporarily casing holes and removing water when necessary, furnishing and placing concrete and reinforcement, and constructing reinforced concrete extensions, complete in place, to the required penetration, as shown on the plans, as specified in these specifications and in the special provisions, and as directed by the Engineer.

## **SECTION 50: PRESTRESSING CONCRETE**

Issue Date: December 31, 2001

Section 50-1.02, "Drawings," of the Standard Specifications is amended by adding the following paragraph after the second paragraph:

- Each working drawing submittal shall consist of plans for a single bridge or portion thereof. For multi-frame bridges, each frame shall require a separate working drawing submittal.

Section 50-1.05, "Prestressing Steel," of the Standard Specifications is amended to read:

- Prestressing steel shall be high-tensile wire conforming to the requirements in ASTM Designation: A 421, including Supplement I; high-tensile seven-wire strand conforming to the requirements in ASTM Designation: A 416; or uncoated high-strength steel bars conforming to the requirements in ASTM Designation: A 722, including all supplementary requirements. The maximum mass requirement of ASTM Designation: A 722 will not apply.

- In addition to the requirements of ASTM Designation: A 722, for deformed bars, the reduction of area shall be determined from a bar from which the deformations have been removed. The bar shall be machined no more than necessary to remove the deformations over a length of 300 mm, and reduction will be based on the area of the machined portion.

- In addition to the requirements specified herein, epoxy-coated seven-wire prestressing steel strand shall be grit impregnated and filled in conformance with the requirements in ASTM Designation: A 882/A 882M, including Supplement I, and the following:

- A. The coating material shall be on the Department's list of approved coating materials for epoxy-coated strand, available from the Transportation Laboratory.
- B. The film thickness of the coating after curing shall be 381  $\mu\text{m}$  to 1143  $\mu\text{m}$ .
- C. Prior to coating the strand, the Contractor shall furnish to the Transportation Laboratory a representative 230-g sample from each batch of epoxy coating material to be used. Each sample shall be packaged in an airtight container identified with the manufacturer's name and batch number.
- D. Prior to use of the epoxy-coated strand in the work, written certifications referenced in ASTM Designation: A 882/A 882M, including a representative load-elongation curve for each size and grade of strand to be used and a copy of the quality control tests performed by the manufacturer, shall be furnished to the Engineer.
- E. In addition to the requirements in Section 50-1.10, "Samples for Testing," four 1.5-m long samples of coated strand and one 1.5-m long sample of uncoated strand of each size and reel shall be furnished to the Engineer for testing. These samples, as selected by the Engineer, shall be representative of the material to be used in the work.
- F. Epoxy-coated strand shall be cut using an abrasive saw.
- G. All visible damage to coatings caused by shipping and handling, or during installation, including cut ends, shall be repaired in conformance with the requirements in ASTM Designation: A 882/A 882M. The patching material shall be furnished by the manufacturer of the epoxy powder and shall be applied in conformance with the manufacturer's written recommendations. The patching material shall be compatible with the original epoxy coating material and shall be inert in concrete.

- All bars in any individual member shall be of the same grade, unless otherwise permitted by the Engineer.

- When bars are to be extended by the use of couplers, the assembled units shall have a tensile strength of not less than the manufacturer's minimum guaranteed ultimate tensile strength of the bars. Failure of any one sample to meet this requirement will be cause for rejection of the heat of bars and lot of couplers. The location of couplers in the member shall be subject to approval by the Engineer.
- Wires shall be straightened if necessary to produce equal stress in all wires or wire groups or parallel lay cables that are to be stressed simultaneously or when necessary to ensure proper positioning in the ducts.
- Where wires are to be button-headed, the buttons shall be cold formed symmetrically about the axes of the wires. The buttons shall develop the minimum guaranteed ultimate tensile strength of the wire. No cold forming process shall be used that causes indentations in the wire. Buttonheads shall not contain wide open splits, more than 2 splits per head, or splits not parallel with the axis of the wire.
- Prestressing steel shall be protected against physical damage and rust or other results of corrosion at all times from manufacture to grouting or encasing in concrete. Prestressing steel that has sustained physical damage at any time shall be rejected. The development of visible rust or other results of corrosion shall be cause for rejection, when ordered by the Engineer.
- Epoxy-coated prestressing steel strand shall be covered with an opaque polyethylene sheeting or other suitable protective material to protect the strand from exposure to sunlight, salt spray, and weather. For stacked coils, the protective covering shall be draped around the perimeter of the stack. The covering shall be adequately secured; however, it should allow for air circulation around the strand to prevent condensation under the covering. Epoxy-coated strand shall not be stored within 300 m of ocean or tidal water for more than 2 months.
- Prestressing steel shall be packaged in containers or shipping forms for the protection of the steel against physical damage and corrosion during shipping and storage. Except for epoxy-coated strand, a corrosion inhibitor which prevents rust or other results of corrosion, shall be placed in the package or form, or shall be incorporated in a corrosion inhibitor carrier type packaging material, or when permitted by the Engineer, may be applied directly to the steel. The corrosion inhibitor shall have no deleterious effect on the steel or concrete or bond strength of steel to concrete. Packaging or forms damaged from any cause shall be immediately replaced or restored to original condition.
- The shipping package or form shall be clearly marked with a statement that the package contains high-strength prestressing steel, and the type of corrosion inhibitor used, including the date packaged.
- Prestressing steel for post-tensioning which is installed in members prior to placing and curing of the concrete, and which is not epoxy-coated, shall be continuously protected against rust or other results of corrosion, until grouted, by means of a corrosion inhibitor placed in the ducts or applied to the steel in the duct. The corrosion inhibitor shall conform to the provisions specified herein.
- When steam curing is used, prestressing steel for post-tensioning shall not be installed until the steam curing is completed.
- Water used for flushing ducts shall contain either quick lime (calcium oxide) or slaked lime (calcium hydroxide) in the amount of 0.01-kg/L. Compressed air used to blow out ducts shall be oil free.
- When prestressing steel for post-tensioning is installed in the ducts after completion of concrete curing, and if stressing and grouting are completed within 10 days after the installation of the prestressing steel, rust which may form during those 10 days will not be cause for rejection of the steel. Prestressing steel installed, tensioned, and grouted in this manner, all within 10 days, will not require the use of a corrosion inhibitor in the duct following installation of the prestressing steel. Prestressing steel installed as above but not grouted within 10 days shall be subject to all the requirements in this section pertaining to corrosion protection and rejection because of rust. The requirements in this section pertaining to tensioning and grouting within 10 days shall not apply to epoxy-coated prestressing steel strand.
- Any time prestressing steel for pretensioning is placed in the stressing bed and is exposed to the elements for more than 36 hours prior to encasement in concrete, adequate measures shall be taken by the Contractor, as approved by the Engineer, to protect the steel from contamination or corrosion.
- After final fabrication of the seven-wire prestressing steel strand, no electric welding of any form shall be performed on the prestressing steel. Whenever electric welding is performed on or near members containing prestressing steel, the welding ground shall be attached directly to the steel being welded.
- Pretensioned prestressing steel shall be cut off flush with the end of the member. For epoxy-coated prestressing steel, only abrasive saws shall be used to cut the steel. The exposed ends of the prestressing steel and a 25-mm strip of adjoining concrete shall be cleaned and painted. Cleaning shall be by wire brushing or abrasive blast cleaning to remove all dirt and residue on the metal or concrete surfaces. Immediately after cleaning, the surfaces shall be covered with one application of unthinned zinc-rich primer (organic vehicle type) conforming to the provisions in Section 91, "Paint," except that 2 applications shall be applied to surfaces which will not be covered by concrete or mortar. Aerosol cans shall not be used. The paint shall be thoroughly mixed at the time of application and shall be worked into any voids in the prestressing tendons.

The thirteenth paragraph in Section 50-1.08, "Prestressing," of the Standard Specifications is amended to read:

Contract No. 07-053514

- Prestressing steel in pretensioned members shall not be cut or released until the concrete in the member has attained a compressive strength of not less than the value shown on the plans or 28 MPa, whichever is greater. In addition to these concrete strength requirements, when epoxy-coated prestressing steel strand is used, the steel shall not be cut or released until the temperature of the concrete surrounding the strand is less than 65°C, and falling.

The fifth paragraph in Section 50-1.10, "Samples for Testing," of the Standard Specifications is amended to read:

- The following samples of materials and tendons, selected by the Engineer from the prestressing steel at the plant or jobsite, shall be furnished by the Contractor to the Engineer well in advance of anticipated use:  
For wire or bars, one 2-m long sample and for strand, one 1.5-m long sample, of each size shall be furnished for each heat or reel.  
For epoxy-coated strand, one 1.5-m long sample of uncoated strand of each size shall be furnished for each reel.  
If the prestressing tendon is a bar, one 2-m long sample shall be furnished and in addition, if couplers are to be used with the bar, two 1.25-m long samples of bar, equipped with one coupler and fabricated to fit the coupler, shall be furnished.

The second paragraph in Section 50-1.11, "Payment," of the Standard Specifications is amended to read:

- The contract lump sum prices paid for prestressing cast-in-place concrete of the types listed in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all work involved in furnishing, placing, and tensioning the prestressing steel in cast-in-place concrete structures, complete in place, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

## **SECTION 51: CONCRETE STRUCTURES**

Issue Date: December 31, 2001

The first and second paragraph in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications are amended to read:

- The Contractor shall submit to the Engineer working drawings and design calculations for falsework proposed for use at bridges. For bridges where the height of any portion of the falsework, as measured from the ground line to the soffit of the superstructure, exceeds 4.25 m; or where any individual falsework clear span length exceeds 4.85 m; or where provision for vehicular, pedestrian, or railroad traffic through the falsework is made; the drawings shall be signed by an engineer who is registered as a Civil Engineer in the State of California. Six sets of the working drawings and 2 copies of the design calculations shall be furnished. Additional working drawings and design calculations shall be submitted to the Engineer when specified in "Railroad Relations and Insurance" of the special provisions.
  - The falsework drawings shall include details of the falsework erection and removal operations showing the methods and sequences of erection and removal and the equipment to be used. The details of the falsework erection and removal operations shall demonstrate the stability of all or any portions of the falsework during all stages of the erection and removal operations.

The seventh paragraph in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications is amended to read:

- In the event that several falsework plans are submitted simultaneously, or an additional plan is submitted for review before the review of a previously submitted plan has been completed, the Contractor shall designate the sequence in which the plans are to be reviewed. In such event, the time to be provided for the review of any plan in the sequence shall be not less than the review time specified above for that plan, plus 2 weeks for each plan of higher priority which is still under review. A falsework plan submittal shall consist of plans for a single bridge or portion thereof. For multi-frame bridges, each frame shall require a separate falsework plan submittal.

Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications is amended by adding the following paragraphs:

- If structural composite lumber is proposed for use, the falsework drawings shall clearly identify the structural composite lumber members by grade (E value), species, and type. The Contractor shall provide technical data from the manufacturer showing the tabulated working stress values of the composite lumber. The Contractor shall furnish a certificate of compliance as specified in Section 6-1.07, "Certificates of Compliance," for each delivery of structural composite lumber to the project site.

- For falsework piles with a calculated loading capacity greater than 900 kN, the falsework piles shall be designed by an engineer who is registered as either a Civil Engineer or a Geotechnical Engineer in the State of California, and the calculations shall be submitted to the Engineer.

The first paragraph in Section 51-1.06A(1), "Design Loads," of the Standard Specifications is amended to read:

- The design load for falsework shall consist of the sum of dead and live vertical loads, and an assumed horizontal load. The minimum total design load for any falsework, including members that support walkways, shall be not less than 4800 N/m<sup>2</sup> for the combined live and dead load regardless of slab thickness.

The eighth paragraph in Section 51-1.06A(1), "Design Loads," of the Standard Specifications is amended to read:

- In addition to the minimum requirements specified in this Section 51-1.06A, falsework for box girder structures with internal falsework bracing systems using flexible members capable of withstanding tensile forces only, shall be designed to include the vertical effects caused by the elongation of the flexible member and the design horizontal load combined with the dead and live loads imposed by concrete placement for the girder stems and connected bottom slabs. Falsework comprised of individual steel towers with bracing systems using flexible members capable of withstanding tensile forces only to resist overturning, shall be exempt from these additional requirements.

The third paragraph in Section 51-1.06B, "Falsework Construction," of the Standard Specifications is amended to read:

- When falsework is supported on piles, the piles shall be driven and the actual bearing value assessed in conformance with the provisions in Section 49, "Piling."

Section 51-1.06B, "Falsework Construction," of the Standard Specifications is amended by adding the following paragraphs:

- For falsework piles with a calculated loading capacity greater than 900 kN, the Contractor shall conduct dynamic monitoring of pile driving and conduct penetration and bearing analyses based on a wave equation analysis. These analyses shall be signed by an engineer who is registered as a Civil Engineer in the State of California and submitted to the Engineer prior to completion of falsework erection.

- Prior to the placement of falsework members above the stringers, the final bracing system for the falsework shall be installed.

Section 51-1.06C, "Removing Falsework," of the Standard Specifications is amended by adding the following paragraph:

- The falsework removal operation shall be conducted in such a manner that any portion of the falsework not yet removed remains in a stable condition at all times.

The sixth paragraph in Section 51-1.09, "Placing Concrete," of the Standard Specifications is amended to read:

- Vibrators used to consolidate concrete containing epoxy-coated bar reinforcement or epoxy-coated prestressing steel shall have a resilient covering to prevent damage to the epoxy-coating on the reinforcement or prestressing steel.

The table in the ninth paragraph of Section 51-1.12H(1), "Plain and Fabric Reinforced Elastomeric Bearing Pads," of the Standard Specifications is amended to read:

Tensile strength, percent	-15
Elongation at break, percent	-40; but not less than 300% total elongation of the material
Hardness, points	+10

Section 51-1.17, "Finishing Bridge Decks," of the Standard Specifications is amended by deleting the thirteenth and fourteenth paragraphs.

The fourteenth paragraph in Section 51-1.23, "Payment," of the Standard Specifications is amended by deleting "and injecting epoxy in cracks".

## SECTION 52: REINFORCEMENT

Issue Date: December 31, 2001

The third paragraph in Section 52-1.04, "Inspection," of the Standard Specifications is amended to read:

- A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall also be furnished for each shipment of epoxy-coated bar reinforcement or wire reinforcement certifying that the coated reinforcement conforms to the requirements in ASTM Designation: A 775/A 775M or A 884/A 884M, respectively, and the provisions in Section 52-1.02B, "Epoxy-coated Reinforcement." The Certificate of Compliance shall include all of the certifications specified in ASTM Designation: A 775/A 775M or A 884/A 884M respectively, and a statement that the coating material has been prequalified by acceptance testing performed by the Valley Forge Laboratories, Inc., Devon, Pennsylvania.

The third paragraph in Section 52-1.08C, "Mechanical Butt Splices," of the Standard Specifications is amended to read:

- The total slip of the reinforcing bars within the splice sleeve after loading in tension to 200 MPa and relaxing to 20 MPa shall not exceed the values listed in the following table. The slip shall be measured between gage points that are clear of the splice sleeve.

Reinforcing Bar Number	Total Slip ( $\mu\text{m}$ )
13	250
16	250
19	250
22	350
25	350
29	350
32	450
36	450
43	600
57	750

The first paragraph in Section 52-1.08C(5), "Sleeve-Lockshear Bolt Mechanical Butt Splices," of the Standard Specifications is amended to read:

- The sleeve-lockshear bolt type of mechanical butt splices shall consist of a seamless steel sleeve, center hole with centering pin, and bolts that are tightened until the bolt heads shear off with the bolt ends left embedded in the reinforcing bars. The seamless steel sleeve shall be either formed into a V configuration or shall have 2 serrated steel strips welded to the inside of the sleeve.

Section 52-1.08F, "Nondestructive Splice Tests," of the Standard Specifications is amended by deleting the seventh paragraph.

## SECTION 55: STEEL STRUCTURES

Issue Date: December 31, 2001

Section 55-3.14, "Bolted Connections," of the Standard Specifications is amended by adding the following after the ninth paragraph:

- If a torque multiplier is used in conjunction with a calibrated wrench as a method for tightening fastener assemblies to the required tension, both the multiplier and the wrench shall be calibrated together as a system. The same length input and output sockets and extensions that will be used in the work shall also be included in the calibration of the system. The manufacturer's torque multiplication ratio shall be adjusted during calibration of the system, such that when this adjusted ratio is multiplied by the actual input calibrated wrench reading, the product is a calculated output torque that is within 2 percent of the true output torque. When this system is used in the work to perform any installation tension testing, rotational capacity testing, fastener tightening, or tension verification, it shall be used, intact as calibrated.

The sixth paragraph of Section 55-4.02, "Payment," of the Standard Specifications is amended to read:

- If a portion or all of the structural steel is fabricated more than 480 air line kilometers from both Sacramento and Los Angeles, additional shop inspection expenses will be sustained by the State. Whereas it is and will be impracticable and extremely difficult to ascertain and determine the actual increase in these expenses, it is agreed that payment to the Contractor for furnishing the structural steel from each fabrication site located more than 480 air line kilometers from both Sacramento and Los Angeles will be reduced \$5000 or by an amount computed at \$0.044 per kilogram of structural steel fabricated, whichever is greater, or in the case of each fabrication site located more than 4800 air line kilometers from both Sacramento and Los Angeles, payment will be reduced \$8000 or by \$0.079 per kilogram of structural steel fabricated, whichever is greater.

## **SECTION 56: SIGNS**

Issue Date: December 31, 2001

Section 56-1.01, "Description," of the Standard Specifications is amended by deleting the third paragraph.

The sixth through the thirteenth paragraphs in Section 56-1.03, "Fabrication," of the Standard Specifications are amended to read:

- High-strength bolted connections, where shown on the plans, shall conform to the provisions in Section 55-3.14, "Bolted Connections," except that only fastener assemblies consisting of a high-strength bolt, nut, hardened washer, and direct tension indicator shall be used.
  - High-strength fastener assemblies, and any other bolts, nuts, and washers attached to sign structures shall be zinc-coated by the mechanical deposition process.
  - An alternating snugging and tensioning pattern for anchor bolts and high-strength bolted splices shall be used. Once tensioned, high-strength fastener components and direct tension indicators shall not be reused.
  - For bolt diameters less than 10 mm, the diameter of the bolt hole shall be not more than 0.80-mm larger than the nominal bolt diameter. For bolt diameters greater than or equal to 10 mm, the diameter of the bolt hole shall be not more than 1.6 mm larger than the nominal bolt diameter.
  - Sign structures shall be fabricated into the largest practical sections prior to galvanizing.
  - Ribbed sheet metal panels for box beam closed truss sign structures shall be fastened to the truss members by cap screws or bolts as shown on the plans, or by 4.76 mm stainless steel blind rivets conforming to Industrial Fasteners Institute, Standard IFI-114, Grade 51. The outside diameter of the large flange rivet head shall be not less than 15.88 mm in diameter. Web splices in ribbed sheet metal panels may be made with similar type blind rivets of a size suitable for the thickness of material being connected.
    - Spalling or chipping of concrete structures shall be repaired by the Contractor at the Contractor's expense.
    - Overhead sign supports shall have an aluminum identification plate permanently attached near the base, adjacent to the traffic side on one of the vertical posts, using either stainless steel rivets or stainless steel screws. As a minimum, the information on the plate shall include the name of the manufacturer, the date of manufacture and the contract number.

## **SECTION 59: PAINTING**

Issue Date: December 31, 2001

Contract No. 07-053514

Section 59-2.01, "General," of the Standard Specifications is amended by adding the following paragraphs after the first paragraph:

- Unless otherwise specified, no painting Contractors or subcontractors will be permitted to commence work without having the following current "SSPC: The Society for Protective Coatings" (formerly the Steel Structures Painting Council) certifications in good standing:
  - A. For cleaning and painting structural steel in the field, certification in conformance with the requirements in Qualification Procedure No. 1, "Standard Procedure For Evaluating Painting Contractors (Field Application to Complex Industrial Structures)" (SSPC-QP 1).
  - B. For removing paint from structural steel, certification in conformance with the requirements in Qualification Procedure No. 2, "Standard Procedure For Evaluating Painting Contractors (Field Removal of Hazardous Coatings from Complex Structures)" (SSPC-QP 2).
  - C. For cleaning and painting structural steel in a permanent painting facility, certification in conformance with the requirements in Qualification Procedure No. 3, "Standard Procedure For Evaluating Qualifications of Shop Painting Applicators" (SSPC-QP 3). The AISC's Sophisticated Paint Endorsement (SPE) quality program will be considered equivalent to SSPC-QP 3.

The third paragraph of Section 59-2.03, "Blast Cleaning," of the Standard Specifications is amended to read:

- Exposed steel or other metal surfaces to be blast cleaned shall be cleaned in conformance with the requirements in Surface Preparation Specification No. 6, "Commercial Blast Cleaning," of the "SSPC: The Society for Protective Coatings." Blast cleaning shall leave all surfaces with a dense, uniform, angular anchor pattern of not less than 35  $\mu\text{m}$  as measured in conformance with the requirements in ASTM Designation: D 4417.

The first paragraph of Section 59-2.06, "Hand Cleaning," of the Standard Specifications is amended to read:

- Dirt, loose rust and mill scale, or paint which is not firmly bonded to the surfaces shall be removed in conformance with the requirements in Surface Preparation Specification No. 2, "Hand Tool Cleaning," of the "SSPC: The Society for Protective Coatings." Edges of old remaining paint shall be feathered.

The fourth paragraph of Section 59-2.12, "Painting," of the Standard Specifications is amended to read:

- The dry film thickness of the paint will be measured in place with a calibrated Type 2 magnetic film thickness gage in conformance with the requirements of specification SSPC-PA2 of the "SSPC: The Society for Protective Coatings."

## **SECTION 75: MISCELLANEOUS METAL**

Issue Date: December 31, 2001

The table in the tenth paragraph of Section 75-1.02, "Miscellaneous Iron and Steel," of the Standard Specifications is amended to read:

Material	Specification
Steel bars, plates and shapes	ASTM Designation: A 36/A 36M or A 575, A 576 (AISI or M Grades 1016 through 1030 except Grade 1017)
Steel fastener components for general applications:	
Bolts and studs	ASTM Designation: A 307
Headed anchor bolts	ASTM Designation: A 307, Grade B, including S1 supplementary requirements
Nonheaded anchor bolts	ASTM Designation: A 307, Grade C, including S1 supplementary requirements and S1.6 of AASHTO Designation: M 314 supplementary requirements or AASHTO Designation: M 314, Grade 36 or 55, including S1 supplementary requirements
High-strength bolts and studs, threaded rods, and nonheaded anchor bolts	ASTM Designation: A 449, Type 1
Nuts	ASTM Designation: A 563, including Appendix X1*
Washers	ASTM Designation: F 844
Components of high-strength steel fastener assemblies for use in structural steel joints:	
Bolts	ASTM Designation: A 325, Type 1
Tension control bolts	ASTM Designation: F 1852, Type 1
Nuts	ASTM Designation: A 563, including Appendix X1*
Hardened washers	ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements
Direct tension indicators	ASTM Designation: F 959, Type 325, zinc-coated
Stainless steel fasteners (Alloys 304 & 316) for general applications:	
Bolts, screws, studs, threaded rods, and nonheaded anchor bolts	ASTM Designation: F 593 or F 738M
Nuts	ASTM Designation: F 594 or F 836M
Washers	ASTM Designation: A 240/A 240M and ANSI B 18.22M
Carbon-steel castings	ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1
Malleable iron castings	ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010
Gray iron castings	ASTM Designation: A 48, Class 30B
Ductile iron castings	ASTM Designation: A 536, Grade 65-45-12
Cast iron pipe	Commercial quality
Steel pipe	Commercial quality, welded or extruded
Other parts for general applications	Commercial quality

\* Zinc-coated nuts that will be tightened beyond snug or wrench tight shall be furnished with a dyed dry lubricant conforming to Supplementary Requirement S2 in ASTM Designation: A 563.

The table in the eighteenth paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

Stud Diameter (millimeters)	Sustained Tension Test Load (kilonewtons)
29.01-33.00	137.9
23.01-29.00	79.6
21.01-23.00	64.1
* 18.01-21.00	22.2
15.01-18.00	18.2
12.01-15.00	14.2
9.01-12.00	9.34
6.00-9.00	4.23

\* Maximum stud diameter permitted for mechanical expansion anchors.

The table in the nineteenth paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

Stud Diameter (millimeters)	Ultimate Tensile Load (kilonewtons)
30.01-33.00	112.1
27.01-30.00	88.1
23.01-27.00	71.2
20.01-23.00	51.6
16.01-20.00	32.0
14.01-16.00	29.4
12.00-14.00	18.7

The table in the twenty-second paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

Installation Torque Values, (newton meters)

Stud Diameter (millimeters)	Shell Type Mechanical Expansion Anchors	Integral Stud Type Mechanical Expansion Anchors	Resin Capsule Anchors and Cast-in-Place Inserts
29.01-33.00	—	—	540
23.01-29.00	—	—	315
21.01-23.00	—	—	235
18.01-21.00	110	235	200
15.01-18.00	45	120	100
12.01-15.00	30	65	40
9.01-12.00	15	35	24
6.00-9.00	5	10	—

**SECTION 83: RAILINGS AND BARRIERS**

Issue Date: June 13, 2002

The ninth paragraph in Section 83-1.02B, "Metal Beam Guard Railing," of the Standard Specifications is amended to read:

- The grades and species of wood posts and blocks shall be No. 1 timbers (also known as No. 1 structural) Douglas fir or No. 1 timbers Southern yellow pine. Wood posts and blocks shall be graded in conformance with the provisions in Section 57-2, "Structural Timber," of the Standard Specifications, except allowances for shrinkage after mill cutting shall in no case exceed 5 percent of the American Lumber Standards minimum sizes, at the time of installation.

The eleventh paragraph in Section 83-1.02B, "Metal Beam Guard Railing," of the Standard Specifications is amended to read:

- Wood posts and blocks shall be pressure treated after fabrication in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," of the Standard Specifications with creosote, creosote coal tar solution, creosote petroleum solution (50-50), pentachlorophenol in hydrocarbon solvent, copper naphthenate, ammoniacal copper arsenate, or ammoniacal copper zinc arsenate. In addition to the preservatives listed above, Southern yellow pine may also be pressure treated with chromated copper arsenate. When other than one of the creosote processes is used, blocks shall have a minimum retention of 6.4 Kg/m<sup>3</sup>, and need not be incised.

## **SECTION 86: SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS**

Issue Date: February 28, 2002

The seventh paragraph of Section 86-2.03, "Foundations," of the Standard Specifications is amended to read:

- Forms shall be true to line and grade. Tops of foundations for posts and standards, except special foundations, shall be finished to curb or sidewalk grade or as directed by the Engineer. Forms shall be rigid and securely braced in place. Conduit ends and anchor bolts shall be placed in proper position and to proper height, and anchor bolts shall be held in place by means of rigid templates. Anchor bolts shall not be installed more than 1:40 from vertical.

The twelfth paragraph of Section 86-2.03, "Foundations," of the Standard Specifications is amended to read:

- Plumbing of the standards shall be accomplished by adjusting the leveling nuts before placing the mortar or before the foundation is finished to final grade. Shims, or other similar devices shall not be used for plumbing or raking of posts, standards or pedestals. After final adjustments of both top nuts and leveling nuts on anchorage assemblies have been made, firm contact shall exist between all bearing surfaces of the anchor bolt nuts, washers, and the base plate.

Section 86-8.01, "Payment," of the Standard Specifications is amended to read by adding the following paragraph after the first paragraph:

- If a portion or all of the traffic signal and lighting standards, pursuant to Standard Specification Section 86, "Signals, Lighting and Electrical Systems," are fabricated more than 480 air line kilometers from both-Sacramento and Los Angeles, additional shop inspection expenses will be sustained by the State. Whereas it is and will be impracticable and extremely difficult to ascertain and determine the actual increase in such expenses, it is agreed that payment to the Contractor for furnishing such items from each fabrication site located more than 480 air line kilometers from both Sacramento and Los Angeles will be reduced \$5000; in addition, in the case where a fabrication site is located more than 4800 air line kilometers from both Sacramento and Los Angeles, payment will be reduced an additional \$3000 per each fabrication site (\$8000 total per site).

## **SECTION 88: ENGINEERING FABRIC**

Issue Date: January 15, 2002

Section 88-1.02, "Pavement Reinforcing Fabric," of the Standard Specifications is amended to read:

- Pavement reinforcing fabric shall be 100 percent polypropylene staple fiber fabric material, needle-punched, thermally bonded on one side, and conform to the following:

Specification	Requirement
Weight, grams per square meter ASTM Designation: D 5261	140
Grab tensile strength (25-mm grip), kilonewtons, min. in each direction ASTM Designation: D 4632	0.45
Elongation at break, percent min. ASTM Designation: D 4632	50
Asphalt retention by fabric, grams per square meter. (Residual Minimum) ASTM Designation: D 6140	900

Note: Weight, grab, elongation and asphalt retention are based on Minimum Average Roll Value (MARV)

## **SECTION 90: PORTLAND CEMENT CONCRETE**

Issue Date: March 12, 2002

Section 90, "Portland Cement Concrete," of the Standard Specifications is amended to read:

## **SECTION 90: PORTLAND CEMENT CONCRETE**

### **90-1 GENERAL**

#### **90-1.01 DESCRIPTION**

- Portland cement concrete shall be composed of cementitious material, fine aggregate, coarse aggregate, admixtures if used, and water, proportioned and mixed as specified in these specifications.
- The Contractor shall determine the mix proportions for all concrete except pavement concrete. The Engineer will determine the mix proportions for pavement concrete. Concrete for which the mix proportions are determined either by the Contractor or the Engineer shall conform to the requirements of this Section 90.
- Unless otherwise specified, cementitious material shall be a combination of cement and mineral admixture. Cementitious material shall be either:
  1. "Type IP (MS) Modified" cement; or
  2. A combination of "Type II Modified" portland cement and mineral admixture; or
  3. A combination of Type V portland cement and mineral admixture.
- Type III portland cement shall be used only as allowed in the special provisions or with the approval of the Engineer.
  - Class 1 concrete shall contain not less than 400 kg of cementitious material per cubic meter.
  - Class 2 concrete shall contain not less than 350 kg of cementitious material per cubic meter.
  - Class 3 concrete shall contain not less than 300 kg of cementitious material per cubic meter.
  - Class 4 concrete shall contain not less than 250 kg of cementitious material per cubic meter.
  - Minor concrete shall contain not less than 325 kg of cementitious material per cubic meter unless otherwise specified in these specifications or the special provisions.
  - Unless otherwise designated on the plans or specified in these specifications or the special provisions, the amount of cementitious material used per cubic meter of concrete in structures or portions of structures shall conform to the following:

Use	Cementitious Material Content (kg/m <sup>3</sup> )
Concrete designated by compressive strength:	
Deck slabs and slab spans of bridges	400 min., 475 max.
Roof sections of exposed top box culverts	400 min., 475 max.
Other portions of structures	350 min., 475 max.
Concrete not designated by compressive strength:	
Deck slabs and slab spans of bridges	400 min.
Roof sections of exposed top box culverts	400 min.
Prestressed members	400 min.
Seal courses	400 min.
Other portions of structures	350 min.
Concrete for precast members	350 min., 550 max.

- Whenever the 28-day compressive strength shown on the plans is greater than 25 MPa, the concrete shall be designated by compressive strength. If the plans show a 28-day compressive strength that is 28 MPa or greater, an additional 14 days will be allowed to obtain the specified strength. The 28-day compressive strengths shown on the plans that are 25 MPa or less are shown for design information only and are not a requirement for acceptance of the concrete.
- Concrete designated by compressive strength shall be proportioned such that the concrete will attain the strength shown on the plans or specified in the special provisions.
- Before using concrete for which the mix proportions have been determined by the Contractor, or in advance of revising those mix proportions, the Contractor shall submit in writing to the Engineer a copy of the mix design.
- Compliance with cementitious material content requirements will be verified in conformance with procedures described in California Test 518 for cement content. For testing purposes, mineral admixture shall be considered to be cement. Batch proportions shall be adjusted as necessary to produce concrete having the specified cementitious material content.
- If any concrete has a cementitious material, portland cement, or mineral admixture content that is less than the minimum required, the concrete shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place and the Contractor shall pay to the State \$0.55 for each kilogram of cementitious material, portland cement, or mineral admixture that is less than the minimum required. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract. The deductions will not be made unless the difference between the contents required and those actually provided exceeds the batching tolerances permitted by Section 90-5, "Proportioning." No deductions will be made based on the results of California Test 518.
- The requirements of the preceding paragraph shall not apply to minor concrete or commercial quality concrete.

## 90-2 MATERIALS

### 90-2.01 CEMENT

- Unless otherwise specified, cement shall be either "Type IP (MS) Modified" cement, "Type II Modified" portland cement or Type V portland cement.
- "Type IP (MS) Modified" cement shall conform to the requirements for Type IP (MS) cement in ASTM Designation: C 595, and shall be comprised of an intimate and uniform blend of Type II cement and not more than 35 percent by mass of mineral admixture. The type and minimum amount of mineral admixture used in the manufacture of "Type IP (MS) Modified" cement shall be in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures."
- "Type II Modified" portland cement shall conform to the requirements for Type II portland cement in ASTM Designation: C 150.
- In addition, "Type IP (MS) Modified" cement and "Type II Modified" portland cement shall conform to the following requirements:
  - A. The cement shall not contain more than 0.60 percent by mass of alkalis, calculated as the percentage of Na<sub>2</sub>O plus 0.658 times the percentage of K<sub>2</sub>O, when determined by either direct intensity flame photometry or by the atomic absorption method. The instrument and procedure used shall be qualified as to precision and accuracy in conformance with the requirements in ASTM Designation: C 114;
  - B. The autoclave expansion shall not exceed 0.50 percent; and
  - C. Mortar, containing the cement to be used and Ottawa sand, when tested in conformance with California Test 527, shall not expand in water more than 0.010 percent and shall not contract in air more than 0.048 percent, except that

when cement is to be used for precast prestressed concrete piling, precast prestressed concrete members, or steam cured concrete products, the mortar shall not contract in air more than 0.053 percent.

- Type III and Type V portland cements shall conform to the requirements in ASTM Designation: C 150 and the additional requirements listed above for "Type II Modified" portland cement, except that when tested in conformance with California Test 527, mortar containing Type III portland cement shall not contract in air more than 0.075 percent.
- Cement used in the manufacture of cast-in-place concrete for exposed surfaces of like elements of a structure shall be from the same cement mill.
- Cement shall be protected from exposure to moisture until used. Sacked cement shall be piled to permit access for tally, inspection, and identification of each shipment.
- Adequate facilities shall be provided to assure that cement meeting the provisions specified in this Section 90-2.01 shall be kept separate from other cement in order to prevent any but the specified cement from entering the work. Safe and suitable facilities for sampling cement shall be provided at the weigh hopper or in the feed line immediately in advance of the hopper, in conformance with California Test 125.
- If cement is used prior to sampling and testing as provided in Section 6-1.07, "Certificates of Compliance," and the cement is delivered directly to the site of the work, the Certificate of Compliance shall be signed by the cement manufacturer or supplier of the cement. If the cement is used in ready-mixed concrete or in precast concrete products purchased as such by the Contractor, the Certificate of Compliance shall be signed by the manufacturer of the concrete or product.
- Cement furnished without a Certificate of Compliance shall not be used in the work until the Engineer has had sufficient time to make appropriate tests and has approved the cement for use.

#### **90-2.02 AGGREGATES**

- Aggregates shall be free from deleterious coatings, clay balls, roots, bark, sticks, rags, and other extraneous material.
- Natural aggregates shall be thoroughly and uniformly washed before use.
- The Contractor, at the Contractor's expense, shall provide safe and suitable facilities, including necessary splitting devices for obtaining samples of aggregates, in conformance with California Test 125.
- Aggregates shall be of such character that it will be possible to produce workable concrete within the limits of water content provided in Section 90-6.06, "Amount of Water and Penetration."
- Aggregates shall have not more than 10 percent loss when tested for soundness in conformance with the requirements in California Test 214. The soundness requirement for fine aggregate will be waived, provided that the durability index,  $D_f$ , of the fine aggregate is 60, or greater, when tested for durability in conformance with California Test 229.
- If the results of any one or more of the Cleanness Value, Sand Equivalent, or aggregate grading tests do not meet the requirements specified for "Operating Range" but all meet the "Contract Compliance" requirements, the placement of concrete shall be suspended at the completion of the current pour until tests or other information indicate that the next material to be used in the work will comply with the requirements specified for "Operating Range."
- If the results of either or both the Cleanness Value and coarse aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete that is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State \$4.60 per cubic meter for paving concrete and \$7.20 per cubic meter for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.
- If the results of either or both the Sand Equivalent and fine aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete which is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State \$4.60 per cubic meter for paving concrete and \$7.20 per cubic meter for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.
- The 2 preceding paragraphs apply individually to the "Contract Compliance" requirements for coarse aggregate and fine aggregate. When both coarse aggregate and fine aggregate do not conform to the "Contract Compliance" requirements, both paragraphs shall apply. The payments specified in those paragraphs shall be in addition to any payments made in conformance with the provisions in Section 90-1.01, "Description."
- No single Cleanness Value, Sand Equivalent or aggregate grading test shall represent more than 250 m<sup>3</sup> of concrete or one day's pour, whichever is smaller.
- Aggregates specified for freeze-thaw resistance shall pass the freezing and thawing test, California Test 528.

- The Contractor shall notify the Engineer of the proposed source of freeze-thaw resistant concrete aggregates at least 4 months before intended use. Should the Contractor later propose a different source of concrete aggregates, the Contractor shall again notify the Engineer at least 4 months before intended use. Blending of fine or coarse aggregates from untested sources with acceptable aggregates will not be permitted. Provisions for the time of submission of samples as provided in Section 40-1.015, "Cement Content," are superseded by the foregoing.

- Concurrently with notification of proposed sources of freeze-thaw resistant concrete aggregates, the Contractor shall furnish samples in the quantity ordered by the Engineer. The samples shall be secured under the direct supervision of the Engineer. Samples from existing stockpiles of processed aggregate shall be taken from washed materials and shall be visibly damp. Samples from materials in place in a material source shall be taken at depths from the existing surface that will ensure the presence of the full quantity of ground water. Excavations for the purpose of securing samples shall be made to the full depth of intended source operations. Samples shall be protected against loss of contained water until they are delivered to the Engineer.

- The Engineer will waive the above freeze-thaw test and the 4-month advance notice, required in this Section, provided aggregates are to be obtained from sources that have previously passed this test and test results are currently applicable.

- No extension of contract time will be allowed for the time required to perform the freezing and thawing test.

- When the source of an aggregate is changed, except for pavement concrete, the Contractor shall adjust the mix proportions and submit in writing to the Engineer a copy of the mix design before using the aggregates. When the source of an aggregate is changed for pavement concrete, the Engineer shall be allowed sufficient time to adjust the mix, and the aggregates shall not be used until necessary adjustments are made.

**90-2.02A Coarse Aggregate**

- Coarse aggregate shall consist of gravel, crushed gravel, crushed rock, crushed air-cooled iron blast furnace slag or combinations thereof. Crushed air-cooled blast furnace slag shall not be used in reinforced or prestressed concrete.

- Coarse aggregate shall conform to the following quality requirements:

Tests	California Test	Requirements
Loss in Los Angeles Rattler (after 500 revolutions)	211	45% max.
Cleanness Value		
Operating Range	227	75 min.
Contract Compliance	227	71 min.

- In lieu of the above Cleanness Value requirements, a Cleanness Value "Operating Range" limit of 71, minimum, and a Cleanness Value "Contract Compliance" limit of 68, minimum, will be used to determine the acceptability of the coarse aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

- coarse aggregate sampled at the completion of processing at the aggregate production plant had a Cleanness Value of not less than 82 when tested by California Test 227; and
- prequalification tests performed in conformance with the requirements in California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

**90-2.02B Fine Aggregate**

- Fine aggregate shall consist of natural sand, manufactured sand produced from larger aggregate or a combination thereof. Manufactured sand shall be well graded.

- Fine aggregate shall conform to the following quality requirements:

Test	California Test	Requirements
Organic Impurities	213	Satisfactory <sup>a</sup>
Mortar Strengths Relative to Ottawa Sand	515	95%, min.
Sand Equivalent:		
Operating Range	217	75, min.
Contract Compliance	217	71, min.

a Fine aggregate developing a color darker than the reference standard color solution may be accepted if it is determined by the Engineer, from mortar strength tests, that a darker color is acceptable.

• In lieu of the above Sand Equivalent requirements, a Sand Equivalent "Operating Range" limit of 71 minimum and a Sand Equivalent "Contract Compliance" limit of 68 minimum will be used to determine the acceptability of the fine aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

1. fine aggregate sampled at the completion of processing at the aggregate production plant had a Sand Equivalent value of not less than 82 when tested by California Test 217; and
2. prequalification tests performed in conformance with California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

#### 90-2.03 WATER

• In conventionally reinforced concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 1000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1300 parts per million of sulfates as SO<sub>4</sub>, when tested in conformance with California Test 417. In prestressed concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 650 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1300 parts per million of sulfates as SO<sub>4</sub>, when tested in conformance with California Test 417. In no case shall the water contain an amount of impurities that will cause either: 1) a change in the setting time of cement of more than 25 percent when tested in conformance with the requirements in ASTM Designation: C 191 or ASTM Designation: C 266 or 2) a reduction in the compressive strength of mortar at 14 days of more than 5 percent, when tested in conformance with the requirements in ASTM Designation: C 109, when compared to the results obtained with distilled water or deionized water, tested in conformance with the requirements in ASTM Designation: C 109.

• In non-reinforced concrete work, the water for curing, for washing aggregates and for mixing shall be free from oil and shall not contain more than 2000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, or more than 1500 parts per million of sulfates as SO<sub>4</sub>, when tested in conformance with California Test 417.

• In addition to the above provisions, water for curing concrete shall not contain impurities in a sufficient amount to cause discoloration of the concrete or produce etching of the surface.

• Water reclaimed from mixer wash-out operations may be used in mixing concrete. The water shall not contain coloring agents or more than 300 parts per million of alkalis (Na<sub>2</sub>O + 0.658 K<sub>2</sub>O) as determined on the filtrate. The specific gravity of the water shall not exceed 1.03 and shall not vary more than ±0.010 during a day's operations.

#### 90-2.04 ADMIXTURE MATERIALS

• Admixture materials shall conform to the requirements in the following ASTM Designations:

- A. Chemical Admixtures—ASTM Designation: C 494.
- B. Air-entraining Admixtures—ASTM Designation: C 260.
- C. Calcium Chloride—ASTM Designation: D 98.
- D. Mineral Admixtures—Coal fly ash; raw or calcined natural pozzolan as specified in ASTM Designation: C618; silica fume conforming to the requirements in ASTM Designation: C1240, with reduction of mortar expansion of 80 percent, minimum, using the cement from the proposed mix design.

• Unless otherwise specified in the special provisions, mineral admixtures shall be used in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures."

## 90-3 AGGREGATE GRADINGS

### 90-3.01 GENERAL

- Before beginning concrete work, the Contractor shall submit in writing to the Engineer the gradation of the primary aggregate nominal sizes that the Contractor proposes to furnish. If a primary coarse aggregate or the fine aggregate is separated into 2 or more sizes, the proposed gradation shall consist of the gradation for each individual size, and the proposed proportions of each individual size, combined mathematically to indicate one proposed gradation. The proposed gradation shall meet the grading requirements shown in the table in this section, and shall show the percentage passing each of the sieve sizes used in determining the end result.

- The Engineer may waive, in writing, the gradation requirements in this Section 90-3.01 and in Sections 90-3.02, "Coarse Aggregate Grading," 90-3.03, "Fine Aggregate Grading," and 90-3.04, "Combined Aggregate Gradings," if, in the Engineer's opinion, furnishing the gradation is not necessary for the type or amount of concrete work to be constructed.

- Gradations proposed by the Contractor shall be within the following percentage passing limits:

Primary Aggregate Nominal Size	Sieve Size	Limits of Proposed Gradation
37.5-mm x 19-mm	25-mm	19 - 41
25-mm x 4.75-mm	19-mm	52 - 85
25-mm x 4.75-mm	9.5-mm	15 - 38
12.5-mm x 4.75-mm	9.5-mm	40 - 78
9.5-mm x 2.36-mm	9.5-mm	50 - 85
Fine Aggregate	1.18-mm	55 - 75
Fine Aggregate	600- $\mu$ m	34 - 46
Fine Aggregate	300- $\mu$ m	16 - 29

- Should the Contractor change the source of supply, the Contractor shall submit in writing to the Engineer the new gradations before their intended use.

### 90-3.02 COARSE AGGREGATE GRADING

- The grading requirements for coarse aggregates are shown in the following table for each size of coarse aggregate:

Sieve Sizes	Percentage Passing Primary Aggregate Nominal Sizes							
	37.5-mm x 19-mm		25-mm x 4.75-mm		12.5-mm x 4.75-mm		9.5-mm x 2.36-mm	
	Operating Range	Contract Compliance	Operating Range	Contract Compliance	Operating Range	Contract Compliance	Operating Range	Contract Compliance
50-mm	100	100	—	—	—	—	—	—
37.5-mm	88-100	85-100	100	100	—	—	—	—
25-mm	x $\pm$ 18	X $\pm$ 25	88-100	86-100	—	—	—	—
19-mm	0-17	0-20	X $\pm$ 15	X $\pm$ 22	100	100	—	—
12.5-mm	—	—	—	—	82-100	80-100	100	100
9.5-mm	0-7	0-9	X $\pm$ 15	X $\pm$ 22	X $\pm$ 15	X $\pm$ 22	X $\pm$ 15	X $\pm$ 20
4.75-mm	—	—	0-16	0-18	0-15	0-18	0-25	0-28
2.36-mm	—	—	0-6	0-7	0-6	0-7	0-6	0-7

- In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."

- Coarse aggregate for the 37.5-mm, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," shall be furnished in 2 or more primary aggregate nominal sizes. Each primary aggregate nominal size may be separated into 2 sizes and stored separately, provided that the combined material conforms to the grading requirements for that particular primary aggregate nominal size.

- When the 25-mm, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," is to be used, the coarse aggregate may be separated into 2 sizes and stored separately, provided that the combined material shall conform to the grading requirements for the 25-mm x 4.75-mm primary aggregate nominal size.

**90-3.03 FINE AGGREGATE GRADING**

- Fine aggregate shall be graded within the following limits:

Sieve Sizes	Percentage Passing	
	Operating Range	Contract Compliance
9.5-mm	100	100
4.75-mm	95-100	93-100
2.36-mm	65-95	61-99
1.18-mm	X ± 10	X ± 13
600-µm	X ± 9	X ± 12
300-µm	X ± 6	X ± 9
150-µm	2-12	1-15
75-µm	0-8	0-10

- In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."
- In addition to the above required grading analysis, the distribution of the fine aggregate sizes shall be such that the difference between the total percentage passing the 1.18-mm sieve and the total percentage passing the 600-µm sieve shall be between 10 and 40, and the difference between the percentage passing the 600-µm and 300-µm sieves shall be between 10 and 40.
- Fine aggregate may be separated into 2 or more sizes and stored separately, provided that the combined material conforms to the grading requirements specified in this Section 90-3.03.

**90-3.04 COMBINED AGGREGATE GRADINGS**

- Combined aggregate grading limits shall be used only for the design of concrete mixes. Concrete mixes shall be designed so that aggregates are combined in proportions that shall produce a mixture within the grading limits for combined aggregates as specified herein. Within these limitations, the relative proportions shall be as ordered by the Engineer, except as otherwise provided in Section 90-1.01, "Description."
- The combined aggregate grading used in portland cement concrete pavement shall be the 37.5-mm, maximum grading.
- The combined aggregate grading used in concrete for structures and other concrete items, except when specified otherwise in these specifications or the special provisions, shall be either the 37.5-mm, maximum grading, or the 25-mm, maximum grading, at the option of the Contractor.

Grading Limits of Combined Aggregates

Sieve Sizes	Percentage Passing			
	37.5-mm Max.	25-mm Max.	12.5-mm Max.	9.5-mm Max.
50-mm	100	—	—	—
37.5-mm	90-100	100	—	—
25-mm	50-86	90-100	—	—
19-mm	45-75	55-100	100	—
12.5-mm	—	—	90-100	100
9.5-mm	38-55	45-75	55-86	50 - 100
4.75-mm	30-45	35-60	45-63	45 - 63
2.36-mm	23-38	27-45	35-49	35 - 49
1.18-mm	17-33	20-35	25-37	25 - 37
600-µm	10-22	12-25	15-25	15 - 25
300-µm	4-10	5-15	5-15	5 - 15
150-µm	1-6	1-8	1-8	1 - 8
75-µm	0-3	0-4	0-4	0 - 4

- Changes from one grading to another shall not be made during the progress of the work unless permitted by the Engineer.

## 90-4 ADMIXTURES

### 90-4.01 GENERAL

- Admixtures used in portland cement concrete shall conform to and be used in conformance with the provisions in this Section 90-4 and the special provisions. Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option as provided herein.
- Chemical admixtures and air-entraining admixtures containing chlorides as Cl in excess of one percent by mass of admixture, as determined by California Test 415, shall not be used in prestressed or reinforced concrete.
- Calcium chloride shall not be used in concrete containing steel reinforcement or other embedded metals.
- Mineral admixture used in concrete for exposed surfaces of like elements of a structure shall be from the same source and of the same percentage.
- Admixtures shall be uniform in properties throughout their use in the work. Should it be found that an admixture as furnished is not uniform in properties, its use shall be discontinued.
- If more than one admixture is used, the admixtures shall be compatible with each other so that the desirable effects of all admixtures used will be realized.

### 90-4.02 MATERIALS

- Admixture materials shall conform to the provisions in Section 90-2.04, "Admixture Materials."

### 90-4.03 ADMIXTURE APPROVAL

- No admixture brand shall be used in the work unless it is on the Department's current list of approved brands for the type of admixture involved.
- Admixture brands will be considered for addition to the approved list if the manufacturer of the admixture submits to the Transportation Laboratory a sample of the admixture accompanied by certified test results demonstrating that the admixture complies with the requirements in the appropriate ASTM Designation and these specifications. The sample shall be sufficient to permit performance of all required tests. Approval of admixture brands will be dependent upon a determination as to compliance with the requirements, based on the certified test results submitted, together with tests the Department may elect to perform.
- When the Contractor proposes to use an admixture of a brand and type on the current list of approved admixture brands, the Contractor shall furnish a Certificate of Compliance from the manufacturer, as provided in Section 6-1.07, "Certificates of Compliance," certifying that the admixture furnished is the same as that previously approved. If a previously approved admixture is not accompanied by a Certificate of Compliance, the admixture shall not be used in the work until the Engineer has had sufficient time to make the appropriate tests and has approved the admixture for use. The Engineer may take samples for testing at any time, whether or not the admixture has been accompanied by a Certificate of Compliance.
- If a mineral admixture is delivered directly to the site of the work, the Certificate of Compliance shall be signed by the manufacturer or supplier of the mineral admixture. If the mineral admixture is used in ready-mix concrete or in precast concrete products purchased as such by the Contractor, the Certificate of Compliance shall be signed by the manufacturer of the concrete or product.

### 90-4.04 REQUIRED USE OF CHEMICAL ADMIXTURES AND CALCIUM CHLORIDE

- When the use of a chemical admixture or calcium chloride is specified or ordered by the Engineer, the admixture shall be used at the dosage specified or ordered, except that if no dosage is specified or ordered, the admixture shall be used at the dosage normally recommended by the manufacturer of the admixture.
- Calcium chloride shall be dispensed in liquid, flake, or pellet form. Calcium chloride dispensed in liquid form shall conform to the provisions for dispensing liquid admixtures in Section 90-4.10, "Proportioning and Dispensing Liquid Admixtures."

### 90-4.05 OPTIONAL USE OF CHEMICAL ADMIXTURES

- The Contractor will be permitted to use Type A or F, water-reducing; Type B, retarding; or Type D or G, water-reducing and retarding admixtures as described in ASTM Designation: C 494 to conserve cementitious material or to facilitate any concrete construction application subject to the following conditions:
  - A. When a water-reducing admixture or a water-reducing and retarding admixture is used, the cementitious material content specified or ordered may be reduced by a maximum of 5 percent by mass, except that the resultant cementitious material content shall be not less than 300 kilograms per cubic meter; and
  - B. When a reduction in cementitious material content is made, the dosage of admixture used shall be the dosage used in determining approval of the admixture.

- Unless otherwise specified, a Type C accelerating chemical admixture conforming to the requirements in ASTM Designation: C 494, may be used in portland cement concrete. Inclusion in the mix design submitted for approval will not be required provided that the admixture is added to counteract changing conditions that contribute to delayed setting of the portland cement concrete, and the use or change in dosage of the admixture is approved in writing by the Engineer.

#### **90-4.06 REQUIRED USE OF AIR-ENTRAINING ADMIXTURES**

- When air-entrainment is specified or ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce a concrete having the specified air content as determined by California Test 504.

#### **90-4.07 OPTIONAL USE OF AIR-ENTRAINING ADMIXTURES**

- When air-entrainment has not been specified or ordered by the Engineer, the Contractor will be permitted to use an air-entraining admixture to facilitate the use of any construction procedure or equipment provided that the average air content, as determined by California Test 504, of 3 successive tests does not exceed 4 percent, and no single test value exceeds 5.5 percent. If the Contractor elects to use an air-entraining admixture in concrete for pavement, the Contractor shall so indicate at the time the Contractor designates the source of aggregate as provided in Section 40-1.015, "Cement Content."

#### **90-4.08 REQUIRED USE OF MINERAL ADMIXTURES**

- Unless otherwise specified, mineral admixture shall be combined with cement to make cementitious material.
- The calcium oxide content of mineral admixtures shall not exceed 10 percent and the available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C 618.

- The amounts of cement and mineral admixture used in cementitious material shall be sufficient to satisfy the minimum cementitious material content requirements specified in Section 90-1.01, "Description," or Section 90-4.05, "Optional Use of Chemical Admixtures," and shall conform to the following:

- A. The minimum amount of cement shall not be less than 75 percent by mass of the specified minimum cementitious material content;
- B. The minimum amount of mineral admixture to be combined with cement shall be determined using one of the following criteria:
  1. When the calcium oxide content of a mineral admixture is equal to or less than 2 percent by mass, the amount of mineral admixture shall not be less than 15 percent by mass of the total amount of cementitious material to be used in the mix;
  2. When the calcium oxide content of a mineral admixture is greater than 2 percent, the amount of mineral admixture shall not be less than 25 percent by mass of the total amount of cementitious material to be used in the mix;
  3. When a mineral admixture that conforms to the provisions for silica fume in Section 90-2.04, "Admixture Materials," is used, the amount of mineral admixture shall not be less than 10 percent by mass of the total amount of cementitious material to be used in the mix
- C. The total amount of mineral admixture shall not exceed 35 percent by mass of the total amount of cementitious material to be used in the mix. Where Section 90-1.01, "Description," specifies a maximum cementitious content in kilograms per cubic meter, the total mass of cement and mineral admixture per cubic meter shall not exceed the specified maximum cementitious material content.

#### **90-4.09 BLANK**

#### **90-4.10 PROPORTIONING AND DISPENSING LIQUID ADMIXTURES**

- Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers for liquid admixtures shall have sufficient capacity to measure at one time the prescribed quantity required for each batch of concrete. Each dispenser shall include a graduated measuring unit into which liquid admixtures are measured to within  $\pm 5$  percent of the prescribed quantity for each batch. Dispensers shall be located and maintained so that the graduations can be accurately read from the point at which proportioning operations are controlled to permit a visual check of batching accuracy prior to discharge. Each measuring unit shall be clearly marked for the type and quantity of admixture.

- Each liquid admixture dispensing system shall be equipped with a sampling device consisting of a valve located in a safe and readily accessible position such that a sample of the admixture may be withdrawn slowly by the Engineer.

- If more than one liquid admixture is used in the concrete mix, each liquid admixture shall have a separate measuring unit and shall be dispensed by injecting equipment located in such a manner that the admixtures are not mixed at high concentrations and do not interfere with the effectiveness of each other. When air-entraining admixtures are used in conjunction with other liquid admixtures, the air-entraining admixture shall be the first to be incorporated into the mix.
- When automatic proportioning devices are required for concrete pavement, dispensers for liquid admixtures shall operate automatically with the batching control equipment. The dispensers shall be equipped with an automatic warning system in good operating condition that will provide a visible or audible signal at the point at which proportioning operations are controlled when the quantity of admixture measured for each batch of concrete varies from the preselected dosage by more than 5 percent, or when the entire contents of the measuring unit are not emptied from the dispenser into each batch of concrete.
- Unless liquid admixtures are added to premeasured water for the batch, their discharge into the batch shall be arranged to flow into the stream of water so that the admixtures are well dispersed throughout the batch, except that air-entraining admixtures may be dispensed directly into moist sand in the batching bins provided that adequate control of the air content of the concrete can be maintained.
- Liquid admixtures requiring dosages greater than 2.5 L/m<sup>3</sup> shall be considered to be water when determining the total amount of free water as specified in Section 90-6.06, "Amount of Water and Penetration."
- Special admixtures, such as "high range" water reducers that may contribute to a high rate of slump loss, shall be measured and dispensed as recommended by the admixture manufacturer and as approved by the Engineer.

#### **90-4.11 STORAGE, PROPORTIONING, AND DISPENSING OF MINERAL ADMIXTURES**

- Mineral admixtures shall be protected from exposure to moisture until used. Sacked material shall be piled to permit access for tally, inspection and identification for each shipment.
- Adequate facilities shall be provided to assure that mineral admixtures meeting the specified requirements are kept separate from other mineral admixtures in order to prevent any but the specified mineral admixtures from entering the work. Safe and suitable facilities for sampling mineral admixtures shall be provided at the weigh hopper or in the feed line immediately in advance of the hopper.
- Mineral admixtures shall be incorporated into concrete using equipment conforming to the requirements for cement weigh hoppers, and charging and discharging mechanisms in ASTM Designation: C 94, in Section 90-5.03, "Proportioning," and in this Section 90-4.11.
- When concrete is completely mixed in stationary paving mixers, the mineral admixture shall be weighed in a separate weigh hopper conforming to the provisions for cement weigh hoppers and charging and discharging mechanisms in Section 90-5.03A, "Proportioning for Pavement," and the mineral admixture and cement shall be introduced simultaneously into the mixer proportionately with the aggregate. If the mineral admixture is not weighed in a separate weigh hopper, the Contractor shall provide certification that the stationary mixer is capable of mixing the cement, admixture, aggregates and water uniformly prior to discharge. Certification shall contain the following:
  - A. Test results for 2 compressive strength test cylinders of concrete taken within the first one-third and 2 compressive strength test cylinders of concrete taken within the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength;"
  - B. Calculations demonstrating that the difference in the averages of 2 compressive strengths taken in the first one-third is no greater than 7.5 percent different than the averages of 2 compressive strengths taken in the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength;" and
  - C. The mixer rotation speed and time of mixing prior to discharge that are required to produce a mix that meets the requirements above.

### **90-5 PROPORTIONING**

#### **90-5.01 STORAGE OF AGGREGATES**

- Aggregates shall be stored or stockpiled in such a manner that separation of coarse and fine particles of each size shall be avoided and also that the various sizes shall not become intermixed before proportioning.
- Aggregates shall be stored or stockpiled and handled in a manner that shall prevent contamination by foreign materials. In addition, storage of aggregates at batching or mixing facilities that are erected subsequent to the award of the contract and that furnish concrete to the project shall conform to the following:

- A. Intermingling of the different sizes of aggregates shall be positively prevented. The Contractor shall take the necessary measures to prevent intermingling. The preventive measures may include, but are not necessarily limited to, physical separation of stockpiles or construction of bulkheads of adequate length and height; and
- B. Contamination of aggregates by contact with the ground shall be positively prevented. The Contractor shall take the necessary measures to prevent contamination. The preventive measures shall include, but are not necessarily limited to, placing aggregates on wooden platforms or on hardened surfaces consisting of portland cement concrete, asphalt concrete, or cement treated material.

- In placing aggregates in storage or in moving the aggregates from storage to the weigh hopper of the batching plant, any method that may cause segregation, degradation, or the combining of materials of different gradings that will result in any size of aggregate at the weigh hopper failing to meet the grading requirements, shall be discontinued. Any method of handling aggregates that results in excessive breakage of particles shall be discontinued. The use of suitable devices to reduce impact of falling aggregates may be required by the Engineer.

#### **90-5.02 PROPORTIONING DEVICES**

- Weighing, measuring, or metering devices used for proportioning materials shall conform to the requirements in Section 9-1.01, "Measurement of Quantities," and this Section 90-5.02. In addition, automatic weighing systems shall comply with the requirements for automatic proportioning devices in Section 90-5.03A, "Proportioning for Pavement." Automatic devices shall be automatic to the extent that the only manual operation required for proportioning the aggregates, cement, and mineral admixture for one batch of concrete is a single operation of a switch or starter.

- Proportioning devices shall be tested at the expense of the Contractor as frequently as the Engineer may deem necessary to ensure their accuracy.

- Weighing equipment shall be insulated against vibration or movement of other operating equipment in the plant. When the plant is in operation, the mass of each batch of material shall not vary from the mass designated by the Engineer by more than the tolerances specified herein.

- Equipment for cumulative weighing of aggregate shall have a zero tolerance of  $\pm 0.5$  percent of the designated total batch mass of the aggregate. For systems with individual weigh hoppers for the various sizes of aggregate, the zero tolerance shall be  $\pm 0.5$  percent of the individual batch mass designated for each size of aggregate. Equipment for cumulative weighing of cement and mineral admixtures shall have a zero tolerance of  $\pm 0.5$  percent of the designated total batch mass of the cement and mineral admixture. Equipment for weighing cement or mineral admixture separately shall have a zero tolerance of  $\pm 0.5$  percent of their designated individual batch masses. Equipment for measuring water shall have a zero tolerance of  $\pm 0.5$  percent of its designated mass or volume.

- The mass indicated for any batch of material shall not vary from the preselected scale setting by more than the following:

- A. Aggregate weighed cumulatively shall be within 1.0 percent of the designated total batch mass of the aggregate. Aggregates weighed individually shall be within 1.5 percent of their respective designated batch masses; and
- B. Cement shall be within 1.0 percent of its designated batch mass. When weighed individually, mineral admixture shall be within 1.0 percent of its designated batch mass. When mineral admixture and cement are permitted to be weighed cumulatively, cement shall be weighed first to within 1.0 percent of its designated batch mass, and the total for cement and mineral admixture shall be within 1.0 percent of the sum of their designated batch masses; and
- C. Water shall be within 1.5 percent of its designated mass or volume.

- Each scale graduation shall be approximately 0.001 of the total capacity of the scale. The capacity of scales for weighing cement, mineral admixture, or cement plus mineral admixture and aggregates shall not exceed that of commercially available scales having single graduations indicating a mass not exceeding the maximum permissible mass variation above, except that no scale shall be required having a capacity of less than 500 kg, with 0.5-kg graduations.

#### **90-5.03 PROPORTIONING**

- Proportioning shall consist of dividing the aggregates into the specified sizes, each stored in a separate bin, and combining them with cement, mineral admixture, and water as provided in these specifications. Aggregates shall be proportioned by mass.

- At the time of batching, aggregates shall have been dried or drained sufficiently to result in a stable moisture content such that no visible separation of water from aggregate will take place during transportation from the proportioning plant to the point of mixing. In no event shall the free moisture content of the fine aggregate at the time of batching exceed 8 percent of its saturated, surface-dry mass.

- Should separate supplies of aggregate material of the same size group, but of different moisture content or specific gravity or surface characteristics affecting workability, be available at the proportioning plant, withdrawals shall be made from one supply exclusively and the materials therein completely exhausted before starting upon another.
- Bulk "Type IP (MS) Modified" cement shall be weighed in an individual hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer.
- Bulk cement and mineral admixture may be weighed in separate, individual weigh hoppers or may be weighed in the same weigh hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer. If the cement and mineral admixture are weighed cumulatively, the cement shall be weighed first.
- When cement and mineral admixtures are weighed in separate weigh hoppers, the weigh systems for the proportioning of the aggregate, the cement, and the mineral admixture shall be individual and distinct from all other weigh systems. Each weigh system shall be equipped with a hopper, a lever system, and an indicator to constitute an individual and independent material weighing device. The cement and the mineral admixture shall be discharged into the mixer simultaneously with the aggregate.
- The scales and weigh hoppers for bulk weighing cement, mineral admixture, or cement plus mineral admixture shall be separate and distinct from the aggregate weighing equipment.
- For batches with a volume of one cubic meter or more, the batching equipment shall conform to one of the following combinations:
  - A. Separate boxes and separate scale and indicator for weighing each size of aggregate.
  - B. Single box and scale indicator for all aggregates.
  - C. Single box or separate boxes and automatic weighing mechanism for all aggregates.
- In order to check the accuracy of batch masses, the gross mass and tare mass of batch trucks, truck mixers, truck agitators, and non-agitating hauling equipment shall be determined when ordered by the Engineer. The equipment shall be weighed at the Contractor's expense on scales designated by the Engineer.

**90-5.03A Proportioning for Pavement**

- Aggregates and bulk cement, mineral admixture, and cement plus mineral admixture for use in pavement shall be proportioned by mass by means of automatic proportioning devices of approved type conforming to these specifications.
- The Contractor shall install and maintain in operating condition an electronically actuated moisture meter that will indicate, on a readily visible scale, changes in the moisture content of the fine aggregate as it is batched within a sensitivity of 0.5 percent by mass of the fine aggregate.
- The batching of cement, mineral admixture, or cement plus mineral admixture and aggregate shall be interlocked so that a new batch cannot be started until all weigh hoppers are empty, the proportioning devices are within zero tolerance, and the discharge gates are closed. The interlock shall permit no part of the batch to be discharged until all aggregate hoppers and the cement and mineral admixture hoppers or the cement plus mineral admixture hopper are charged with masses that are within the tolerances specified in Section 90-5.02, "Proportioning Devices."
- When interlocks are required for cement and mineral admixture charging mechanisms and cement and mineral admixtures are weighed cumulatively, their charging mechanisms shall be interlocked to prevent the introduction of mineral admixture until the mass of cement in the cement weigh hopper is within the tolerances specified in Section 90-5.02, "Proportioning Devices."
- The discharge gate on the cement and mineral admixture hoppers or the cement plus mineral admixture hopper shall be designed to permit regulating the flow of cement, mineral admixture, or cement plus mineral admixture into the aggregate as directed by the Engineer.
- When separate weigh boxes are used for each size of aggregate, the discharge gates shall permit regulating the flow of each size of aggregate as directed by the Engineer.
- Material discharged from the several bins shall be controlled by gates or by mechanical conveyors. The means of withdrawal from the several bins, and of discharge from the weigh box, shall be interlocked so that not more than one bin can discharge at a time, and so that the weigh box cannot be tripped until the required quantity from each of the several bins has been deposited therein. Should a separate weigh box be used for each size of aggregate, all may be operated and discharged simultaneously.
- When the discharge from the several bins is controlled by gates, each gate shall be actuated automatically so that the required mass is discharged into the weigh box, after which the gate shall automatically close and lock.
- The automatic weighing system shall be designed so that all proportions required may be set on the weighing controller at the same time.

## 90-6 MIXING AND TRANSPORTING

### 90-6.01 GENERAL

- Concrete shall be mixed in mechanically operated mixers, except that when permitted by the Engineer, batches not exceeding 0.25 m<sup>3</sup> may be mixed by hand methods in conformance with the provisions in Section 90-6.05, "Hand-Mixing."
- Equipment having components made of aluminum or magnesium alloys that would have contact with plastic concrete during mixing, transporting, or pumping of portland cement concrete shall not be used.
- Concrete shall be homogeneous and thoroughly mixed, and there shall be no lumps or evidence of undispersed cement, mineral admixture, or cement plus mineral admixture.
- Uniformity of concrete mixtures will be determined by differences in penetration as determined by California Test 533, or slump as determined by ASTM Designation: C 143, and by variations in the proportion of coarse aggregate as determined by California Test 529.
- When the mix design specifies a penetration value, the difference in penetration, determined by comparing penetration tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed 10 mm. When the mix design specifies a slump value, the difference in slump, determined by comparing slump tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed the values given in the table below. Variation in the proportion of coarse aggregate will be determined by comparing the results of tests of 2 samples of mixed concrete from the same batch or truck mixer load and the difference between the 2 results shall not exceed 100 kg per cubic meter of concrete.

Average Slump	Maximum Permissible Difference
Less than 100-mm	25-mm
100-mm to 150-mm	38-mm
Greater than 150-mm to 225-mm	50-mm

- The Contractor, at the Contractor's expense, shall furnish samples of the freshly mixed concrete and provide satisfactory facilities for obtaining the samples.

### 90-6.02 MACHINE MIXING

- Concrete mixers may be of the revolving drum or the revolving blade type, and the mixing drum or blades shall be operated uniformly at the mixing speed recommended by the manufacturer. Mixers and agitators that have an accumulation of hard concrete or mortar shall not be used.
- The temperature of mixed concrete, immediately before placing, shall be not less than 10°C or more than 32°C. Aggregates and water shall be heated or cooled as necessary to produce concrete within these temperature limits. Neither aggregates nor mixing water shall be heated to exceed 65°C. If ice is used to cool the concrete, discharge of the mixer will not be permitted until all ice is melted.
- The batch shall be so charged into the mixer that some water will enter in advance of cementitious materials and aggregates. All water shall be in the drum by the end of the first one - fourth of the specified mixing time.
- Cementitious materials shall be batched and charged into the mixer by means that will not result either in loss of cementitious materials due to the effect of wind, in accumulation of cementitious materials on surfaces of conveyors or hoppers, or in other conditions that reduce or vary the required quantity of cementitious material in the concrete mixture.
- Paving and stationary mixers shall be operated with an automatic timing device. The timing device and discharge mechanism shall be interlocked so that during normal operation no part of the batch will be discharged until the specified mixing time has elapsed.
- The total elapsed time between the intermingling of damp aggregates and all cementitious materials and the start of mixing shall not exceed 30 minutes.
- The size of batch shall not exceed the manufacturer's guaranteed capacity.
- When producing concrete for pavement or base, suitable batch counters shall be installed and maintained in good operating condition at jobsite batching plants and stationary mixers. The batch counters shall indicate the exact number of batches proportioned and mixed.
- Concrete shall be mixed and delivered to the jobsite by means of one of the following combinations of operations:
  - A. Mixed completely in a stationary mixer and the mixed concrete transported to the point of delivery in truck agitators or in non-agitating hauling equipment (central-mixed concrete).
  - B. Mixed partially in a stationary mixer, and the mixing completed in a truck mixer (shrink-mixed concrete).
  - C. Mixed completely in a truck mixer (transit-mixed concrete).
  - D. Mixed completely in a paving mixer.

- Agitators may be truck mixers operating at agitating speed or truck agitators. Each mixer and agitator shall have attached thereto in a prominent place a metal plate or plates on which is plainly marked the various uses for which the equipment is designed, the manufacturer's guaranteed capacity of the drum or container in terms of the volume of mixed concrete and the speed of rotation of the mixing drum or blades.
- Truck mixers shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified.
- When shrink-mixed concrete is furnished, concrete that has been partially mixed at a central plant shall be transferred to a truck mixer and all requirements for transit-mixed concrete shall apply. No credit in the number of revolutions at mixing speed shall be allowed for partial mixing in a central plant.

### **90-6.03 TRANSPORTING MIXED CONCRETE**

- Mixed concrete may be transported to the delivery point in truck agitators or truck mixers operating at the speed designated by the manufacturer of the equipment as agitating speed, or in non-agitating hauling equipment, provided the consistency and workability of the mixed concrete upon discharge at the delivery point is suitable for adequate placement and consolidation in place, and provided the mixed concrete after hauling to the delivery point conforms to the provisions in Section 90-6.01, "General."
- Truck agitators shall be loaded not to exceed the manufacturer's guaranteed capacity and shall maintain the mixed concrete in a thoroughly mixed and uniform mass during hauling.
- Bodies of non-agitating hauling equipment shall be constructed so that leakage of the concrete mix, or any part thereof, will not occur at any time.
- Concrete hauled in open-top vehicles shall be protected during hauling against rain or against exposure to the sun for more than 20 minutes when the ambient temperature exceeds 24°C.
- No additional mixing water shall be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer. If the Engineer authorizes additional water to be incorporated into the concrete, the drum shall be revolved not less than 30 revolutions at mixing speed after the water is added and before discharge is commenced.
- The rate of discharge of mixed concrete from truck mixer-agitators shall be controlled by the speed of rotation of the drum in the discharge direction with the discharge gate fully open.
- When a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be completed within 1.5 hours or before 250 revolutions of the drum or blades, whichever occurs first, after the introduction of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C or above, the time allowed may be less than 1.5 hours.
- When non-agitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be completed within one hour after the addition of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.
- Each load of concrete delivered at the jobsite shall be accompanied by a weighmaster certificate showing the mix identification number, non-repeating load number, date and time at which the materials were batched, the total amount of water added to the load, and for transit-mixed concrete, the reading of the revolution counter at the time the truck mixer is charged with cement. This weighmaster certificate shall also show the actual scale masses (kilograms) for the ingredients batched. Theoretical or target batch masses shall not be used as a substitute for actual scale masses.
- Weighmaster certificates shall be provided in printed form, or if approved by the Engineer, the data may be submitted in electronic media. Electronic media shall be presented in a tab-delimited format on a 90 mm diskette with a capacity of at least 1.4 megabytes. Captured data, for the ingredients represented by each batch shall be "line feed, carriage return" (LFCR) and "one line, separate record" with allowances for sufficient fields to satisfy the amount of data required by these specifications.
- The Contractor may furnish a weighmaster certificate accompanied by a separate certificate that lists the actual batch masses or measurements for a load of concrete provided that both certificates are imprinted with the same non-repeating load number that is unique to the contract and delivered to the jobsite with the load.
- Weighmaster certificates furnished by the Contractor shall conform to the provisions in Section 9-1.01, "Measurement of Quantities."

### **90-6.04 TIME OR AMOUNT OF MIXING**

- Mixing of concrete in paving or stationary mixers shall continue for the required mixing time after all ingredients, except water and admixture, if added with the water, are in the mixing compartment of the mixer before any part of the batch is released. Transfer time in multiple drum mixers shall not be counted as part of the required mixing time.

- The required mixing time, in paving or stationary mixers, of concrete used for concrete structures, except minor structures, shall be not less than 90 seconds or more than 5 minutes, except that when directed by the Engineer in writing, the requirements of the following paragraph shall apply.
- The required mixing time, in paving or stationary mixers, except as provided in the preceding paragraph, shall be not less than 50 seconds or more than 5 minutes.
- The minimum required revolutions at the mixing speed for transit-mixed concrete shall not be less than that recommended by the mixer manufacturer, but in no case shall the number of revolutions be less than that required to consistently produce concrete conforming to the provisions for uniformity in Section 90-6.01, "General."

**90-6.05 HAND-MIXING**

- Hand-mixed concrete shall be made in batches of not more than 0.25 m<sup>3</sup> and shall be mixed on a watertight, level platform. The proper amount of coarse aggregate shall be measured in measuring boxes and spread on the platform and the fine aggregate shall be spread on this layer, the 2 layers being not more than 0.3 meters in total depth. On this mixture shall be spread the dry cement and mineral admixture and the whole mass turned no fewer than 2 times dry; then sufficient clean water shall be added, evenly distributed, and the whole mass again turned no fewer than 3 times, not including placing in the carriers or forms.

**90-6.06 AMOUNT OF WATER AND PENETRATION**

- The amount of water used in concrete mixes shall be regulated so that the penetration of the concrete as determined by California Test 533 or the slump of the concrete as determined by ASTM Designation: C 143 is within the "Nominal" values shown in the following table. When the penetration or slump of the concrete is found to exceed the nominal values listed, the mixture of subsequent batches shall be adjusted to reduce the penetration or slump to a value within the nominal range shown. Batches of concrete with a penetration or slump exceeding the maximum values listed shall not be used in the work. When Type F or Type G chemical admixtures are added to the mix, the penetration requirements shall not apply and the slump shall not exceed 225 mm after the chemical admixtures are added.

Type of Work	Nominal		Maximum	
	Penetration (mm)	Slump (mm)	Penetration (mm)	Slump (mm)
Concrete Pavement	0-25	—	40	—
Non-reinforced concrete facilities	0-35	—	50	—
Reinforced concrete structures				
Sections over 300-mm thick	0-35	—	65	—
Sections 300-mm thick or less	0-50	—	75	—
Concrete placed under water	—	150-200	—	225
Cast-in-place concrete piles	65-90	130-180	100	200

- The amount of free water used in concrete shall not exceed 183 kg/m<sup>3</sup>, plus 20 kg for each required 100 kg of cementitious material in excess of 325 kg/m<sup>3</sup>.
- The term free water is defined as the total water in the mixture minus the water absorbed by the aggregates in reaching a saturated surface-dry condition.
- Where there are adverse or difficult conditions that affect the placing of concrete, the above specified penetration and free water content limitations may be exceeded providing the Contractor is granted permission by the Engineer in writing to increase the cementitious material content per cubic meter of concrete. The increase in water and cementitious material shall be at a ratio not to exceed 30 kg of water per added 100 kg of cementitious material per cubic meter. The cost of additional cementitious material and water added under these conditions shall be at the Contractor's expense and no additional compensation will be allowed therefor.
- The equipment for supplying water to the mixer shall be constructed and arranged so that the amount of water added can be measured accurately. Any method of discharging water into the mixer for a batch shall be accurate within 1.5 percent of the quantity of water required to be added to the mix for any position of the mixer. Tanks used to measure water shall be designed so that water cannot enter while water is being discharged into the mixer and discharge into the mixer shall be made rapidly in one operation without dribbling. All equipment shall be arranged so as to permit checking the amount of water delivered by discharging into measured containers.

**90-7 CURING CONCRETE**

## 90-7.01 METHODS OF CURING

- Newly placed concrete shall be cured by the methods specified in this Section 90-7.01 and the special provisions.

### 90-7.01A Water Method

- The concrete shall be kept continuously wet by the application of water for a minimum curing period of 7 days after the concrete has been placed.
  - When a curing medium consisting of cotton mats, rugs, carpets, or earth or sand blankets is to be used to retain the moisture, the entire surface of the concrete shall be kept damp by applying water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. The moisture from the nozzle shall not be applied under pressure directly upon the concrete and shall not be allowed to accumulate on the concrete in a quantity sufficient to cause a flow or wash the surface. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing mediums.
    - When concrete bridge decks and flat slabs are to be cured without the use of a curing medium, the entire surface of the bridge deck or slab shall be kept damp by the application of water with an atomizing nozzle as specified in the preceding paragraph, until the concrete has set, after which the entire surface of the concrete shall be sprinkled continuously with water for a period of not less than 7 days.

### 90-7.01B Curing Compound Method

- Surfaces of the concrete that are exposed to the air shall be sprayed uniformly with a curing compound.
- Curing compounds to be used shall be as follows:
  1. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B, except the resin type shall be poly-alpha-methylstyrene.
  2. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B.
  3. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class A.
  4. Non-pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class B.
  5. Non-pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class A.
  6. Non-pigmented curing compound with fugitive dye conforming to the requirements in ASTM Designation: C 309, Type 1-D, Class A.
- The infrared scan for the dried vehicle from curing compound (1) shall match the infrared scan on file at the Transportation Laboratory.
  - The loss of water for each type of curing compound, when tested in conformance with the requirements in California Test 534, shall not be more than 0.15-kg/m<sup>2</sup> in 24 hours or more than 0.45-kg/m<sup>2</sup> in 72 hours.
  - The curing compound to be used will be specified elsewhere in these specifications or in the special provisions.
  - When the use of curing compound is required or permitted elsewhere in these specifications or in the special provisions and no specific kind is specified, any of the curing compounds listed above may be used.
    - Curing compound shall be applied at a nominal rate of 3.7 m<sup>2</sup>/L, unless otherwise specified.
    - At any point, the application rate shall be within ±1.2 m<sup>2</sup>/L of the nominal rate specified, and the average application rate shall be within ±0.5 m<sup>2</sup>/L of the nominal rate specified when tested in conformance with the requirements in California Test 535. Runs, sags, thin areas, skips, or holidays in the applied curing compound shall be evidence that the application is not satisfactory.
    - Curing compounds shall be applied using power operated spray equipment. The power operated spraying equipment shall be equipped with an operational pressure gage and a means of controlling the pressure. Hand spraying of small and irregular areas that are not reasonably accessible to mechanical spraying equipment, in the opinion of the Engineer, may be permitted.
      - The curing compound shall be applied to the concrete following the surface finishing operation, immediately before the moisture sheen disappears from the surface, but before any drying shrinkage or craze cracks begin to appear. In the event of any drying or cracking of the surface, application of water with an atomizing nozzle as specified in Section 90-7.01A, "Water Method," shall be started immediately and shall be continued until application of the compound is resumed or started; however, the compound shall not be applied over any resulting freestanding water. Should the film of compound be damaged from any cause before the expiration of 7 days after the concrete is placed in the case of structures and 72 hours in the case of pavement, the damaged portion shall be repaired immediately with additional compound.
        - At the time of use, compounds containing pigments shall be in a thoroughly mixed condition with the pigment uniformly dispersed throughout the vehicle. A paddle shall be used to loosen all settled pigment from the bottom of the container, and a power driven agitator shall be used to disperse the pigment uniformly throughout the vehicle.
          - Agitation shall not introduce air or other foreign substance into the curing compound.

- The manufacturer shall include in the curing compound the necessary additives for control of sagging, pigment settling, leveling, de-emulsification, or other requisite qualities of a satisfactory working material. Pigmented curing compounds shall be manufactured so that the pigment does not settle badly, does not cake or thicken in the container, and does not become granular or curdled. Settlement of pigment shall be a thoroughly wetted, soft, mushy mass permitting the complete and easy vertical penetration of a paddle. Settled pigment shall be easily redispersed, with minimum resistance to the sideways manual motion of the paddle across the bottom of the container, to form a smooth uniform product of the proper consistency.

- Curing compounds shall remain sprayable at temperatures above 4°C and shall not be diluted or altered after manufacture.

- The curing compound shall be packaged in clean 210-L barrels or round 19-L containers or shall be supplied from a suitable storage tank located at the jobsite. The containers shall comply with "Title 49, Code of Federal Regulations, Hazardous Materials Regulations." The 210-L barrels shall have removable lids and airtight fasteners. The 19-L containers shall be round and have standard full open head and bail. Lids with bungholes shall not be permitted. On-site storage tanks shall be kept clean and free of contaminants. Each tank shall have a permanent system designed to completely redisperse settled material without introducing air or other foreign substances.

- Steel containers and lids shall be lined with a coating that will prevent destructive action by the compound or chemical agents in the air space above the compound. The coating shall not come off the container or lid as skins. Containers shall be filled in a manner that will prevent skinning. Plastic containers shall not react with the compound.

- Each container shall be labeled with the manufacturer's name, kind of curing compound, batch number, volume, date of manufacture, and volatile organic compound (VOC) content. The label shall also warn that the curing compound containing pigment shall be well stirred before use. Precautions concerning the handling and the application of curing compound shall be shown on the label of the curing compound containers in conformance with the Construction Safety Orders and General Industry Safety Orders of the State of California.

- Containers of curing compound shall be labeled to indicate that the contents fully comply with the rules and regulations concerning air pollution control in the State of California.

- When the curing compound is shipped in tanks or tank trucks, a shipping invoice shall accompany each load. The invoice shall contain the same information as that required herein for container labels.

- Curing compound will be sampled by the Engineer at the source of supply or at the jobsite or at both locations.

- Curing compound shall be formulated so as to maintain the specified properties for a minimum of one year. The Engineer may require additional testing before use to determine compliance with these specifications if the compound has not been used within one year or whenever the Engineer has reason to believe the compound is no longer satisfactory.

- Tests will be conducted in conformance with the latest ASTM test methods and methods in use by the Transportation Laboratory.

#### **90-7.01C Waterproof Membrane Method**

- The exposed finished surfaces of concrete shall be sprayed with water, using a nozzle that so atomizes the flow that a mist and not a spray is formed, until the concrete has set, after which the curing membrane shall be placed. The curing membrane shall remain in place for a period of not less than 72 hours.

- Sheeting material for curing concrete shall conform to the requirements in AASHTO Designation: M 171 for white reflective materials.

- The sheeting material shall be fabricated into sheets of such width as to provide a complete cover for the entire concrete surface. Joints in the sheets shall be securely cemented together in such a manner as to provide a waterproof joint. The joint seams shall have a minimum lap of 100 mm.

- The sheets shall be securely weighted down by placing a bank of earth on the edges of the sheets or by other means satisfactory to the Engineer.

- Should any portion of the sheets be broken or damaged before the expiration of 72 hours after being placed, the broken or damaged portions shall be immediately repaired with new sheets properly cemented into place.

- Sections of membrane that have lost their waterproof qualities or have been damaged to such an extent as to render them unfit for curing the concrete shall not be used.

#### **90-7.01D Forms-In-Place Method**

- Formed surfaces of concrete may be cured by retaining the forms in place. The forms shall remain in place for a minimum period of 7 days after the concrete has been placed, except that for members over 0.5-m in least dimension the forms shall remain in place for a minimum period of 5 days.

- Joints in the forms and the joints between the end of forms and concrete shall be kept moisture tight during the curing period. Cracks in the forms and cracks between the forms and the concrete shall be resealed by methods subject to the approval of the Engineer.

### **90-7.02 CURING PAVEMENT**

- The entire exposed area of the pavement, including edges, shall be cured by the waterproof membrane method, or curing compound method using curing compound (1) or (2) as the Contractor may elect. Should the side forms be removed before the expiration of 72 hours following the start of curing, the exposed pavement edges shall also be cured. If the pavement is cured by means of the curing compound method, the sawcut and all portions of the curing compound that have been disturbed by sawing operations shall be restored by spraying with additional curing compound.

- Curing shall commence as soon as the finishing process provided in Section 40-1.10, "Final Finishing," has been completed. The method selected shall conform to the provisions in Section 90-7.01, "Methods of Curing."

- When the curing compound method is used, the compound shall be applied to the entire pavement surface by mechanical sprayers. Spraying equipment shall be of the fully atomizing type equipped with a tank agitator that provides for continual agitation of the curing compound during the time of application. The spray shall be adequately protected against wind, and the nozzles shall be so oriented or moved mechanically transversely as to result in the minimum specified rate of coverage being applied uniformly on exposed faces. Hand spraying of small and irregular areas, and areas inaccessible to mechanical spraying equipment, in the opinion of the Engineer, will be permitted. When the ambient air temperature is above 15°C, the Contractor shall fog the surface of the concrete with a fine spray of water as specified in Section 90-7.01A, "Water Method." The surface of the pavement shall be kept moist between the hours of 10:00 a.m. and 4:30 p.m. on the day the concrete is placed. However, the fogging done after the curing compound has been applied shall not begin until the compound has set sufficiently to prevent displacement. Fogging shall be discontinued if ordered in writing by the Engineer.

### **90-7.03 CURING STRUCTURES**

- Newly placed concrete for cast-in-place structures, other than highway bridge decks, shall be cured by the water method, the forms-in-place method, or, as permitted herein, by the curing compound method, in conformance with the provisions in Section 90-7.01, "Methods of Curing."

- The curing compound method using a pigmented curing compound may be used on concrete surfaces of construction joints, surfaces that are to be buried underground, and surfaces where only Ordinary Surface Finish is to be applied and on which a uniform color is not required and that will not be visible from a public traveled way. If the Contractor elects to use the curing compound method on the bottom slab of box girder spans, the curing compound shall be curing compound (1).

- The top surface of highway bridge decks shall be cured by both the curing compound method and the water method. The curing compound shall be curing compound (1).

- Concrete surfaces of minor structures, as defined in Section 51-1.02, "Minor Structures," shall be cured by the water method, the forms-in-place method or the curing compound method.

- When deemed necessary by the Engineer during periods of hot weather, water shall be applied to concrete surfaces being cured by the curing compound method or by the forms-in-place method, until the Engineer determines that a cooling effect is no longer required. Application of water for this purpose will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."

### **90-7.04 CURING PRECAST CONCRETE MEMBERS**

- Precast concrete members shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing." Curing shall be provided for the minimum time specified for each method or until the concrete reaches its design strength, whichever is less. Steam curing may also be used for precast members and shall conform to the following provisions:

- A. After placement of the concrete, members shall be held for a minimum 4-hour presteaming period. If the ambient air temperature is below 10°C, steam shall be applied during the presteaming period to hold the air surrounding the member at a temperature between 10°C and 32°C.
- B. To prevent moisture loss on exposed surfaces during the presteaming period, members shall be covered as soon as possible after casting or the exposed surfaces shall be kept wet by fog spray or wet blankets.
- C. Enclosures for steam curing shall allow free circulation of steam about the member and shall be constructed to contain the live steam with a minimum moisture loss. The use of tarpaulins or similar flexible covers will be permitted, provided they are kept in good repair and secured in such a manner as to prevent the loss of steam and moisture.
- D. Steam at the jets shall be at low pressure and in a saturated condition. Steam jets shall not impinge directly on the concrete, test cylinders, or forms. During application of the steam, the temperature rise within the enclosure shall not exceed 22°C per hour. The curing temperature throughout the enclosure shall not exceed 65°C and shall be maintained at a constant level for a sufficient time necessary to develop the required transfer strength. Control

cylinders shall be covered to prevent moisture loss and shall be placed in a location where temperature is representative of the average temperature of the enclosure.

- E. Temperature recording devices that will provide an accurate, continuous, permanent record of the curing temperature shall be provided. A minimum of one temperature recording device per 60 m of continuous bed length will be required for checking temperature.
- F. Members in pretension beds shall be detensioned immediately after the termination of steam curing while the concrete and forms are still warm, or the temperature under the enclosure shall be maintained above 15°C until the stress is transferred to the concrete.
- G. Curing of precast concrete will be considered completed after termination of the steam curing cycle.

#### **90-7.05 CURING PRECAST PRESTRESSED CONCRETE PILES**

- Newly placed concrete for precast prestressed concrete piles shall be cured in conformance with the provisions in Section 90-7.04, "Curing Precast Concrete Members," except that piles with a class designation ending in C (corrosion resistant) shall be cured as follows:

- A. Piles shall be either steam cured or water cured. If water curing is used, the piles shall be kept continuously wet by the application of water in conformance with the provisions in Section 90-7.01A, "Water Method."
- B. If steam curing is used, the steam curing provisions in Section 90-7.04, "Curing Precast Concrete Members," shall apply except that the piles shall be kept continuously wet for their entire length for a period of not less than 3 days, including the holding and steam curing periods.

#### **90-7.06 CURING SLOPE PROTECTION**

- Concrete slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."
- Concreted-rock slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing," or with a blanket of earth kept wet for 72 hours, or by sprinkling with a fine spray of water every 2 hours during the daytime for a period of 3 days.

#### **90-7.07 CURING MISCELLANEOUS CONCRETE WORK**

- Exposed surfaces of curbs shall be cured by pigmented curing compounds as specified in Section 90-7.01B, "Curing Compound Method."
- Concrete sidewalks, gutter depressions, island paving, curb ramps, driveways, and other miscellaneous concrete areas shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."
- Shotcrete shall be cured for at least 72 hours by spraying with water, or by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."
- Mortar and grout shall be cured by keeping the surface damp for 3 days.
- After placing, the exposed surfaces of sign structure foundations, including pedestal portions, if constructed, shall be cured for at least 72 hours by spraying with water, or by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

### **90-8 PROTECTING CONCRETE**

#### **90-8.01 GENERAL**

- In addition to the provisions in Section 7-1.16, "Contractor's Responsibility for the Work and Materials," the Contractor shall protect concrete as provided in this Section 90-8.
- Concrete shall not be placed on frozen or ice-coated ground or subgrade nor on ice-coated forms, reinforcing steel, structural steel, conduits, precast members, or construction joints.
- Under rainy conditions, placing of concrete shall be stopped before the quantity of surface water is sufficient to damage surface mortar or cause a flow or wash of the concrete surface, unless the Contractor provides adequate protection against damage.
- Concrete that has been frozen or damaged by other causes, as determined by the Engineer, shall be removed and replaced by the Contractor at the Contractor's expense.

## **90-8.02 PROTECTING CONCRETE STRUCTURES**

- Structure concrete and shotcrete used as structure concrete shall be maintained at a temperature of not less than 7°C for 72 hours after placing and at not less than 4°C for an additional 4 days. When required by the Engineer, the Contractor shall submit a written outline of the proposed methods for protecting the concrete.

## **90-8.03 PROTECTING CONCRETE PAVEMENT**

- Pavement concrete shall be maintained at a temperature of not less than 4°C for 72 hours. When required by the Engineer, the Contractor shall submit a written outline of the proposed methods for protecting the concrete.

- Except as provided in Section 7-1.08, "Public Convenience," the Contractor shall protect concrete pavement against construction and other activities that abrade, scar, discolor, reduce texture depth, lower coefficient of friction, or otherwise damage the surface. Stockpiling, drifting, or excessive spillage of soil, gravel, petroleum products, and concrete or asphalt mixes on the surface of concrete pavement is prohibited unless otherwise specified in these specifications, the special provisions or permitted by the Engineer.

- When ordered by the Engineer or shown on the plans or specified in the special provisions, pavement crossings shall be constructed for the convenience of public traffic. The material and work necessary for the construction of the crossings, and their subsequent removal and disposal, will be paid for at the contract unit prices for the items of work involved and if there are no contract items for the work involved, payment for pavement crossings will be made by extra work as provided in Section 4-1.03D, "Extra Work.". Where public traffic will be required to cross over the new pavement, Type III portland cement may be used in concrete, if permitted in writing by the Engineer. The pavement may be opened to traffic as soon as the concrete has developed a modulus of rupture of 3.8 MPa. The modulus of rupture will be determined by California Test 523.

- No traffic or Contractor's equipment, except as hereinafter provided, will be permitted on the pavement before a period of 10 days has elapsed after the concrete has been placed, nor before the concrete has developed a modulus of rupture of at least 3.8 MPa. Concrete that fails to attain a modulus of rupture of 3.8 MPa within 10 days shall not be opened to traffic until directed by the Engineer.

- Equipment for sawing weakened plane joints will be permitted on the pavement as specified in Section 40-1.08B, "Weakened Plane Joints."

- When requested in writing by the Contractor, the tracks on one side of paving equipment will be permitted on the pavement after a modulus of rupture of 2.4 MPa has been attained, provided that:

- A. Unit pressure exerted on the pavement by the paver shall not exceed 135 kPa;
- B. Tracks with cleats, grousers, or similar protuberances shall be modified or shall travel on planks or equivalent protective material, so that the pavement is not damaged; and
- C. No part of the track shall be closer than 0.3-m from the edge of pavement.

- In case of visible cracking of, or other damage to the pavement, operation of the paving equipment on the pavement shall be immediately discontinued.

- Damage to the pavement resulting from early use of pavement by the Contractor's equipment as provided above shall be repaired by the Contractor at the Contractor's expense.

- The State will furnish the molds and machines for testing the concrete for modulus of rupture, and the Contractor, at the Contractor's expense, shall furnish the material and whatever labor the Engineer may require.

## **90-9 COMPRESSIVE STRENGTH**

### **90-9.01 GENERAL**

- Concrete compressive strength requirements consist of a minimum strength that shall be attained before various loads or stresses are applied to the concrete and, for concrete designated by strength, a minimum strength at the age of 28 days or at the age otherwise allowed in Section 90-1.01, "Description." The various strengths required are specified in these specifications or the special provisions or are shown on the plans.

- The compressive strength of concrete will be determined from test cylinders that have been fabricated from concrete sampled in conformance with the requirements of California Test 539. Test cylinders will be molded and initially field cured in conformance with California Test 540. Test cylinders will be cured and tested after receipt at the testing laboratory in conformance with the requirements of California Test 521. A strength test shall consist of the average strength of 2 cylinders fabricated from material taken from a single load of concrete, except that, if any cylinder should show evidence of improper sampling, molding, or testing, that cylinder shall be discarded and the strength test shall consist of the strength of the remaining cylinder.

- When concrete compressive strength is specified as a prerequisite to applying loads or stresses to a concrete structure or member, test cylinders for other than steam cured concrete will be cured in conformance with Method 1 of California Test 540. The compressive strength of concrete determined for these purposes will be evaluated on the basis of individual tests.

- When concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete strength to be used as a basis for acceptance of other than steam cured concrete will be determined from cylinders cured in conformance with Method 1 of California Test 540. If the result of a single compressive strength test at the maximum age specified or allowed is below the specified strength but is 95 percent or more of the specified strength, the Contractor shall, at the Contractor's expense, make corrective changes, subject to approval of the Engineer, in the mix proportions or in the concrete fabrication procedures, before placing additional concrete, and shall pay to the State \$14 for each in-place cubic meter of concrete represented by the deficient test. If the result of a single compressive strength test at the maximum age specified or allowed is below 95 percent of the specified strength, but is 85 percent or more of the specified strength, the Contractor shall make the corrective changes specified above, and shall pay to the State \$20 for each in place cubic meter of concrete represented by the deficient test. In addition, such corrective changes shall be made when the compressive strength of concrete tested at 7 days indicates, in the judgment of the Engineer, that the concrete will not attain the required compressive strength at the maximum age specified or allowed. Concrete represented by a single test that indicates a compressive strength of less than 85 percent of the specified 28-day compressive strength will be rejected in conformance with the provisions in Section 6-1.04, "Defective Materials."

- If the test result indicates that the compressive strength at the maximum curing age specified or allowed is below the specified strength, but is 85 percent or more of the specified strength, payments to the State as required above shall be made, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength of the concrete placed in the work meets or exceeds the specified 28-day compressive strength. If the test result indicates a compressive strength at the maximum curing age specified or allowed below 85 percent, the concrete represented by that test will be rejected, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength and quality of the concrete placed in the work are acceptable. If the evidence consists of tests made on cores taken from the work, the cores shall be obtained and tested in conformance with the requirements in ASTM Designation: C 42.

- No single compressive strength test shall represent more than 250 m<sup>3</sup>.

- When a precast concrete member is steam cured, the compressive strength of the concrete will be determined from test cylinders that have been handled and stored in conformance with Method 3 of California Test 540. The compressive strength of steam cured concrete will be evaluated on the basis of individual tests representing specific portions of production. When the concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete shall be considered to be acceptable whenever its compressive strength reaches the specified 28-day compressive strength provided that strength is reached in not more than the maximum number of days specified or allowed after the member is cast.

- When concrete is specified by compressive strength, prequalification of materials, mix proportions, mixing equipment, and procedures proposed for use will be required prior to placement of the concrete. Prequalification shall be accomplished by the submission of acceptable certified test data or trial batch reports by the Contractor. Prequalification data shall be based on the use of materials, mix proportions, mixing equipment, procedures, and size of batch proposed for use in the work.

- Certified test data, in order to be acceptable, shall indicate that not less than 90 percent of at least 20 consecutive tests exceed the specified strength at the maximum number of cure days specified or allowed, and none of those tests are less than 95 percent of specified strength. Strength tests included in the data shall be the most recent tests made on concrete of the proposed mix design and all shall have been made within one year of the proposed use of the concrete.

- Trial batch test reports, in order to be acceptable, shall indicate that the average compressive strength of 5 consecutive concrete cylinders, taken from a single batch, at not more than 28 days (or the maximum age allowed) after molding shall be at least 4 MPa greater than the specified 28-day compressive strength, and no individual cylinder shall have a strength less than the specified strength at the maximum age specified or allowed. Data contained in the report shall be from trial batches that were produced within one year of the proposed use of specified strength concrete in the project. Whenever air-entrainment is required, the air content of trial batches shall be equal to or greater than the air content specified for the concrete without reduction due to tolerances.

- Tests shall be performed in conformance with either the appropriate California Test methods or the comparable ASTM test methods. Equipment employed in testing shall be in good condition and shall be properly calibrated. If the tests are performed during the life of the contract, the Engineer shall be notified sufficiently in advance of performing the tests in order to witness the test procedures.

- The certified test data and trial batch test reports shall include the following information:

- A. Date of mixing.

- B. Mixing equipment and procedures used.
- C. The size of batch in cubic meters and the mass, type, and source of all ingredients used.
- D. Penetration of the concrete.
- E. The air content of the concrete if an air-entraining admixture is used.
- F. The age at time of testing and strength of all concrete cylinders tested.

- Certified test data and trial batch test reports shall be signed by an official of the firm that performed the tests.
- When approved by the Engineer, concrete from trial batches may be used in the work at locations where concrete of a lower quality is required and the concrete will be paid for as the type or class of concrete required at that location.
  - After materials, mix proportions, mixing equipment, and procedures for concrete have been prequalified for use, additional prequalification by testing of trial batches will be required prior to making changes that, in the judgment of the Engineer, could result in a strength of concrete below that specified.
    - The Contractor's attention is directed to the time required to test trial batches and the Contractor shall be responsible for production of trial batches at a sufficiently early date so that the progress of the work is not delayed.
    - When precast concrete members are manufactured at the plant of an established manufacturer of precast concrete members, the mix proportions of the concrete shall be determined by the Contractor, and a trial batch and prequalification of the materials, mix proportions, mixing equipment, and procedures will not be required.

## **90-10 MINOR CONCRETE**

### **90-10.01 GENERAL**

- Concrete for minor structures, slope paving, curbs, sidewalks and other concrete work, when designated as minor concrete on the plans, in the specifications, or in the contract item, shall conform to the provisions specified herein.
- The Engineer, at the Engineer's discretion, will inspect and test the facilities, materials and methods for producing the concrete to ensure that minor concrete of the quality suitable for use in the work is obtained.

### **90-10.02 MATERIALS**

- Minor concrete shall conform to the following requirements:

#### **90-10.02A Cementitious Material**

- Cementitious material shall conform to the provisions in Section 90-1.01, "Description."

#### **90-10.02B Aggregate**

- Aggregate shall be clean and free from deleterious coatings, clay balls, roots, and other extraneous materials.
- The Contractor shall submit to the Engineer for approval, a grading of the combined aggregate proposed for use in the minor concrete. After acceptance of the grading, aggregate furnished for minor concrete shall conform to that grading, unless a change is authorized in writing by the Engineer.
  - The Engineer may require the Contractor to furnish periodic test reports of the aggregate grading furnished. The maximum size of aggregate used shall be at the option of the Contractor, but in no case shall the maximum size be larger than 37.5 mm or smaller than 19 mm.
  - The Engineer may waive, in writing, the gradation requirements in this Section 90-10.02B, if, in the Engineer's opinion, the furnishing of the gradation is not necessary for the type or amount of concrete work to be constructed.

#### **90-10.02C Water**

- Water used for washing, mixing, and curing shall be free from oil, salts, and other impurities that would discolor or etch the surface or have an adverse affect on the quality of the concrete.

#### **90-10.02D Admixtures**

- The use of admixtures shall conform to the provisions in Section 90-4, "Admixtures."

### **90-10.03 PRODUCTION**

- Cementitious material, water, aggregate, and admixtures shall be stored, proportioned, mixed, transported, and discharged in conformance with recognized standards of good practice that will result in concrete that is thoroughly and uniformly mixed, that is suitable for the use intended, and that conforms to requirements specified herein. Recognized

standards of good practice are outlined in various industry publications such as are issued by American Concrete Institute, AASHTO, or the Department.

- The cementitious material content of minor concrete shall conform to the provisions in Section 90-1.01, "Description."

- The amount of water used shall result in a consistency of concrete conforming to the provisions in Section 90-6.06, "Amount of Water and Penetration." Additional mixing water shall not be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer.

- Discharge of ready-mixed concrete from the transporting vehicle shall be made while the concrete is still plastic and before stiffening occurs. An elapsed time of 1.5 hours (one hour in non-agitating hauling equipment), or more than 250 revolutions of the drum or blades, after the introduction of the cementitious material to the aggregates, or a temperature of concrete of more than 32°C will be considered conditions contributing to the quick stiffening of concrete. The Contractor shall take whatever action is necessary to eliminate quick stiffening, except that the addition of water will not be permitted.

- The required mixing time in stationary mixers shall be not less than 50 seconds or more than 5 minutes.

- The minimum required revolutions at mixing speed for transit-mixed concrete shall be not less than that recommended by the mixer manufacturer, and shall be increased, if necessary, to produce thoroughly and uniformly mixed concrete.

- Each load of ready-mixed concrete shall be accompanied by a weighmaster certificate that shall be delivered to the Engineer at the discharge location of the concrete, unless otherwise directed by the Engineer. The weighmaster certificate shall be clearly marked with the date and time of day when the load left the batching plant and, if hauled in truck mixers or agitators, the time the mixing cycle started.

- A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall be furnished to the Engineer, prior to placing minor concrete from a source not previously used on the contract, stating that minor concrete to be furnished meets contract requirements, including minimum cementitious material content specified.

#### **90-10.04 CURING MINOR CONCRETE**

- Curing minor concrete shall conform to the provisions in Section 90-7, "Curing Concrete."

#### **90-10.05 PROTECTING MINOR CONCRETE**

- Protecting minor concrete shall conform to the provisions in Section 90-8, "Protecting Concrete," except the concrete shall be maintained at a temperature of not less than 4°C for 72 hours after placing.

#### **90-10.06 MEASUREMENT AND PAYMENT**

- Minor concrete will be measured and paid for in conformance with the provisions specified in the various sections of these specifications covering concrete construction when minor concrete is specified in the specifications, shown on the plans, or indicated by contract item in the Engineer's Estimate.

### **90-11 MEASUREMENT AND PAYMENT**

#### **90-11.01 MEASUREMENT**

- Portland cement concrete will be measured in conformance with the provisions specified in the various sections of these specifications covering construction requiring concrete.

- When it is provided that concrete will be measured at the mixer, the volume in cubic meters shall be computed as the total mass of the batch in kilograms divided by the density of the concrete in kilograms per cubic meter. The total mass of the batch shall be calculated as the sum of all materials, including water, entering the batch. The density of the concrete will be determined in conformance with the requirements in California Test 518.

#### **90-11.02 PAYMENT**

- Portland cement concrete will be paid for in conformance with the provisions specified in the various sections of these specifications covering construction requiring concrete.

- Full compensation for furnishing and incorporating admixtures required by these specifications or the special provisions will be considered as included in the contract prices paid for the concrete involved and no additional compensation will be allowed therefor.

- Should the Engineer order the Contractor to incorporate any admixtures in the concrete when their use is not required by these specifications or the special provisions, furnishing the admixtures and adding them to the concrete will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."

- Should the Contractor use admixtures in conformance with the provisions in Section 90-4.05, "Optional Use of Chemical Admixtures," or Section 90-4.07, "Optional Use of Air-entraining Admixtures," or should the Contractor request and obtain permission to use other admixtures for the Contractor's benefit, the Contractor shall furnish those admixtures and incorporate them into the concrete at the Contractor's expense and no additional compensation will be allowed therefor.

## **END OF AMENDMENTS**

### **SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS**

#### **2-1.01 GENERAL**

The bidder's attention is directed to the provisions in Section 2, "Proposal Requirements and Conditions," of the Standard Specifications and these special provisions for the requirements and conditions which the bidder must observe in the preparation of the Proposal form and the submission of the bid.

In addition to the subcontractors required to be listed in conformance with Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications, each proposal shall have listed therein the portion of work that will be performed by each subcontractor listed.

The Bidder's Bond form mentioned in the last paragraph in Section 2-1.07, "Proposal Guaranty," of the Standard Specifications will be found following the signature page of the Proposal.

Submit request for substitution of an "or equal" item, and the data substantiating the request to the Department of Transportation, Construction Division Chief, 801 South Grand Avenue, 4th Floor, Los Angeles, CA 90017, so that the request is received by the Department by close of business on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening.

In conformance with Public Contract Code Section 7106, a Noncollusion Affidavit is included in the Proposal. Signing the Proposal shall also constitute signature of the Noncollusion Affidavit.

The contractor, sub recipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate. Each subcontract signed by the bidder must include this assurance.

#### **2-1.015 FEDERAL LOBBYING RESTRICTIONS**

Section 1352, Title 31, United States Code prohibits Federal funds from being expended by the recipient or any lower tier subrecipient of a Federal-aid contract to pay for any person for influencing or attempting to influence a Federal agency or Congress in connection with the awarding of any Federal-aid contract, the making of any Federal grant or loan, or the entering into of any cooperative agreement.

If any funds other than Federal funds have been paid for the same purposes in connection with this Federal-aid contract, the recipient shall submit an executed certification and, if required, submit a completed disclosure form as part of the bid documents.

A certification for Federal-aid contracts regarding payment of funds to lobby Congress or a Federal agency is included in the Proposal. Standard Form - LLL, "Disclosure of Lobbying Activities," with instructions for completion of the Standard Form is also included in the Proposal. Signing the Proposal shall constitute signature of the Certification.

The above-referenced certification and disclosure of lobbying activities shall be included in each subcontract and any lower-tier contracts exceeding \$100,000. All disclosure forms, but not certifications, shall be forwarded from tier to tier until received by the Engineer.

The Contractor, subcontractors and any lower-tier contractors shall file a disclosure form at the end of each calendar quarter in which there occurs any event that requires disclosure or that materially affects the accuracy of the information contained in any disclosure form previously filed by the Contractor, subcontractors and any lower-tier contractors. An event that materially affects the accuracy of the information reported includes:

- A. A cumulative increase of \$25,000 or more in the amount paid or expected to be paid for influencing or attempting to influence a covered Federal action; or
- B. A change in the person(s) or individual(s) influencing or attempting to influence a covered Federal action; or,
- C. A change in the officer(s), employee(s), or Member(s) contacted to influence or attempt to influence a covered Federal action.

## 2-1.02 DISADVANTAGED BUSINESS ENTERPRISE (DBE)

This project is subject to Part 26, Title 49, Code of Federal Regulations entitled "Participation by Disadvantaged Business Enterprises in Department of Transportation Financial Assistance Programs." The Regulations in their entirety are incorporated herein by this reference.

Bidders shall be fully informed respecting the requirements of the Regulations and the Department's Disadvantaged Business Enterprise (DBE) program developed pursuant to the Regulations; particular attention is directed to the following matters:

- A. A DBE must be a small business concern as defined pursuant to Section 3 of U.S. Small Business Act and relevant regulations promulgated pursuant thereto.
- B. A DBE may participate as a prime contractor, subcontractor, joint venture partner with a prime or subcontractor, vendor of material or supplies, or as a trucking company.
- C. A DBE bidder, not bidding as a joint venture with a non-DBE, will be required to document one or a combination of the following:
  1. The bidder will meet the goal by performing work with its own forces.
  2. The bidder will meet the goal through work performed by DBE subcontractors, suppliers or trucking companies.
  3. The bidder, prior to bidding, made adequate good faith efforts to meet the goal.
- D. A DBE joint venture partner must be responsible for specific contract items of work, or portions thereof. Responsibility means actually performing, managing and supervising the work with its own forces. The DBE joint venture partner must share in the capital contribution, control, management, risks and profits of the joint venture. The DBE joint venturer must submit the joint venture agreement with the proposal or the DBE Information form required in the Section entitled "Submission of DBE Information" of these special provisions.
- E. A DBE must perform a commercially useful function, i.e., must be responsible for the execution of a distinct element of the work and must carry out its responsibility by actually performing, managing and supervising the work.
- F. DBEs must be certified by either the California Department of Transportation, or by a participating State of California or local agency which certifies in conformance with Title 49, Code of Federal Regulations, Part 26, as of the date of bid opening. It is the Contractor's responsibility to verify that DBEs are certified. Listings of DBEs certified by the Department are available from the following sources:
  1. The Department's DBE Directory, which is published quarterly. This Directory may be obtained from the Department of Transportation, Materiel Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520.
  2. The Department's Electronic Information Bulletin Board Service, which is accessible by modem and is updated weekly. The Bulletin Board may be accessed by first contacting the Department's Business Enterprise Program at Telephone: (916) 324-1097 and obtaining a user identification and password.
  3. The Department's web site at <http://www.dot.ca.gov/hq/bep/index.htm>.
  4. The organizations listed in the Section entitled "DBE Goal for this Project" of these special provisions.
- G. Credit for materials or supplies purchased from DBEs will be as follows:
  1. If the materials or supplies are obtained from a DBE manufacturer, 100 percent of the cost of the materials or supplies will count toward the DBE goal. A DBE manufacturer is a firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract and of the general character described by the specifications.
  2. If the materials or supplies are purchased from a DBE regular dealer, 60 percent of the cost of the materials or supplies will count toward the DBE goal. A DBE regular dealer is a firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles or equipment of the general character described by the specifications and required under the contract are bought, kept in stock, and regularly sold or leased to the public in the usual course of business. To be a DBE regular dealer, the firm must be an established, regular business that engages, as its principal business and under its own name, in the purchase and sale or lease of the products in question. A person may be a DBE regular dealer in such bulk items as petroleum products, steel, cement, gravel, stone, or asphalt without owning, operating, or maintaining a place of business as provided in this paragraph G.2. if the person both owns and operates distribution

equipment for the products. Any supplementing of regular dealers' own distribution equipment shall be by a long-term lease agreement and not on an ad hoc or contract-by-contract basis. Packagers, brokers, manufacturers' representatives, or other persons who arrange or expedite transactions are not DBE regular dealers within the meaning of this paragraph G.2.

3. Credit for materials or supplies purchased from a DBE which is neither a manufacturer nor a regular dealer will be limited to the entire amount of fees or commissions charged for assistance in the procurement of the materials and supplies, or fees or transportation charges for the delivery of materials or supplies required on a job site, provided the fees are reasonable and not excessive as compared with fees charged for similar services.

H. Credit for DBE trucking companies will be as follows:

1. The DBE must be responsible for the management and supervision of the entire trucking operation for which it is responsible on a particular contract, and there cannot be a contrived arrangement for the purpose of meeting the DBE goal.
2. The DBE must itself own and operate at least one fully licensed, insured, and operational truck used on the contract.
3. The DBE receives credit for the total value of the transportation services it provides on the contract using trucks it owns, insures, and operates using drivers it employs.
4. The DBE may lease trucks from another DBE firm, including an owner-operator who is certified as a DBE. The DBE who leases trucks from another DBE receives credit for the total value of the transportation services the lessee DBE provides on the contract.
5. The DBE may also lease trucks from a non-DBE firm, including an owner-operator. The DBE who leases trucks from a non-DBE is entitled to credit only for the fee or commission it receives as a result of the lease arrangement. The DBE does not receive credit for the total value of the transportation services provided by the lessee, since these services are not provided by a DBE.
6. For the purposes of this paragraph H, a lease must indicate that the DBE has exclusive use of and control over the truck. This does not preclude the leased truck from working for others during the term of the lease with the consent of the DBE, so long as the lease gives the DBE absolute priority for use of the leased truck. Leased trucks must display the name and identification number of the DBE.

I. Noncompliance by the Contractor with the requirements of the regulations constitutes a breach of this contract and may result in termination of the contract or other appropriate remedy for a breach of this contract.

J. Bidders are encouraged to use services offered by financial institutions owned and controlled by DBEs.

#### **2-1.02A DBE GOAL FOR THIS PROJECT**

The Department has established the following goal for Disadvantaged Business Enterprise (DBE) participation for this project:

Disadvantaged Business Enterprise (DBE): 19 percent

Bidders may use the services of the following firms to contact interested DBEs. These firms are available to assist DBEs in preparing bids for subcontracting or supplying materials.

The following firms may be contacted for projects in the following locations:

Districts 04, 05 (except San Luis Obispo and Santa Barbara Counties), 06 (except Kern County) and 10:
Triaxial Management Services, Inc. - Oakland  1545 Willow Street, 1st Floor Oakland, CA 94607 Telephone - (510) 286-1313 FAX No. - (510) 286-6792

Districts 08, 11 and 12:
Triaxial Management Services, Inc. - San Diego 2725 Congress Street, Suite 1-D San Diego, CA 92110 Telephone - (619) 543-5109 FAX No. - (619) 543-5108

Districts 07 and 08; in San Luis Obispo and Santa Barbara Counties in District 05; and in Kern County in District 06:
Triaxial Management Services, Inc. - Los Angeles 2594 Industry Way, Suite 101 Lynwood, CA 90262 Telephone - (310) 537-6677 FAX No. - (310) 637-0128

Districts 01, 02, 03 and 09:
Triaxial Management Services, Inc. - Sacramento 930 Alhambra Blvd., #205 Sacramento, CA 95816 Telephone - (916) 553-4172 FAX No. - (916) 553-4173

**2-1.02B SUBMISSION OF DBE INFORMATION**

The required DBE information shall be submitted on the "CALTRANS BIDDER - DBE INFORMATION" form included in the Proposal. If the DBE information is not submitted with the bid, the DBE Information form shall be removed from the documents prior to submitting the bid.

It is the bidder's responsibility to make enough work available to DBEs and to select those portions of the work or material needs consistent with the available DBEs to meet the goal for DBE participation or to provide information to establish that, prior to bidding, the bidder made adequate good faith efforts to do so.

If DBE information is not submitted with the bid, the apparent successful bidder (low bidder), the second low bidder and the third low bidder shall submit DBE information to the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, California 95814 so the information is received by the Department no later than 4:00 p.m. on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening. DBE information sent by U.S. Postal Service certified mail with return receipt and certificate of mailing and mailed on or before the third day, not including Saturdays, Sundays and legal holidays, following bid opening will be accepted even if it is received after the fourth day following bid opening. Failure to submit the required DBE information by the time specified will be grounds for finding the bid or proposal nonresponsive. Other bidders need not submit DBE information unless requested to do so by the Department.

The bidder's DBE information shall establish that good faith efforts to meet the DBE goal have been made. To establish good faith efforts, the bidder shall demonstrate that the goal will be met or that, prior to bidding, adequate good faith efforts to meet the goal were made.

Bidders are cautioned that even though their submittal indicates they will meet the stated DBE goal, their submittal should also include their adequate good faith efforts information along with their DBE goal information to protect their eligibility for award of the contract in the event the Department, in its review, finds that the goal has not been met.

The bidder's DBE information shall include the names, addresses and phone numbers of DBE firms that will participate, with a complete description of work or supplies to be provided by each, the dollar value of each DBE transaction, and a written confirmation from the DBE that it is participating in the contract. A copy of the DBE's quote will serve as written confirmation that the DBE is participating in the contract. When 100 percent of a contract item of work is not to be performed or furnished by a DBE, a description of the exact portion of that work to be performed or furnished by that DBE shall be included in the DBE information, including the planned location of that work. The work that a DBE prime contractor has committed to performing with its own forces as well as the work that it has committed to be performed by DBE subcontractors, suppliers and trucking companies will count toward the goal.

The information necessary to establish the bidder's adequate good faith efforts to meet the DBE goal should include:

- A. The names and dates of each publication in which a request for DBE participation for this project was placed by the bidder.

- B. The names and dates of written notices sent to certified DBEs soliciting bids for this project and the dates and methods used for following up initial solicitations to determine with certainty whether the DBEs were interested.
- C. The items of work which the bidder made available to DBE firms, including, where appropriate, any breaking down of the contract work items (including those items normally performed by the bidder with its own forces) into economically feasible units to facilitate DBE participation. It is the bidder's responsibility to demonstrate that sufficient work to meet the DBE goal was made available to DBE firms.
- D. The names, addresses and phone numbers of rejected DBE firms, the firms selected for that work, and the reasons for the bidder's choice.
- E. Efforts made to assist interested DBEs in obtaining bonding, lines of credit or insurance, and any technical assistance or information related to the plans, specifications and requirements for the work which was provided to DBEs.
- F. Efforts made to assist interested DBEs in obtaining necessary equipment, supplies, materials, or related assistance or services, excluding supplies and equipment the DBE subcontractor purchases or leases from the prime contractor or its affiliate.
- G. The names of agencies contacted to provide assistance in contacting, recruiting and using DBE firms.
- H. Any additional data to support a demonstration of good faith efforts.

### **SECTION 3. AWARD AND EXECUTION OF CONTRACT**

The bidder's attention is directed to the provisions in Section 3, "Award and Execution of Contract," of the Standard Specifications and these special provisions for the requirements and conditions concerning award and execution of contract.

The award of the contract, if it be awarded, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed and who has met the goal for DBE participation or has demonstrated, to the satisfaction of the Department, adequate good faith efforts to do so. Meeting the goal for DBE participation or demonstrating, to the satisfaction of the Department, adequate good faith efforts to do so is a condition for being eligible for award of contract.

A "Payee Data Record" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to facilitate the collection of taxpayer identification data. The form shall be completed and returned to the Department by the successful bidder with the executed contract and contract bonds. For the purposes of the form, payee shall be deemed to mean the successful bidder. The form is not to be completed for subcontractors or suppliers. Failure to complete and return the "Payee Data Record" form to the Department as provided herein will result in the retention of 31 percent of payments due the contractor and penalties of up to \$20,000. This retention of payments for failure to complete the "Payee Data Record" form is in addition to any other retention of payments due the Contractor.

### **SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES**

Attention is directed to the provisions in Sections 8-1.03, "Beginning of Work," 8-1.06, "Time of Completion," 8-1.07, "Liquidated Damages," and 20-4.08, "Plant Establishment Work," of the Standard Specifications and these special provisions.

The Contractor shall begin work within 15 calendar days after the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department of Transportation.

The work (except plant establishment work) shall be diligently prosecuted to completion before the expiration of **130 WORKING DAYS** beginning on the fifteenth calendar day after approval of the contract.

The Contractor shall pay to the State of California the sum of \$4,700 per day, for each and every calendar day's delay in finishing the work (except plant establishment work) in excess of the number of working days prescribed above.

The Contractor shall diligently prosecute all work (including plant establishment) to completion before the expiration of **220 WORKING DAYS** beginning on the fifteenth calendar day after approval of the contract.

The Contractor shall pay to the State of California the sum of \$600 per day, for each and every calendar day's delay in completing the work in excess of the number of working days prescribed above.

In no case will liquidated damages of more than \$4,700 per day be assessed.

### **SECTION 5. GENERAL**

#### **SECTION 5-1. MISCELLANEOUS**

##### **5-1.01 PLANS AND WORKING DRAWINGS**

When the specifications require working drawings to be submitted to the Division of Structure Design, the drawings shall be submitted to: Division of Structure Design, Documents Unit, Mail Station 9, 1801 30th Street, Sacramento, CA 95816, Telephone 916 227-8252.

### **5-1.011 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK**

Attention is directed to "Differing Site Conditions" of these special provisions regarding physical conditions at the site which may differ from those indicated in "Materials Information," log of test borings or other geotechnical information obtained by the Department's investigation of site conditions.

### **5-1.012 DIFFERING SITE CONDITIONS**

Attention is directed to Section 5-1.116, "Differing Site Conditions," of the Standard Specifications.

During the progress of the work, if subsurface or latent conditions are encountered at the site differing materially from those indicated in the "Materials Information," log of test borings, other geotechnical data obtained by the Department's investigation of subsurface conditions, or an examination of the conditions above ground at the site, the party discovering those conditions shall promptly notify the other party in writing of the specific differing conditions before they are disturbed and before the affected work is performed.

The Contractor will be allowed 15 days from the notification of the Engineer's determination of whether or not an adjustment of the contract is warranted, in which to file a notice of potential claim in conformance with the provisions of Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications and as specified herein; otherwise the decision of the Engineer shall be deemed to have been accepted by the Contractor as correct. The notice of potential claim shall set forth in what respects the Contractor's position differs from the Engineer's determination and provide any additional information obtained by the Contractor, including but not limited to additional geotechnical data. The notice of potential claim shall be accompanied by the Contractor's certification that the following were made in preparation of the bid: a review of the contract, a review of the "Materials Information," a review of the log of test borings and other records of geotechnical data to the extent they were made available to bidders prior to the opening of bids, and an examination of the conditions above ground at the site. Supplementary information, obtained by the Contractor subsequent to the filing of the notice of potential claim, shall be submitted to the Engineer in an expeditious manner.

### **5-1.013 LINES AND GRADES**

Attention is directed to Section 5-1.07, "Lines and Grades," of the Standard Specifications.

Stakes or marks will be set by the Engineer in conformance with the requirements in Chapter 12, "Construction Surveys," of the Department's Surveys Manual.

### **5-1.015 LABORATORY**

When a reference is made in the specifications to the "Laboratory," the reference shall mean Division of Engineering Services - Materials Engineering and Testing Services and Division of Engineering Services - Geotechnical Services of the Department of Transportation, or established laboratories of the various Districts of the Department, or other laboratories authorized by the Department to test materials and work involved in the contract. When a reference is made in the specifications to the "Transportation Laboratory," the reference shall mean Division of Engineering Services - Materials Engineering and Testing Services and Division of Engineering Services - Geotechnical Services, located at 5900 Folsom Boulevard, Sacramento, CA 95819, Telephone (916) 227-7000.

### **5-1.017 CONTRACT BONDS**

Attention is directed to Section 3-1.02, "Contract Bonds," of the Standard Specifications and these special provisions.

The payment bond shall be in a sum not less than one hundred percent of the total amount payable by the terms of the contract.

### **5-1.019 COST REDUCTION INCENTIVE**

Attention is directed to Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications.

Prior to preparing a written cost reduction proposal, the Contractor shall request a meeting with the Engineer to discuss the proposal in concept. Items of discussion will also include permit issues, impact on other projects, impact on the project schedule, peer reviews, overall merit of the proposal, and review times required by the Department and other agencies.

If a cost reduction proposal submitted by the Contractor, and subsequently approved by the Engineer, provides for a reduction in contract time, 50 percent of that contract time reduction shall be credited to the State by reducing the contract working days, not including plant establishment. Attention is directed to "Beginning of Work, Time of Completion and Liquidated Damages" of these special provisions regarding the working days.

If a cost reduction proposal submitted by the Contractor, and subsequently approved by the Engineer, provides for a reduction in traffic congestion or avoids traffic congestion during construction, 60 percent of the estimated net savings in construction costs attributable to the cost reduction proposal will be paid to the Contractor. In addition to the requirements in

Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications, the Contractor shall provide detailed comparisons of the traffic handling between the existing contract and the proposed change, and estimates of the traffic volumes and congestion.

#### **5-1.02 LABOR NONDISCRIMINATION**

Attention is directed to the following Notice that is required by Chapter 5 of Division 4 of Title 2, California Code of Regulations.

### **NOTICE OF REQUIREMENT FOR NONDISCRIMINATION PROGRAM**

#### **(GOV. CODE, SECTION 12990)**

Your attention is called to the "Nondiscrimination Clause", set forth in Section 7-1.01A(4), "Labor Nondiscrimination," of the Standard Specifications, which is applicable to all nonexempt State contracts and subcontracts, and to the "Standard California Nondiscrimination Construction Contract Specifications" set forth therein. The specifications are applicable to all nonexempt State construction contracts and subcontracts of \$5000 or more.

#### **5-1.022 PAYMENT OF WITHHELD FUNDS**

Payment of withheld funds shall conform to Section 9-1.065, "Payment of Withheld Funds," of the Standard Specifications and these special provisions.

Funds withheld from progress payments to ensure performance of the contract that are eligible for payment into escrow or to an escrow agent pursuant to Section 10263 of the California Public Contract Code do not include funds withheld or deducted from payment due to failure of the Contractor to fulfill a contract requirement.

#### **5-1.03 INTEREST ON PAYMENTS**

Interest shall be payable on progress payments, payments after acceptance, final payments, extra work payments, and claim payments as follows:

- A. Unpaid progress payments, payment after acceptance, and final payments shall begin to accrue interest 30 days after the Engineer prepares the payment estimate.
- B. Unpaid extra work bills shall begin to accrue interest 30 days after preparation of the first pay estimate following receipt of a properly submitted and undisputed extra work bill. To be properly submitted, the bill must be submitted within 7 days of the performance of the extra work and in conformance with the provisions in Section 9-1.03C, "Records," and Section 9-1.06, "Partial Payments," of the Standard Specifications. An undisputed extra work bill not submitted within 7 days of performance of the extra work will begin to accrue interest 30 days after the preparation of the second pay estimate following submittal of the bill.
- C. The rate of interest payable for unpaid progress payments, payments after acceptance, final payments, and extra work payments shall be 10 percent per annum.
- D. The rate of interest payable on a claim, protest or dispute ultimately allowed under this contract shall be 6 percent per annum. Interest shall begin to accrue 61 days after the Contractor submits to the Engineer information in sufficient detail to enable the Engineer to ascertain the basis and amount of said claim, protest or dispute.

The rate of interest payable on any award in arbitration shall be 6 percent per annum if allowed under the provisions of Civil Code Section 3289.

#### **5-1.031 FINAL PAYMENT AND CLAIMS**

Attention is directed to Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications.

If the Contractor files a timely written statement of claims in response to the proposed final estimate, the District that administers the contract will submit a claim position letter to the Contractor by hand delivery or deposit in the U.S. mail within 135 days of acceptance of the contract. The claim position letter will delineate the District's position on the Contractor's claims. If the Contractor disagrees with the claim position letter, the Contractor shall submit a written notification of its disagreement to be received by the District not later than 15 days after the Contractor's receipt of the claim position letter. The written notification of disagreement shall set forth the basis for the Contractor's disagreement and be submitted to the office designated in the claim position letter. The Contractor's failure to provide a timely, written notification of disagreement shall constitute the Contractor's acceptance and agreement with the determinations provided in the claim position letter and with final payment pursuant to the claim position letter.

If the Contractor files a timely notification of disagreement with the District claim position letter, the board of review designated by the District Director to review claims that remain in dispute will meet with the Contractor within 45 days after receipt by the District of the notification of disagreement. Attendance by the Contractor at the board of review meeting shall be mandatory.

If the District fails to submit a claim position letter to the Contractor within 135 days after the acceptance of the contract and the Contractor has claims that remain in dispute, the Contractor may request a meeting with the board of review designated by the District Director to review claims that remain in dispute. The Contractor's request for a meeting shall identify the claims that remain in dispute. If the Contractor files a request for a meeting, the board of review will meet with the Contractor within 45 days after the District receives the request for the meeting. Attendance by the Contractor at the District Director's board of review meeting shall be mandatory.

Failure of the Contractor to file a timely written statement of claims in response to the proposed final estimate, or to file a timely notification of disagreement with the District claim position letter, or to attend the District Director's board of review meeting shall constitute a failure to pursue diligently and exhaust the administrative procedures in the contract and shall be a bar to arbitration in conformance with the requirements in Section 10240.2 of the California Public Contract Code.

#### **5-1.04 PUBLIC SAFETY**

The Contractor shall provide for the safety of traffic and the public in conformance with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications and these special provisions.

The Contractor shall install temporary railing (Type K) between a lane open to public traffic and an excavation, obstacle or storage area when the following conditions exist:

- A. Excavations.—The near edge of the excavation is 3.6 m or less from the edge of the lane, except:
  - 1. Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
  - 2. Excavations less than 0.3-m deep.
  - 3. Trenches less than 0.3-m wide for irrigation pipe or electrical conduit, or excavations less than 0.3-m in diameter.
  - 4. Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
  - 5. Excavations in side slopes, where the slope is steeper than 1:4 (vertical:horizontal).
  - 6. Excavations protected by existing barrier or railing.
- B. Temporarily Unprotected Permanent Obstacles.—The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.
- C. Storage Areas.—Material or equipment is stored within 3.6 m of the lane and the storage is not otherwise prohibited by the provisions of the Standard Specifications and these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this section "Public Safety" and in Section 7-1.09, "Public Safety," of the Standard Specifications, shall be offset a minimum of 4.6 m from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than 0.3-m transversely to 3 m longitudinally with respect to the edge of the traffic lane. If the 4.6-m minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules shall be installed at the approach end of the temporary railing.

Temporary railing (Type K) shall conform to the provisions in Section 12-3.08, "Temporary Railing (Type K)," of the Standard Specifications. Temporary railing (Type K), conforming to the details shown on 1999 Standard Plan T3, may be used. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance.

Temporary crash cushion modules shall conform to the provisions in "Temporary Crash Cushion Module" of these special provisions.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas, the Contractor shall close the adjacent traffic lane unless otherwise provided in the Standard Specifications and these special provisions:

Approach Speed of Public Traffic (Posted Limit) (Kilometers Per Hour)	Work Areas
Over 72 (45 Miles Per Hour)	Within 1.8 m of a traffic lane but not on a traffic lane
56 to 72 (35 to 45 Miles Per Hour)	Within 0.9-m of a traffic lane but not on a traffic lane

The lane closure provisions of this section shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of a traffic lane, the line of cones or delineators shall be considered to be the edge of the traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 3 m without written approval from the Engineer.

When work is not in progress on a trench or other excavation that required closure of an adjacent lane, the traffic cones or portable delineators used for the lane closure shall be placed off of and adjacent to the edge of the traveled way. The spacing of the cones or delineators shall be not more than the spacing used for the lane closure.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

Full compensation for conforming to the provisions in this section "Public Safety," including furnishing and installing temporary railing (Type K) and temporary crash cushion modules, shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

#### **5-1.05 TESTING**

Testing of materials and work shall conform to the provisions in Section 6-3, "Testing," of the Standard Specifications and these special provisions.

Whenever the provisions of Section 6-3.01, "General," of the Standard Specifications refer to tests or testing, it shall mean tests to assure the quality and to determine the acceptability of the materials and work.

The Engineer will deduct the costs for testing of materials and work found to be unacceptable, as determined by the tests performed by the Department, and the costs for testing of material sources identified by the Contractor which are not used for the work, from moneys due or to become due to the Contractor. The amount deducted will be determined by the Engineer.

#### **5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES**

When the presence of asbestos or hazardous substances are not shown on the plans or indicated in the specifications and the Contractor encounters materials which the Contractor reasonably believes to be asbestos or a hazardous substance as defined in Section 25914.1 of the Health and Safety Code, and the asbestos or hazardous substance has not been rendered harmless, the Contractor may continue work in unaffected areas reasonably believed to be safe. The Contractor shall immediately cease work in the affected area and report the condition to the Engineer in writing.

In conformance with Section 25914.1 of the Health and Safety Code, removal of asbestos or hazardous substances including exploratory work to identify and determine the extent of the asbestos or hazardous substance will be performed by separate contract.

If delay of work in the area delays the current controlling operation, the delay will be considered a right of way delay and the Contractor will be compensated for the delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

#### **5-1.07 YEAR 2000 COMPLIANCE**

This contract is subject to Year 2000 Compliance for automated devices in the State of California.

Year 2000 compliance for automated devices in the State of California is achieved when embedded functions have or create no logical or mathematical inconsistencies when dealing with dates prior to and beyond 1999. The year 2000 is recognized and processed as a leap year. The product shall operate accurately in the manner in which the product was intended for date operation without requiring manual intervention.

The Contractor shall provide the Engineer a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for all automated devices furnished for the project.

#### **5-1.075 BUY AMERICA REQUIREMENTS**

Attention is directed to the "Buy America" requirements of the Surface Transportation Assistance Act of 1982 (Section 165) and the Intermodal Surface Transportation Efficiency Act of 1991 (ISTEA) Sections 1041(a) and 1048(a), and the regulations adopted pursuant thereto. In conformance with the law and regulations, all manufacturing processes for steel and iron materials furnished for incorporation into the work on this project shall occur in the United States; with the exception that pig iron and processed, pelletized and reduced iron ore manufactured outside of the United States may be used in the

domestic manufacturing process for such steel and iron materials. The application of coatings, such as epoxy coating, galvanizing, painting, and other coatings that protect or enhance the value of steel or iron materials shall be considered a manufacturing process subject to the "Buy America" requirements.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be furnished for steel and iron materials. The certificates, in addition to certifying that the materials comply with the specifications, shall specifically certify that all manufacturing processes for the materials occurred in the United States, except for the above exceptions.

The requirements imposed by the law and regulations do not prevent a minimal use of foreign steel and iron materials if the total combined cost of the materials used does not exceed one-tenth of one percent (0.1 percent) of the total contract cost or \$2500, whichever is greater. The Contractor shall furnish the Engineer acceptable documentation of the quantity and value of the foreign steel and iron prior to incorporating the materials into the work.

#### **5-1.08 SUBCONTRACTOR AND DBE RECORDS**

The Contractor shall maintain records showing the name and business address of each first-tier subcontractor. The records shall also show the name and business address of every DBE subcontractor, DBE vendor of materials and DBE trucking company, regardless of tier. The records shall show the date of payment and the total dollar figure paid to all of these firms. DBE prime contractors shall also show the date of work performed by their own forces along with the corresponding dollar value of the work.

Upon completion of the contract, a summary of these records shall be prepared on Form CEM-2402 (F) and certified correct by the Contractor or the Contractor's authorized representative, and shall be furnished to the Engineer. The form shall be furnished to the Engineer within 90 days from the date of contract acceptance. \$10,000 will be withheld from payment until the Form CEM-2402 (F) is submitted. The amount will be returned to the Contractor when a satisfactory Form CEM-2402 (F) is submitted.

Prior to the fifteenth of each month, the Contractor shall submit documentation to the Engineer showing the amount paid to DBE trucking companies listed in the Contractor's DBE information. This monthly documentation shall indicate the portion of the revenue paid to DBE trucking companies which is claimed toward DBE participation. The Contractor shall also obtain and submit documentation to the Engineer showing the amount paid by DBE trucking companies to all firms, including owner-operators, for the leasing of trucks. The DBE who leases trucks from a non-DBE is entitled to credit only for the fee or commission it receives as a result of the lease arrangement. The records must confirm that the amount of credit claimed toward DBE participation conforms with Section 2-1.02, "Disadvantaged Business Enterprise," of these special provisions.

The Contractor shall also obtain and submit documentation to the Engineer showing the truck number, owner's name, California Highway Patrol CA number, and if applicable, the DBE certification number of the owner of the truck for all trucks used during that month for which DBE participation will be claimed. This documentation shall be submitted on Form CEM-2404 (F).

#### **5-1.083 DBE CERTIFICATION STATUS**

If a DBE subcontractor is decertified during the life of the project, the decertified subcontractor shall notify the Contractor in writing with the date of decertification. If a subcontractor becomes a certified DBE during the life of the project, the subcontractor shall notify the Contractor in writing with the date of certification. The Contractor shall furnish the written documentation to the Engineer.

Upon completion of the contract, Form CEM-2403 (F) indicating the DBE's existing certification status shall be signed and certified correct by the Contractor. The certified form shall be furnished to the Engineer within 90 days from the date of contract acceptance.

#### **5-1.086 PERFORMANCE OF DBE SUBCONTRACTORS AND SUPPLIERS**

The DBEs listed by the Contractor in response to the provisions in Section 2-1.02B, "Submission of DBE Information," and Section 3, "Award and Execution of Contract," of these special provisions, which are determined by the Department to be certified DBEs, shall perform the work and supply the materials for which they are listed, unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Authorization to use other forces or sources of materials may be requested for the following reasons:

- A. The listed DBE, after having had a reasonable opportunity to do so, fails or refuses to execute a written contract, when such written contract, based upon the general terms, conditions, plans and specifications for the project, or on the terms of such subcontractor's or supplier's written bid, is presented by the Contractor.
- B. The listed DBE becomes bankrupt or insolvent.
- C. The listed DBE fails or refuses to perform the subcontract or furnish the listed materials.

- D. The Contractor stipulated that a bond was a condition of executing a subcontract and the listed DBE subcontractor fails or refuses to meet the bond requirements of the Contractor.
- E. The work performed by the listed subcontractor is substantially unsatisfactory and is not in substantial conformance with the plans and specifications, or the subcontractor is substantially delaying or disrupting the progress of the work.
- F. It would be in the best interest of the State.

The Contractor shall not be entitled to any payment for such work or material unless it is performed or supplied by the listed DBE or by other forces (including those of the Contractor) pursuant to prior written authorization of the Engineer.

**5-1.09 SUBCONTRACTING**

Attention is directed to the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, and Section 2, "Proposal Requirements and Conditions," and Section 3, "Award and Execution of Contract," of these special provisions.

Pursuant to the provisions of Section 1777.1 of the Labor Code, the Labor Commissioner publishes and distributes a list of contractors ineligible to perform work as a subcontractor on a public works project. This list of debarred contractors is available from the Department of Industrial Relations web site at:

<http://www.dir.ca.gov/DLSE/Debar.html>.

The provisions in the third paragraph of Section 8-1.01, "Subcontracting," of the Standard Specifications, that the Contractor shall perform with the Contractor's own organization contract work amounting to not less than 50 percent of the original contract price, is not changed by the Federal Aid requirement specified under "Required Contract Provisions Federal-Aid Construction Contracts" in Section 14 of these special provisions that the Contractor perform not less than 30 percent of the original contract work with the Contractor's own organization.

Each subcontract and any lower tier subcontract that may in turn be made shall include the "Required Contract Provisions Federal-Aid Construction Contracts" in Section 14 of these special provisions. This requirement shall be enforced as follows:

- A. Noncompliance shall be corrected. Payment for subcontracted work involved will be withheld from progress payments due, or to become due, until correction is made. Failure to comply may result in termination of the contract.

In conformance with the Federal DBE regulations Sections 26.53(f)(1) and 26.53(f)(2) Part 26, Title 49 CFR:

- A. The Contractor shall not terminate for convenience a DBE subcontractor listed in response to Section 2-1.02B, "Submission of DBE Information," and then perform that work with its own forces, or those of an affiliate without the written consent of the Department, and
- B. If a DBE subcontractor is terminated or fails to complete its work for any reason, the Contractor will be required to make good faith efforts to substitute another DBE subcontractor for the original DBE subcontractor, to the extent needed to meet the contract goal.

The requirement in Section 2-1.02, "Disadvantaged Business Enterprise (DBE)," of these special provisions that DBEs must be certified on the date bids are opened does not apply to DBE substitutions after award of the contract.

**5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS**

Attention is directed to the provisions in Sections 10262 and 10262.5 of the Public Contract Code and Section 7108.5 of the Business and Professions Code concerning prompt payment to subcontractors.

**5-1.102 PROMPT PAYMENT OF WITHHELD FUNDS TO SUBCONTRACTORS**

The Contractor shall return all moneys withheld in retention from the subcontractor within 30 days after receiving payment for work satisfactorily completed, even if the other contract work is not completed and has not been accepted in conformance with Section 7-1.17, "Acceptance of Contract," of the Standard Specifications. This requirement shall not be construed to limit or impair any contractual, administrative, or judicial remedies otherwise available to the Contractor or subcontractor in the event of a dispute involving late payment or nonpayment by the Contractor or deficient subcontract performance or noncompliance by a subcontractor.

### **5-1.103 RECORDS**

The Contractor shall maintain cost accounting records for the contract pertaining to, and in such a manner as to provide a clear distinction between, the following six categories of costs of work during the life of the contract:

- A. Direct costs of contract item work.
- B. Direct costs of changes in character in conformance with Section 4-1.03C, "Changes in Character of Work," of the Standard Specifications.
- C. Direct costs of extra work in conformance with Section 4-1.03D, "Extra Work," of the Standard Specifications.
- D. Direct costs of work not required by the contract and performed for others.
- E. Direct costs of work performed under a notice of potential claim in conformance with the provisions in Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications.
- F. Indirect costs of overhead.

Cost accounting records shall include the information specified for daily extra work reports in Section 9-1.03C, "Records," of the Standard Specifications. The requirements for furnishing the Engineer completed daily extra work reports shall only apply to work paid for on a force account basis.

The cost accounting records for the contract shall be maintained separately from other contracts, during the life of the contract, and for a period of not less than 3 years after the date of acceptance of the contract. If the Contractor intends to file claims against the Department, the Contractor shall keep the cost accounting records specified above until complete resolution of all claims has been reached.

### **5-1.11 PARTNERING**

The State will promote the formation of a "Partnering" relationship with the Contractor in order to effectively complete the contract to the benefit of both parties. The purpose of this relationship is to maintain a cooperative communication and to mutually resolve conflicts at the lowest responsible management level.

The Contractor may request the formation of a "Partnering" relationship by submitting a request in writing to the Engineer after approval of the contract. If the Contractor's request for "Partnering" is approved by the Engineer, scheduling of a "Partnering Workshop," selecting the "Partnering" facilitator and workshop site, and other administrative details shall be as agreed to by both parties. If agreed to by the parties, additional "Partnering Workshops" will be conducted as needed throughout the life of the contract.

The costs involved in providing the "Partnering Workshop" facilitator and workshop site will be borne equally by the State and the Contractor. The division of cost will be made by determining the cost in providing the "Partnering Workshop" facilitator and workshop site in conformance with the provisions in Section 9-1.03B, "Work Performed by Special Forces or Other Special Services," of the Standard Specifications, and paying to the Contractor one-half of that cost, except no markups will be allowed.

All other costs associated with "Partnering Workshops" will be borne separately by the party incurring the costs, such as wages and travel expenses, and no additional compensation will be allowed therefor.

The establishment of a "Partnering" relationship will not change or modify the terms and conditions of the contract and will not relieve either party of the legal requirements of the contract.

### **5-1.12 AREAS FOR CONTRACTOR'S USE**

Attention is directed to the provisions in Section 7-1.19, "Rights in Land and Improvements," of the Standard Specifications and these special provisions.

The highway right of way shall be used only for purposes that are necessary to perform the required work. The Contractor shall not occupy the right of way, or allow others to occupy the right of way, for purposes which are not necessary to perform the required work.

No State-owned parcels adjacent to the right of way are available for the exclusive use of the Contractor within the contract limits. The Contractor shall secure, at the Contractor's own expense, areas required for plant sites, storage of equipment or materials, or for other purposes.

No area is available within the contract limits for the exclusive use of the Contractor. However, temporary storage of equipment and materials on State property may be arranged with the Engineer, subject to the prior demands of State maintenance forces and to other contract requirements. Use of the Contractor's work areas and other State-owned property shall be at the Contractor's own risk, and the State shall not be held liable for damage to or loss of materials or equipment located within such areas.

### 5-1.13 PAYMENTS

Attention is directed to Sections 9-1.06, "Partial Payments," and 9-1.07, "Payment After Acceptance," of the Standard Specifications and these special provisions.

For the purpose of making partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications, the amount set forth for the contract items of work hereinafter listed shall be deemed to be the maximum value of the contract item of work which will be recognized for progress payment purposes:

A. Clearing and Grubbing	\$51,000
B. Roadside Clearing	\$25,000
C. Bridge Removal (Portion), Location A	\$20,000
D. Bridge Removal (Portion), Location B	\$10,000
E. Bridge Removal (Portion), Location C	\$10,000
F. Bridge Removal (Portion), Location D	\$10,000

After acceptance of the contract pursuant to the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, the amount, if any, payable for a contract item of work in excess of the maximum value for progress payment purposes hereinabove listed for the item, will be included for payment in the first estimate made after acceptance of the contract.

In determining the partial payments to be made to the Contractor, only the following listed materials will be considered for inclusion in the payment as materials furnished but not incorporated in the work:

- A. Sound Wall (Barrier)(Masonry Block)
- B. Sound Wall (Retaining Wall)(Masonry Block)
- C. Sound Wall (Masonry Block)
- D. Bar Reinforcing Steel
- E. Piling
- F. Reinforced Concrete Pipe
- G. Pavement Markers
- H. Guard Railings and Terminal Systems
- I. Miscellaneous Bridge Metal
- J. Fences and Gates
- K. Lighting and Sign Illumination
- L. Miscellaneous Iron and Steel
- M. Fiber Optic Cables
- N. Twisted Pair Cables
- O. Communication Pull Boxes
- P. Service Equipment Enclosures
- Q. Lighting Standards
- R. Luminaires

### 5-1.14 MIGRATORY BIRD ACT REQUIREMENTS

It is anticipated that migratory birds may try to nest in vegetation (trees, tall grass, and shrubs) throughout the project between March 1 and September 1. If any clearing of vegetation is anticipated in nesting areas during this period, the Contractor, the Engineer will request a pre-construction survey by the District Biologist a minimum of 15 days prior to beginning work. If evidence of bird nesting is discovered, the Contractor shall not disturb the nesting birds until they have left the nest. If evidence of migratory bird nesting is discovered during clearing of vegetation, the Contractor shall immediately notify the Engineer.

Federal and State laws protect migratory birds, their occupied nests, and their eggs from destruction. The applicable Federal law is the Migratory Bird Treaty Act (15 USC 703-711), 50 CFR Part 21, and 50 CFR Part 10. Protection under California Law is found in Fish Game Code Sections 3503, 3513, and 3800.

If suspension of work is required due to the nesting of migratory birds, work will be suspended as provided in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications.

Full compensation for conforming to the requirements in these special provisions shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

### **5-1.15 SOUND CONTROL REQUIREMENTS**

Sound control shall conform to the provisions in Section 7-1.01I, "Sound Control Requirements," of the Standard Specifications and these special provisions.

The noise level from the Contractor's operations, between the hours of 9:00 p.m. and 7:00 a.m., shall not exceed 86 dBA at a distance of 15 m. This requirement shall not relieve the Contractor from responsibility for complying with local ordinances regulating noise level.

The noise level requirement shall apply to the equipment on the job or related to the job, including but not limited to trucks, transit mixers or transient equipment that may or may not be owned by the Contractor. The use of loud sound signals shall be avoided in favor of light warnings except those required by safety laws for the protection of personnel.

No night work on sound walls adjacent to residential areas shall be allowed.

Full compensation for conforming to the requirements of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

### **5-1.16 ACCESS TO THE WORK AREA**

Temporary construction easements shown on the plans shall be limited to foot traffic. The Contractor shall take precautions while within the easement to protect the natural terrain, existing trees, shrubs and other plants, and private owner's properties from injury or damage resulting from the Contractor's operations. Contractor shall not use the temporary construction easement area to store construction materials or to operate Contractor's equipment, including but not limited to trucks and transit mixers.

Relocation or removal of private owner's improvements (including but not limited to storage sheds and swimming pool pumps) located within the temporary construction easement area will be removed or relocated by the owner prior to construction. In the event temporary construction easement area has not been cleared of the improvements by the owner, and when directed by the Engineer, the removal or relocating of these improvements will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

The Contractor shall remove equipment, materials, and rubbish from the work areas and other State-owned property which the Contractor occupies. The Contractor shall leave the areas in a presentable condition in conformance with the provisions in Section 4-1.02, "Final Cleaning Up," of the Standard Specifications.

Full compensation for conforming to the provisions in this section shall be considered as included in prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

### **5-1.17 RELATIONS WITH CITY OF LOS ANGELES**

Attention is directed to Section 7, "Legal Relations and Responsibility" of the Standard Specifications.

A portion of this project is located within the jurisdiction of the City Los Angeles. The Contractor shall obtain an encroachment permit from the City of Los Angeles. The Contractor shall fully inform himself of all rules, regulations, and conditions that may govern operations in said area and shall conduct operations accordingly.

The Contractor shall notify the City of Los Angeles and obtain a permit for working outside of State right-of-way. The permit shall be obtained 5 working days in advance of the work to be performed.

Should the Contractor fail to conform to the regulations and requirements of the City of Los Angeles, the State reserves the right to perform the work necessary to the provisions and the cost of such work shall be deducted from any moneys due or to become due the Contractor.

Any changes in the conditions set in the agreement proposed by the Contractor shall be submitted to the Engineer for transmittal to the affected agency for their approval. Changes shall not be implemented until approved in writing by the affected agency.

The Contractor shall have readily available copies of the Permit at the worksite at all times during periods of active work and must be presented to any personnel from the permitting agency upon request.

### **5-1.18 AERIALY DEPOSITED LEAD**

Aerially deposited lead is present within the project limits. Aerially deposited lead is lead deposited within unpaved areas or formerly unpaved areas, primarily due to vehicle emissions.

Attention is directed to "Material Containing Aerially Deposited Lead" of these special provisions.

Portions of the Site Investigation Report are included in the "Material Information" handout. The complete report, entitled "ADL Investigation Report Route 5, Los Angeles County, California, Contract No. 43A0078, Task Order No. 07-053511-RF" is available for inspection at the Department of Transportation, District 7 Office of Construction, Change Order Desk, located in a secure building at 801 South Grand Avenue, Los Angeles, California. Prospective bidder shall telephone (213) 897-0054 in advance to make arrangements for entering the building.

Aerially deposited lead is typically found within the top 0.6-m of material in unpaved areas within the highway right of way. Levels of lead found near the project limits range from less than 5.0 to 3300 mg/kg total lead with an average concentration of 428.7 mg/kg total lead, as analyzed by EPA Test Method 6010 or EPA Test Method 7000 series.

The Department has received from the California Department of Toxic Substances Control (DTSC) a Variance regarding the use of material containing aerially deposited lead. This project is subject to the conditions of the Variance, as amended. The Variance is available for inspection at the Department of Transportation, District 7 Office of Construction, Change Order Desk, located in a secure building at 801 South Grand Avenue, Los Angeles, California. Prospective bidder shall telephone (213) 897-0054 in advance to make arrangements for entering the building.

Once the Contractor has completed the placement of material containing aerially deposited lead in conformance with these special provisions and as directed by the Engineer, the Contractor shall have no responsibility for such materials in place. The Department will not consider the Contractor a generator of such contaminated materials. Further cleanup, removal or remedial actions for such materials will not be required if handled or disposed of as specified herein.

Excavation, reuse, and disposal of material with aerially deposited lead shall be in conformance with all rules and regulations including, but not limited to, those of the following agencies:

United States Department of Transportation (USDOT)  
United States Environmental Protection Agency (USEPA)  
California Environmental Protection Agency (Cal-EPA)  
California Department of Health Services  
Department of Toxic Substances Control (DTSC), Glendale Office  
California Division of Occupational Safety and Health Administration (Cal-OSHA)  
Integrated Waste Management Board  
Regional Water Quality Control Board (RWQCB), Region 4 (Los Angeles)  
State Air Resources Control Board  
South Coast Air Quality Management District (SCAQMD)

Materials containing hazardous levels of lead shall be transported and disposed of in conformance with Federal and State laws and regulations, as amended, and county and municipal ordinances and regulations, as amended. Laws and regulations that govern this work include, but are not limited to:

Health and Safety Code, Division 20, Chapter 6.5 (California Hazardous Waste Control Act)  
Title 22, California Code of Regulations, Division 4.5 (Environmental Health Standards for the Management of Hazardous Waste)  
Title 8, California Code of Regulations

## **SECTION 6. (BLANK)**

## **SECTION 7. (BLANK)**

## **SECTION 8. MATERIALS**

### **SECTION 8-1. MISCELLANEOUS**

#### **8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS**

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the United States Standard Measures which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following provisions:

- A. Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.
- B. Before other non-metric materials and products will be considered for use, the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish necessary

information as required by the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision will be final.

- C. When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, the list of sources of material specified in Section 6-1.01, "Source of Supply and Quality of Materials," of the Standard Specification shall include a list of substitutions to be made and contract items involved. In addition, for a change in design or details, the Contractor shall submit plans and working drawings in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The plans and working drawings shall be submitted at least 7 days before the Contractor intends to begin the work involved.

Unless otherwise specified, the following substitutions of materials and products will be allowed:

**SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS**  
ASTM Designation: A 325M

METRIC SIZE SHOWN ON THE PLANS mm x thread pitch	SIZE TO BE SUBSTITUTED inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

**SUBSTITUTION TABLE FOR PLAIN WIRE REINFORCEMENT**  
ASTM Designation: A 82

METRIC SIZE SHOWN ON THE PLANS <sup>2</sup> mm	SIZE TO BE SUBSTITUTED <sup>2</sup> inch x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

**SUBSTITUTION TABLE FOR BAR REINFORCEMENT**

METRIC BAR DESIGNATION NUMBER <sup>1</sup> SHOWN ON THE PLANS	BAR DESIGNATION NUMBER <sup>2</sup> TO BE SUBSTITUTED
10	3
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

<sup>1</sup>Bar designation numbers approximate the number of millimeters of the nominal diameter of the bars.

<sup>2</sup>Bar numbers are based on the number of eighths of an inch included in the nominal diameter of the bars.

No adjustment will be required in spacing or total number of reinforcing bars due to a difference in minimum yield strength between metric and non-metric bars.

**SUBSTITUTION TABLE FOR SIZES OF:**

(1) STEEL FASTENERS FOR GENERAL APPLICATIONS (ASTM Designation: A 307 or AA(SSH)O Designation: M 314, Grade 36 or 55), and

(2) HIGH STRENGTH STEEL FASTENERS (ASTM Designation: A 325 or A 449)

METRIC SIZE SHOWN ON THE PLANS mm	SIZE TO BE SUBSTITUTED inch
6 or 6.35	1/4
8 or 7.94	5/16
10 or 9.52	3/8
11 or 11.11	7/16
13 or 12.70	1/2
14 or 14.29	9/16
16 or 15.88	5/8
19 or 19.05	3/4
22 or 22.22	7/8
24, 25, or 25.40	1
29 or 28.58	1-1/8
32 or 31.75	1-1/4
35 or 34.93	1-3/8
38 or 38.10	1-1/2
44 or 44.45	1-3/4
51 or 50.80	2
57 or 57.15	2-1/4
64 or 63.50	2-1/2
70 or 69.85	2-3/4
76 or 76.20	3
83 or 82.55	3-1/4
89 or 88.90	3-1/2
95 or 95.25	3-3/4
102 or 101.60	4

SUBSTITUTION TABLE FOR NOMINAL THICKNESS OF SHEET METAL

UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED SHEETS (GALVANIZED)	
METRIC THICKNESS SHOWN ON THE PLANS mm	GAGE TO BE SUBSTITUTED inch	METRIC THICKNESS SHOWN ON THE PLANS mm	GAGE TO BE SUBSTITUTED inch
7.94	0.3125	4.270	0.1681
6.07	0.2391	3.891	0.1532
5.69	0.2242	3.510	0.1382
5.31	0.2092	3.132	0.1233
4.94	0.1943	2.753	0.1084
4.55	0.1793	2.372	0.0934
4.18	0.1644	1.994	0.0785
3.80	0.1495	1.803	0.0710
3.42	0.1345	1.613	0.0635
3.04	0.1196	1.461	0.0575
2.66	0.1046	1.311	0.0516
2.28	0.0897	1.158	0.0456
1.90	0.0747	1.006 or 1.016	0.0396
1.71	0.0673	0.930	0.0366
1.52	0.0598	0.853	0.0336
1.37	0.0538	0.777	0.0306
1.21	0.0478	0.701	0.0276
1.06	0.0418	0.627	0.0247
0.91	0.0359	0.551	0.0217
0.84	0.0329	0.513	0.0202
0.76	0.0299	0.475	0.0187
0.68	0.0269	-----	-----
0.61	0.0239	-----	-----
0.53	0.0209	-----	-----
0.45	0.0179	-----	-----
0.42	0.0164	-----	-----
0.38	0.0149	-----	-----

**SUBSTITUTION TABLE FOR WIRE**

METRIC THICKNESS SHOWN ON THE PLANS mm	WIRE THICKNESS TO BE SUBSTITUTED inch	GAGE NO.
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

**SUBSTITUTION TABLE FOR PIPE PILES**

METRIC SIZE SHOWN ON THE PLANS mm x mm	SIZE TO BE SUBSTITUTED inch x inch
PP 360 x 4.55	NPS 14 x 0.179
PP 360 x 6.35	NPS 14 x 0.250
PP 360 x 9.53	NPS 14 x 0.375
PP 360 x 11.12	NPS 14 x 0.438
PP 406 x 12.70	NPS 16 x 0.500
PP 460 x T	NPS 18 x T"
PP 508 x T	NPS 20 x T"
PP 559 x T	NPS 22 x T"
PP 610 x T	NPS 24 x T"
PP 660 x T	NPS 26 x T"
PP 711 x T	NPS 28 x T"
PP 762 x T	NPS 30 x T"
PP 813 x T	NPS 32 x T"
PP 864 x T	NPS 34 x T"
PP 914 x T	NPS 36 x T"
PP 965 x T	NPS 38 x T"
PP 1016 x T	NPS 40 x T"
PP 1067 x T	NPS 42 x T"
PP 1118 x T	NPS 44 x T"
PP 1219 x T	NPS 48 x T"
PP 1524 x T	NPS 60 x T"

The thickness in millimeters (T) represents an exact conversion of the thickness in inches (T").

**SUBSTITUTION TABLE FOR STRUCTURAL TIMBER AND LUMBER**

METRIC MINIMUM DRESSED DRY, SHOWN ON THE PLANS mm x mm	METRIC MINIMUM DRESSED GREEN, SHOWN ON THE PLANS mm x mm	NOMINAL SIZE TO BE SUBSTITUTED inch x inch
19x89	20x90	1x4
38x89	40x90	2x4
64x89	65x90	3x4
89x89	90x90	4x4
140x140	143x143	6x6
140x184	143x190	6x8
184x184	190x190	8x8
235x235	241x241	10x10
286x286	292x292	12x12

**SUBSTITUTION TABLE FOR NAILS AND SPIKES**

METRIC COMMON NAIL, SHOWN ON THE PLANS  Length, mm Diameter, mm	METRIC BOX NAIL, SHOWN ON THE PLANS  Length, mm Diameter, mm	METRIC SPIKE, SHOWN ON THE PLANS Length, mm Diameter, mm	SIZE TO BE SUBSTITUTED Penny-weight
50.80 2.87	50.80 2.51	————	6d
63.50 3.33	63.50 2.87	————	8d
76.20 3.76	76.20 3.25	76.20 4.88	10d
82.55 3.76	82.55 3.25	82.55 4.88	12d
88.90 4.11	88.90 3.43	88.90 5.26	16d
101.60 4.88	101.60 3.76	101.60 5.72	20d
114.30 5.26	114.30 3.76	114.30 6.20	30d
127.00 5.72	127.00 4.11	127.00 6.68	40d
————	————	139.70 7.19	50d
————	————	152.40 7.19	60d

**SUBSTITUTION TABLE FOR IRRIGATION  
COMPONENTS**

METRIC WATER METERS, TRUCK LOADING STANDPIPES, VALVES, BACKFLOW PREVENTERS, FLOW SENSORS, WYE STRAINERS, FILTER ASSEMBLY UNITS, PIPE SUPPLY LINES, AND PIPE IRRIGATION SUPPLY LINES SHOWN ON THE PLANS DIAMETER NOMINAL (DN) mm	NOMINAL SIZE TO BE SUBSTITUTED  inch
15	1/2
20	3/4
25	1
32	1-1/4
40	1-1/2
50	2
65	2-1/2
75	3
100	4
150	6
200	8
250	10
300	12
350	14
400	16

Unless otherwise specified, substitutions of United States Standard Measures standard structural shapes corresponding to the metric designations shown on the plans and in conformance with the requirements in ASTM Designation: A 6/A 6M, Annex 2, will be allowed.

**8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS**

The Department maintains the following list of Prequalified and Tested Signing and Delineation Materials. The Engineer shall not be precluded from sampling and testing products on the list of Prequalified and Tested Signing and Delineation Materials.

The manufacturer of products on the list of Prequalified and Tested Signing and Delineation Materials shall furnish the Engineer a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of traffic product supplied.

For those categories of materials included in the list of Prequalified and Tested Signing and Delineation Materials, only those products shown within the listing may be used in the work. Other categories of products, not included in the list of Prequalified and Tested Signing and Delineation Materials, may be used in the work provided they conform to the requirements of the Standard Specifications.

Materials and products may be added to the list of Prequalified and Tested Signing and Delineation Materials if the manufacturer submits a New Product Information Form to the New Product Coordinator at the Transportation Laboratory. Upon a Departmental request for samples, sufficient samples shall be submitted to permit performance of required tests. Approval of materials or products will depend upon compliance with the specifications and tests the Department may elect to perform.

**PAVEMENT MARKERS, PERMANENT TYPE  
Retroreflective With Abrasion Resistant Surface (ARS)**

- A. Apex, Model 921AR (100 mm x 100 mm)

- B. Avery Dennison (formerly Stimsonite), Models C88 (100 mm x 100 mm), 911 (100 mm x 100 mm) and 953 (70 mm x 114 mm)
- C. Ray-O-Lite, Model "AA" ARS (100 mm x 100 mm)
- D. 3M Series 290 (89 mm x 100 mm)

**Retroreflective With Abrasion Resistant Surface (ARS)**

(for recessed applications only)

- A. Avery Dennison (formerly Stimsonite), Model 948 (58 mm x 119 mm)
- B. Avery Dennison (formerly Stimsonite), Model 944SB (51 mm x 100 mm)\*
- C. Ray-O-Lite, Model 2002 (58 mm x 117 mm)
- D. Ray-O-Lite, Model 2004 ARS (51 mm x 100 mm)\*

\*For use only in 114 mm wide (older) recessed slots

**Non-Reflective For Use With Epoxy Adhesive, 100 mm Round**

- A. Apex Universal (Ceramic)

**Non-Reflective For Use With Bitumen Adhesive, 100 mm Round**

- A. Alpine Products, "D-Dot" and "ANR" (ABS)
- B. Apex Universal (Ceramic)
- C. Apex Universal, Models 929 (ABS) and 929PP (Polypropylene)
- D. Elgin Molded Plastics, "Empco-Lite" Model 900 (ABS)
- E. Hi-Way Safety, Inc., Models P20-2000W and 2001Y (ABS)
- F. Interstate Sales, "Diamond Back" (ABS) and (Polypropylene)
- G. Novabrite Models Adot-w (White) Adot-y (Yellow), (ABS)
- H. Road Creations, Model RCB4NR (Acrylic)
- I. Zumar Industries, "Titan TM40A" (ABS)

**PAVEMENT MARKERS, TEMPORARY TYPE**

**Temporary Markers For Long Term Day/Night Use (6 months or less)**

- A. Apex Universal, Model 924 (100 mm x 100 mm)
- B. Elgin Molded Plastics, "Empco-Lite" Model 901 (100 mm x 100 mm)
- C. Road Creations, Model R41C (100 mm x 100 mm)
- D. Vega Molded Products "Temporary Road Marker" (75 mm x 100 mm)

**Temporary Markers For Short Term Day/Night Use (14 days or less)**

(For seal coat or chip seal applications, clear protective covers are required)

- A. Apex Universal, Model 932
- B. Bunzl Extrusion, Models T.O.M., T.R.P.M., and "HH" (High Heat)
- C. Hi-Way Safety, Inc., Model 1280/1281

**STRIPING AND PAVEMENT MARKING MATERIAL**

**Permanent Traffic Striping and Pavement Marking Tape**

- A. Advanced Traffic Marking, Series 300 and 400
- B. Brite-Line, Series 1000
- C. Brite-Line, "DeltaLine XRP"
- D. Swarco Industries, "Director 35" (For transverse application only)
- E. Swarco Industries, "Director 60"
- F. 3M, "Stamark" Series 380 and 5730
- G. 3M, "Stamark" Series 420 (For transverse application only)

**Temporary (Removable) Striping and Pavement Marking Tape (6 months or less)**

- A. Advanced Traffic Marking, Series 200
- B. Brite-Line, Series 100
- C. Garlock Rubber Technologies, Series 2000
- D. P.B. Laminations, Aztec, Grade 102
- E. Swarco Industries, "Director-2"

- F. Trelleborg Industri, R140 Series
- G. 3M, Series 620 "CR", and Series A750
- H. 3M, Series A145, Removable Black Line Mask  
(Black Tape: for use only on Asphalt Concrete Surfaces)
- I. Advanced Traffic Marking Black "Hide-A-Line"  
(Black Tape: for use only on Asphalt Concrete Surfaces)
- J. Brite-Line "BTR" Black Removable Tape  
(Black Tape: for use only on Asphalt Concrete Surfaces)
- K. Trelleborg Industri, RB-140  
(Black Tape: for use only on Asphalt Concrete Surfaces)

**Preformed Thermoplastic (Heated in place)**

- A. Avery Dennison, "Hotape"
- B. Flint Trading, "Premark" and "Premark 20/20 Flex"

**Ceramic Surfacing Laminate, 150 mm x 150 mm**

- A. Safeline Industries/Highway Ceramics, Inc.

**CLASS 1 DELINEATORS**

**One Piece Driveable Flexible Type, 1700 mm**

- A. Bunzl Extrusion, "Flexi-Guide Models 400 and 566"
- B. Carsonite, Curve-Flex CFRM-400
- C. Carsonite, Roadmarker CRM-375
- D. FlexStake, Model 654 TM
- E. GreenLine Models HWD1-66 and CGD1-66
- F. J. Miller Industries, Model JMI-375 (with soil anchor)

**Special Use Flexible Type, 1700 mm**

- A. Bunzl Extrusion, Model FG 560 (with 450 mm U-Channel base)
- B. Carsonite, "Survivor" (with 450 mm U-Channel base)
- C. Carsonite, Roadmarker CRM-375 (with 450 mm U-Channel base)
- D. FlexStake, Model 604
- E. GreenLine Models HWDU and CGD (with 450 mm U-Channel base)
- F. Safe-Hit with 200 mm pavement anchor (SH248-GP1)
- G. Safe-Hit with 380 mm soil anchor (SH248-GP2) and with 450 mm soil anchor (SH248-GP3)

**Surface Mount Flexible Type, 1200 mm**

- A. Bent Manufacturing Company, Masterflex Model MF-180EX-48
- B. Carsonite, "Super Duck II"
- C. FlexStake, Surface Mount, Models 704 and 754 TM

**CHANNELIZERS**

**Surface Mount Type, 900 mm**

- A. Bent Manufacturing Company, Masterflex Models MF-360-36 (Round) and MF-180-36 (Flat)
- B. Bunzl Extrusion, Flex-Guide Models FG300LD and FG300UR
- C. Carsonite, "Super Duck" (Flat SDF-436, Round SDR-336)
- D. Carsonite, "Super Duck II" Model SDCF203601MB "The Channelizer"
- E. FlexStake, Surface Mount, Models 703 and 753 TM
- F. GreenLine, Model SMD-36
- G. Hi-Way Safety, Inc. "Channel Guide Channelizer" Model CGC36
- H. Repo, Models 300 and 400
- I. Safe-Hit, Guide Post, Model SH236SMA
- J. The Line Connection, "Dura-Post" Model DP36-3 (Permanent)
- K. The Line Connection, "Dura-Post" Model DP36-3C (Temporary)

**CONICAL DELINEATORS, 1070 mm**

(For 700 mm Traffic Cones, see Standard Specifications)

- A. Bent Manufacturing Company "T-Top"
- B. Plastic Safety Systems "Navigator-42"
- C. Radiator Specialty Company "Enforcer"
- D. Roadmaker Company "Stacker"
- E. TrafFix Devices "Grabber"

#### **OBJECT MARKERS**

##### **Type "K", 450 mm**

- A. Carsonite, Model SMD 615
- B. FlexStake, Model 701 KM
- C. Repo, Models 300 and 400
- D. Safe-Hit, Model SH718SMA
- E. The Line Connection, Model DP21-4K

##### **Type "K-4" / "Q" Object Markers, 600 mm**

- A. Bent Manufacturing "Masterflex" Model MF-360-24
- B. Bunzl Extrusion, Model FG324PE
- C. Carsonite, Super Duck II
- D. FlexStake, Model 701KM
- E. Repo, Models 300 and 400
- F. Safe-Hit, Models SH8 24SMA\_WA and SH8 24GP3\_WA
- G. The Line Connection, Model DP21-4Q

#### **CONCRETE BARRIER MARKERS AND TEMPORARY RAILING (TYPE K) REFLECTORS**

##### **Impactable Type**

- A. ARTUK, "FB"
- B. Bunzl Extrusion, Model PCBM-12
- C. Duraflex Corp., "Flexx 2020" and "Electriflexx"
- D. Hi-Way Safety, Inc., Model GMKRM100
- E. Sun-Lab Technology, "Safety Guide Light Model TM-5"

##### **Non-Impactable Type**

- A. ARTUK, JD Series
- B. Vega Molded Products, Models GBM and JD

#### **THREE BEAM BARRIER MARKERS**

(For use to the left of traffic)

- A. Bunzl Extrusion, "Mini" (75 mm x 254 mm)
- B. Duraflex Corp., "Railrider"

#### **CONCRETE BARRIER DELINEATORS, 400 mm**

(For use to the right of traffic)

- A. Bunzl Extrusion, Model PCBM T-16
- B. Safe-Hit, Model SH216RBM
- C. Sun-Lab Technology, "Safety Guide Light, Model TM16," 75 mm x 300 mm

#### **CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm)**

- A. Stinson Equipment Company "SaddleMarker"

#### **SOUND WALL DELINEATOR**

(Applied vertically. Place top of 75 mm x 300 mm reflective element at 1200 mm above roadway)

- A. Bunzl Extrusion, PCBM S-36
- B. Sun-Lab Technology, "Safety Guide Light, Model SM12," 75 mm x 300 mm

## **GUARD RAILING DELINEATOR**

(Place top of reflective element at 1200 mm above plane of roadway)

### **Wood Post Type, 686 mm**

- A. Bunzl Extrusion, FG 427 and FG 527
- B. Carsonite, Model 427
- C. FlexStake, Model 102 GR
- D. GreenLine GRD 27
- E. J. Miller Model JMI-375G
- F. Safe-Hit, Model SH227GRD

### **Steel Post Type**

- A. Carsonite, Model CFGR-327 with CFGRBK300 Mounting Bracket

## **RETROREFLECTIVE SHEETING**

### **Channelizers, Barrier Markers, and Delineators**

- A. Avery Dennison T-6500 Series (Formerly Stimsonite, Series 6200) (For rigid substrate devices only)
- B. Nippon Carbide, Flexible Ultralite Grade (ULG) II
- C. Reflexite, PC-1000 Metalized Polycarbonate
- D. Reflexite, AC-1000 Acrylic
- E. Reflexite, AP-1000 Metalized Polyester
- F. Reflexite, Conformalight, AR-1000 Abrasion Resistant Coating
- G. 3M, High Intensity

### **Traffic Cones, 330 mm Sleeves**

- A. Reflexite SB (Polyester), Vinyl or "TR" (Semi-transparent)

### **Traffic Cones, 100 mm and 150 mm Sleeves**

- A. Nippon Carbide, Flexible Ultralite Grade (ULG) II
- B. Reflexite, Vinyl, "TR" (Semi-transparent) or "Conformalight"
- C. 3M Series 3840

### **Barrels and Drums**

- A. Avery Dennison W-6100
- B. Nippon Carbide, Flexible Ultralite Grade (ULG) II
- C. Reflexite, "Conformalight", "Super High Intensity" or "High Impact Drum Sheeting"
- D. 3M Series 3810

### **Barricades: Type I, Medium-Intensity (Typically Enclosed Lens, Glass-Bead Element)**

- A. American Decal, Adcolite
- B. Avery Dennison, T-1500 and T-1600 series
- C. 3M Engineer Grade, Series 3170

### **Barricades: Type II, Medium-High-Intensity (Typically Enclosed Lens, Glass-Bead Element)**

- A. Avery Dennison, T-2500 Series
- B. Kiwalite Type II
- C. Nikkalite 1800 Series

### **Signs: Type II, Medium-High-Intensity (Typically Enclosed Lens, Glass-Bead Element)**

- A. Avery Dennison, T-2500 Series
- B. Kiwalite, Type II
- C. Nikkalite 1800 Series

### **Signs: Type III, High-Intensity (Typically Encapsulated Glass-Bead Element)**

- A. Avery Dennison, T-5500 Series
- B. Nippon Carbide, Nikkalite Brand Ultralite Grade II

- C. 3M Series 3870

**Signs: Type IV, High-Intensity (Typically Unmetallized Microprismatic Element)**

- A. Avery Dennison, T-6500 Series (Formerly Stimsonite Series 6200)

**Signs: Type VI, Elastomeric (Roll-Up) High-Intensity, without Adhesive**

- A. Reflexite "Vinyl" (Orange)
- B. Reflexite "SuperBright" (Fluorescent orange)
- C. Reflexite "Marathon" (Fluorescent orange)
- D. 3M Series RS34 (Orange) and RS20 (Fluorescent orange)

**Signs: Type VII, Super-High-Intensity (Typically Unmetallized Microprismatic Element)**

- A. 3M LDP Series 3970

**Signs: Type VIII, Super-High-Intensity (Typically Unmetallized Microprismatic Element)**

- A. Avery Dennison, T-7500 Series

**SPECIALTY SIGNS**

- A. All Sign Products, STOP Sign (All Plastic), 750 mm
- B. Relexite "Endurance" Work Zone Sign

**SIGN SUBSTRATE**

**Fiberglass Reinforced Plastic (FRP)**

- A. Fiber-Brite
- B. Sequentia, "Polyplate"

**Aluminum**

**8-1.03 STATE-FURNISHED MATERIALS**

Attention is directed to Section 6-1.02, "State-Furnished Materials," of the Standard Specifications and these special provisions.

The following materials will be furnished to the Contractor:

- A. Sign panels for roadside signs .
- B. Hardware for mounting sign panels as follows:
  - 1. Blind rivets for mounting overlapping legend at sign panel joints.
  - 2. Closure inserts.
  - 3. Aluminum bolts and nuts and steel beveled washers for mounting laminated sign panels on overhead sign structures.
  - 4. Aluminum bolts, nuts, and washers for mounting overhead formed panels.
- C. Padlocks for walk gates, and irrigation controller enclosure cabinets.
- D. Reflective numbers and edge sealer for numbering electrical equipment.

Reflective numbers and edge sealer for numbering electrical equipment will be furnished to the Contractor at the following address:

Department of Transportation  
District Maintenance Yard  
9153 Lower Azusa Avenue.  
Rosemead, CA 91770  
Telephone (626) 286-7849

The Contractor shall notify the Engineer not less than fifteen working days before State-furnished material is to be picked up by the Contractor. A full description of the material and the time the material will be picked up shall be provided.

#### **8-1.04 SLAG AGGREGATE**

Aggregate produced from slag resulting from any steel-making process or from air-cooled iron blast furnace slag shall not be used on this project.

#### **8-1.05 ENGINEERING FABRICS**

Engineering fabrics shall conform to the provisions in Section 88, "Engineering Fabrics," of the Standard Specifications and these special provisions.

Filter fabric for this project shall be ultraviolet (UV) ray protected.

### **SECTION 8-2. CONCRETE**

#### **8-2.01 PORTLAND CEMENT CONCRETE**

Portland cement concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions.

References to Section 90-2.01, "Portland Cement," of the Standard Specifications shall mean Section 90-2.01, "Cement," of the Standard Specifications.

Mineral admixture shall be combined with cement in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures," of the Standard Specifications for the concrete materials specified in Section 56-2, "Roadside Signs," of the Standard Specifications.

The requirements of Section 90-4.08, "Required Use of Mineral Admixture," of the Standard Specifications shall not apply to Section 19-3.025C, "Soil Cement Bedding," of the Standard Specifications.

The Department maintains a list of sources of fine and coarse aggregate that have been approved for use with a reduced amount of mineral admixture in the total amount of cementitious material to be used. A source of aggregate will be considered for addition to the approved list if the producer of the aggregate submits to the Transportation Laboratory certified test results from a qualified testing laboratory that verify the aggregate complies with the requirements. Prior to starting the testing, the aggregate test shall be registered with the Department. A registration number can be obtained by calling (916) 227-7228. The registration number shall be used as the identification for the aggregate sample in correspondence with the Department. Upon request, a split of the tested sample shall be provided to the Department. Approval of aggregate will depend upon compliance with the specifications, based on the certified test results submitted, together with any replicate testing the Department may elect to perform. Approval will expire 3 years from the date the most recent registered and evaluated sample was collected from the aggregate source.

Qualified testing laboratories shall conform to the following requirements:

- A. Laboratories performing ASTM Designation: C 1293 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Concrete Proficiency Sample Program and shall have received a score of 3 or better on all tests of the previous 2 sets of concrete samples.
- B. Laboratories performing ASTM Designation: C 1260 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Pozzolan Proficiency Sample Program and shall have received a score of 3 or better on the shrinkage and soundness tests of the previous 2 sets of pozzolan samples.

Aggregates on the list shall conform to one of the following requirements:

- A. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1293, the average expansion at one year shall be less than or equal to 0.040 percent; or
- B. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1260, the average of the expansion at 16 days shall be less than or equal to 0.15 percent.

The amounts of cement and mineral admixture used in cementitious material shall be sufficient to satisfy the minimum cementitious material content requirements specified in Section 90-1.01, "Description," or Section 90-4.05, "Optional Use of Chemical Admixtures," of the Standard Specifications and shall conform to the following:

- A. The minimum amount of cement shall not be less than 75 percent by mass of the specified minimum cementitious material content.
- B. The minimum amount of mineral admixture to be combined with cement shall be determined using one of the following criteria:

1. When the calcium oxide content of a mineral admixture is equal to or less than 2 percent by mass, the amount of mineral admixture shall not be less than 15 percent by mass of the total amount of cementitious material to be used in the mix.
  2. When the calcium oxide content of a mineral admixture is greater than 2 percent by mass, and any of the aggregates used are not listed on the approved list as specified in these special provisions, then the amount of mineral admixture shall not be less than 25 percent by mass of the total amount of cementitious material to be used in the mix.
  3. When the calcium oxide content of a mineral admixture is greater than 2 percent by mass and the fine and coarse aggregates are listed on the approved list as specified in these special provisions, then the amount of mineral admixture shall not be less than 15 percent by mass of the total amount of cementitious material to be used in the mix.
  4. When a mineral admixture that conforms to the provisions for silica fume in Section 90-2.04, "Admixture Materials," of the Standard Specifications is used, the amount of mineral admixture shall not be less than 10 percent by mass of the total amount of cementitious material to be used in the mix.
  5. When a mineral admixture that conforms to the provisions for silica fume in Section 90-2.04, "Admixture Materials," of the Standard Specifications is used and the fine and coarse aggregates are listed on the approved list as specified in these special provisions, then the amount of mineral admixture shall not be less than 7 percent by mass of the total amount of cementitious material to be used in the mix.
- C. The total amount of mineral admixture shall not exceed 35 percent by mass of the total amount of cementitious material to be used in the mix. Where Section 90-1.01, "Description," of the Standard Specifications specifies a maximum cementitious content in kilograms per cubic meter, the total mass of cement and mineral admixture per cubic meter shall not exceed the specified maximum cementitious material content.

The Contractor will be permitted to use Type III portland cement for concrete used in the manufacture of precast concrete members.

## SECTION 8-3. WELDING

### 8-3.01 WELDING

#### GENERAL

Flux core welding electrodes conforming to the requirements of AWS A5.20 E6XT-4 or E7XT-4 shall not be used to perform welding for this project.

Wherever reference is made to the following AWS welding codes in the Standard Specifications, on the plans, or in these special provisions, the year of adoption for these codes shall be as listed:

AWS Code	Year of Adoption
D1.1	2000
D1.4	1998
D1.5	1995
D1.5 (metric only)	1996

Requirements of the AWS welding codes shall apply unless specified otherwise in the Standard Specifications, on the plans, or in these special provisions. Wherever the abbreviation AWS is used, it shall be equivalent to the abbreviations ANSI/AWS or ANSI/AASHTO/AWS.

Sections 6.1.2 through 6.1.4.3 of AWS D 1.1, Sections 7.1.1 and 7.1.2 of AWS D 1.4, and Sections 6.1.1.1 through 6.1.3.3 of AWS D 1.5 are replaced with the following:

Quality Control (QC) shall be the responsibility of the Contractor. As a minimum, the Contractor shall perform inspection and testing of each weld joint prior to welding, during welding, and after welding as specified in this section and as necessary to ensure that materials and workmanship conform to the requirements of the contract documents.

The QC Inspector shall be the duly designated person who acts for and on behalf of the Contractor for inspection, testing, and quality related matters for all welding.

Quality Assurance (QA) is the prerogative of the Engineer. The QA Inspector is the duly designated person who acts for and on behalf of the Engineer.

The QC Inspector shall be responsible for quality control acceptance or rejection of materials and workmanship, and shall be currently certified as an AWS Certified Welding Inspector (CWI) in conformance with the requirements in AWS QC1, "Standard and Guide for Qualification of Welding Inspectors."

The QC Inspector may be assisted by an Assistant QC Inspector provided that this individual is currently certified as an AWS Certified Associate Welding Inspector (CAWI) in conformance with the requirements in AWS QC1, "Standard and Guide for Qualification of Welding Inspectors," or has equivalent qualifications. The QC Inspector shall monitor the Assistant QC Inspector's work, and shall be responsible for signing all reports.

When the term "Inspector" is used without further qualification, it shall refer to the QC Inspector.

Section 6.14.6, "Personnel Qualification," of AWS D 1.1, Section 7.7.6, "Personnel Qualification," of AWS D 1.4, and Section 6.1.3.4, "Personnel Qualification," of AWS D 1.5 are replaced with the following:

Personnel performing nondestructive testing (NDT) shall be qualified and certified in conformance with the requirements of the American Society for Nondestructive Testing (ASNT) Recommended Practice No. SNT-TC-1A and the Written Practice of the NDT firm. The Written Practice of the NDT firm shall meet or exceed the guidelines of the ASNT Recommended Practice No. SNT-TC-1A. Only individuals who are 1) certified as an NDT Level II, or 2) Level III technicians who hold a current ASNT Level III certificate in that discipline and are authorized and certified to perform the work of Level II technicians, shall perform NDT, review the results, and prepare the written reports.

Section 6.5.4, "Scope of Examination," of AWS D 1.1 and Section 7.5.4 of AWS D 1.4 are replaced with the following:

The QC Inspector shall inspect and approve each joint preparation, assembly practice, welding technique, and the performance of each welder, welding operator, and tack welder to make certain that the applicable requirements of this code and the approved welding procedure specification (WPS) are met.

Section 6.5.4 of AWS D 1.5 is replaced with the following:

The QC Inspector shall inspect and approve each joint preparation, assembly practice, welding technique, and the performance of each welder, welding operator, and tack welder to make certain that the applicable requirements of this code and the approved WPS are met. The QC Inspector shall examine the work to make certain that it meets the requirements of Sections 3 and 9.21. The size and contour of all welds shall be measured using suitable gages. Visual inspection for cracks in welds and base metal, and for other discontinuities should be aided by strong light magnifiers, or such other devices as may be helpful. Acceptance criteria different from those specified in this code may be used when approved by the Engineer.

Section 6.6.5, "Nonspecified Nondestructive Testing Other Than Visual," of AWS D 1.1, Section 6.6.5 of AWS D 1.4 and Section 6.6.5 of AWS D 1.5 shall not apply.

For any welding, the Engineer may direct the Contractor to perform NDT that is in addition to the visual inspection or NDT specified in the AWS welding codes, in the Standard Specifications, or in these special provisions. Additional NDT required by the Engineer, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications. Should any welding deficiencies be discovered by this additional NDT, the cost of the testing will not be paid for as extra work but shall be at the Contractor's expense.

Required repair work to correct welding deficiencies, whether discovered by the required visual inspection or NDT, or by additional NDT directed by the Engineer, and any associated delays or expenses caused to the Contractor by performing these repairs, shall be at the Contractor's expense.

The Engineer shall have the authority to verify the qualifications or certifications of any welder, QC Inspector, or NDT personnel to specified levels by retests or other means.

A sufficient number of QC Inspectors shall be provided to ensure continuous inspection when any welding is being performed. Continuous inspection, as a minimum, shall include (1) having QC Inspectors continually present on the shop floor or project site when any welding operation is being performed, and (2) having a QC Inspector within such close proximity of all welding operations so that inspections by the QC Inspector of each operation, at each welding location, shall not lapse for a period exceeding 30 minutes.

Inspection and approval of all joint preparations, assembly practices, welding techniques, and the performance of each welder, welding operator, and tack welder shall be documented by the QC Inspector on a daily basis for each day that welding is performed. The QC Inspector shall confirm and document compliance with the requirements of the AWS code criteria and the requirements of these special provisions on all weld joints before welding, during welding, and after the completion of each weld.

When joint details that are not prequalified by the applicable AWS codes are proposed for use in the work, welders using these details shall perform a qualification test plate using the approved WPS variables and the joint detail to be used in production. The test plate shall be the maximum thickness to be used in production. The test plate shall be mechanically or radiographically tested as directed by the Engineer. Mechanical and radiographic testing and acceptance criteria shall be as specified in the applicable AWS codes.

The period of effectiveness for a welder's or welding operator's qualification shall be a maximum of 3 years for the same weld process, welding position, and weld type. A valid qualification at the beginning of work on a contract will be acceptable for the entire period of the contract, as long as the welder's work remains satisfactory.

### **WELDING QUALITY CONTROL**

Welding quality control shall conform to the requirements in the AWS welding codes, the Standard Specifications, and these special provisions.

Unless otherwise specified, welding quality control shall apply when any work is welded in conformance with the provisions in Section 49, "Piling," Section 52, "Reinforcement," Section 55, "Steel Structures," Section 56-1, "Overhead Sign Structures," Section 75-1.035, "Bridge Joint Restrainer Units," or Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.

The welding of fracture critical members (FCMs) shall conform to the provisions specified in the Fracture Control Plan (FCP) and herein.

The Contractor shall designate in writing a welding Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for the quality of welding, including materials and workmanship, performed by the Contractor and subcontractors.

The QCM shall be the sole individual responsible to the Contractor for submitting, receiving, and approving all correspondence, required submittals, and reports to and from the Engineer.

The QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

Welding inspection personnel or NDT firms to be used in the work shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project, except for the following conditions:

- A. The welding is performed at a permanent fabrication or manufacturing facility which is certified under the AISC Quality Certification Program, Category Cbr, Major Steel Bridges.
- B. The welding is performed at a permanent fabrication or manufacturing facility which is certified under the AISC Quality Certification Program, Category Sbd, Conventional Steel Building Structures. This condition shall apply only for work welded in conformance with the provisions in Section 56-1, "Overhead Sign Structures" or Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.
- C. The welding is performed on pipe pile material at a permanent pipe manufacturing facility where an automatic welding process or seamless pipe operation is used in conformance with the requirements in the applicable welding code as specified elsewhere in these special provisions.

For welding performed at such facilities, the inspection personnel or NDT firms may be employed or compensated by the facility performing the welding.

Prior to submitting the Welding Quality Control Plan (WQCP) required herein, a pre-welding meeting between the Engineer, Contractor, and any entity performing welding for this project, shall be held to discuss the requirements for the WQCP.

The Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate WQCP for each item of work for which welding is to be performed.

The Contractor shall allow the Engineer 2 weeks to review the WQCP submittal after a complete plan has been received. Except for work that is welded in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, and for pipe piling produced at a permanent manufacturing facility as specified above, no welding shall be performed until the WQCP is approved in writing by the Engineer. Materials welded in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, and pipe piling produced at such permanent manufacturing facilities, shall not be incorporated into the work until the WQCP is approved in writing by the Engineer. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the

Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

An amended WQCP or any addendum to the approved WQCP shall be submitted to, and approved in writing by the Engineer, for proposed revisions to the approved WQCP. An amended WQCP or addendum will be required for revisions to the WQCP, including but not limited to a revised WPS, additional welders, changes in NDT firms or procedures, QC, or NDT personnel, or updated systems for tracking and identifying welds. The Engineer shall have 3 working days to complete the review of the amended WQCP or addendum. Work affected by the proposed revisions shall not be performed until the amended WQCP or addendum has been approved. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Each WQCP shall include the applicable portions of the following, as determined by the Engineer:

- A. The name of the welding firm and any required NDT inspection personnel or firms.
- B. A manual prepared by the NDT inspection personnel or firm that shall include equipment, testing procedures, code of safe practices, the Written Practice of the NDT inspection personnel or firm, and the names, qualifications, and documentation of certifications for all personnel to be used.
- C. The name of the QCM and the names, qualifications, and documentation of certifications for all QC Inspectors and Assistant QC Inspectors to be used.
- D. An organizational chart showing all QC personnel and their assigned QC responsibilities.
- E. The methods and frequencies for performing all required quality control procedures, including QC inspection forms to be used, as required by the specifications including:
  1. all visual inspections.
  2. all NDT including radiographic geometry, penetrometer and shim selection, film quality, film processing, radiograph identification and marking system, and film interpretation and reports.
  3. calibration procedures and calibration frequency for all NDT equipment.
- F. A system for the identification and tracking of all welds, NDT, and any required repairs, and a procedure for the reinspection of repaired welds. The system shall have provisions for 1) permanently identifying each weld and the person who performed the weld, 2) placing all identification and tracking information on each radiograph, 3) a method of reporting nonconforming welds to the Engineer, and 4) a method of documentation of repairs and reinspection of nonconforming welds.
- G. Standard procedures for performing noncritical repair welds. Noncritical repair welds are defined as welds to deposit additional weld beads or layers to compensate for insufficient weld size and to fill limited excavations that were performed to remove unacceptable edge or surface discontinuities, rollover or undercut. The depth of these excavations shall not exceed 65 percent of the specified weld size.
- H. The WPS, including documentation of all supporting Procedure Qualification Record (PQR) tests performed, and the name of the testing laboratory who performed the tests, to verify the acceptability of the WPS. The submitted WPS shall be within the allowable period of effectiveness.
- I. Documentation of all certifications for welders for each weld process and position that will be used. Certifications shall list the electrodes used, test position, base metal and thickness, tests performed, and the witnessing authority. All certifications shall be within the allowable period of effectiveness.
- J. One authorized copy or original code book for each of all AWS welding codes and the FCP which are applicable to the welding to be performed. These codes and the FCP shall become the permanent property of the Department.
- K. Forms to be used for Certificates of Compliance, daily production logs, and daily reports.

After final approval of the WQCP, amended WQCP, or addendum, the Contractor shall submit 7 copies to the Engineer of the approved documents.

It is expressly understood that the Engineer's approval of the Contractor's WQCP shall not relieve the Contractor of any responsibility under the contract for the successful completion of the work in conformance with the requirements of the plans and specifications. The Engineer's approval shall not constitute a waiver of any requirement of the plans and specifications nor relieve the Contractor of any obligation thereunder; and defective work, materials, and equipment may be rejected notwithstanding approval of the WQCP.

A daily production log for welding shall be kept by the QCM for each day that welding is performed. The log shall clearly indicate the locations of all welding, except partial penetration longitudinal seam welds performed in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications. The log shall include the

welders' names, amount of welding performed, any problems or deficiencies discovered, and any testing or repair work performed, at each location. The daily report from each QC Inspector shall also be included in the log.

The following items shall be included in a Welding Report that is to be submitted to the Engineer within 7 days following the performance of any welding. For work welded in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, and for piling produced at a permanent manufacturing facility, the following items shall be included in a Welding Report that is to be submitted to the Engineer 48 hours prior to furnishing a Certificate of Compliance for the material:

- A. Reports of all visual weld inspections and NDT.
- B. Radiographs and radiographic reports, and other required NDT reports.
- C. Documentation that the Contractor has evaluated all radiographs and other nondestructive tests and corrected all rejectable deficiencies, and all repaired welds have been reexamined by the required NDT and found acceptable.
- D. Daily production log.

Radiographic envelopes shall have clearly written on the outside of the envelope the following information: name of the QCM, name of the nondestructive testing firm, name of the radiographer, date, contract number, complete part description, and all included weld numbers or a report number, as detailed in the WQCP. In addition, all innerleaves shall have clearly written on them the part description and all included weld numbers, as detailed in the WQCP.

Reports regarding NDT, including radiographs, shall be signed by both the NDT technician and the person that performed the review, and then submitted directly to the QCM for review and signature prior to submittal to the Engineer. Corresponding names shall be clearly printed or typewritten next to all signatures.

The Engineer will review the Welding Report to determine if the Contractor is in conformance with the WQCP. Unless otherwise specified, the Engineer shall be allowed 7 working days to review the report and respond in writing after a complete Welding Report has been received. Prior to receiving notification from the Engineer of the Contractor's conformance with the WQCP, the Contractor may encase in concrete or cover welds for which a Welding Report has been submitted. However, should the Contractor elect to encase or cover those welds prior to receiving notification from the Engineer, it is expressly understood that the Contractor shall not be relieved of the responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase or cover welds pending notification by the Engineer, and in the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The QC Inspector shall provide reports to the QCM on a daily basis for each day that welding is performed.

Except for noncritical weld repairs, the Engineer shall be notified immediately in writing when welding problems, deficiencies, base metal repairs, or any other type of repairs not submitted in the WQCP are discovered and also of the proposed repair procedures to correct them. The Contractor shall allow the Engineer one week to review these procedures. No remedial work shall begin until the repair procedures are approved in writing by the Engineer. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The QCM shall sign and furnish to the Engineer, a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each item of work for which welding was performed. The certificate shall state that all of the materials and workmanship incorporated in the work, and all required tests and inspections of this work, have been performed in conformance with the details shown on the plans, the Standard Specifications, and these special provisions.

## **PAYMENT**

Full compensation for conforming to the requirements of this section shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

## **SECTION 9. DESCRIPTION OF BRIDGE WORK**

EUCLID AVENUE UNDERCROSSING  
(BRIDGE NUMBER 53-0601)

Contract No. 07-053514

The bridge work to be done in this location shall consist of the following: removing portions of an existing three span concrete box girder superstructure, abutments, bents and wingwalls; replacing the removed portions of superstructure with cast-in-place box girder superstructure; constructing concrete barrier slabs on cast-in-drilled hole piles at existing wingwalls; constructing sound wall (barrier) (masonry block) and concrete barrier on bridge deck and barrier slab; and relocating communication conduits and galvanized sheet metal cover from south side of bridge (Bridge No. 53-0601) to the existing barrier at north side of bridge (Bridge No. 53-1364).

EUCLID AVENUE OFF-RAMP UNDERCROSSING  
(BRIDGE NUMBER 53-1389L)

The bridge work to be done in this location shall consist of the following: removing portions of an existing single span concrete slab superstructure, wingwalls and retaining walls; replacing the removed portions of superstructure with cast-in-place concrete edge beam and slab; constructing concrete barrier slabs at existing wingwalls and retaining walls; constructing sound wall (barrier) (masonry block) and concrete barrier on bridge deck and barrier slab; and construct sound wall (barrier) (masonry block) and concrete barrier on cast-in-drilled hole piles.

SOTO STREET UNDERCROSSING  
(BRIDGE NUMBER 53-1390R)

The bridge work to be done in this location shall consist of the following: removing portions of an existing three span concrete box girder superstructure and adjacent retaining wall; replacing overhang and construct sound wall (barrier) (masonry block), concrete barrier and bent cap extensions on existing superstructure; and constructing sound wall (barrier) (masonry block), concrete barrier, barrier slab and paving notch extension at existing retaining wall.

MARIETTA STREET UNDERCROSSING  
(BRIDGE NUMBER 53-1392L)

The bridge work to be done in this location shall consist of the following: removing portions of an existing three span concrete box girder superstructure and wingwalls; replacing overhang and construct sound wall (barrier) (masonry block), concrete barrier and bent cap extensions on existing superstructure; and constructing sound wall (barrier) (masonry block), concrete barrier and barrier slab on cast-in-drilled hole piles at existing wingwalls.

The bridge work to be done consists, in general, of installation of lighting and communication system routing equipment at the following structures:

Installation of new fiber optic and twisted pair cables, and removal of existing cables in existing communication conduits

Marietta Street Undercrossing  
(Bridge No. 53-0600)

Installation of new fiber optic and twisted pair cables, and new communication conduits Euclid Avenue Undercrossing  
(Bridge No. 53-1364)

Removal of existing fiber optic and twisted pair cables and communication conduits  
Euclid Avenue Undercrossing  
(Bridge No. 53-0601)

Installation of new lighting conduits  
Marietta Street Undercrossing  
(Bridge No. 53-1392L)

Installation of new lighting conduits  
Euclid Avenue Off-ramp Undercrossing  
(Bridge No. 53-1389L)

Installation of new lighting conduits  
Euclid Avenue Undercrossing  
Contract No. 07-053514

**SECTION 10. CONSTRUCTION DETAILS**

**SECTION 10-1. GENERAL**

**10-1.00 CONSTRUCTION PROJECT INFORMATION SIGNS**

Before any major physical construction work readily visible to highway users is started on this contract, the Contractor shall furnish and erect 2 Type 2 Construction Project Information signs at the locations designated by the Engineer.

The signs and overlays shall be of a type and material consistent with the estimated time of completion of the project and shall conform to the details shown on the plans.

The sign letters, border and the Department's construction logos shall conform to the colors (non-reflective) and details shown on the plans, and shall be on a white background (non-reflective). The colors blue and orange shall conform to PR Color Number 3 and Number 6, respectively, as specified in the Federal Highway Administration's Color Tolerance Chart.

The sign message to be used for fund types shall consist of the following, in the order shown:

FEDERAL HIGHWAY TRUST FUNDS
STATE HIGHWAY FUNDS

The sign message to be used for type of work shall consist of the following:

**HIGHWAY IMPROVEMENT**

The sign message to be used for the Year of Completion of Project Construction will be furnished by the Engineer. The Contractor shall furnish and install the "Year" sign overlay within 10 working days of notification of the year date to be used.

The letter sizes to be used shall be as shown on the plans. The information shown on the signs shall be limited to that shown on the plans.

The signs shall be kept clean and in good repair by the Contractor.

Upon completion of the work, the signs shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications.

Full compensation for furnishing, erecting, maintaining, and removing and disposing of the construction project information signs shall be considered as included in the contract lump sum price paid for construction area signs and no additional compensation will be allowed therefor.

**10-1.01 ORDER OF WORK**

Order of work shall conform to the provisions in Section 5-1.05, "Order of Work," of the Standard Specifications and these special provisions.

Attention is directed to "Access to the Work Area" of these special provisions regarding the use of temporary construction easement.

The closure pour shall be placed after the soundwall has been constructed full-height on the bridge deck.

Temporary railing (Type K) and temporary crash cushions shall be secured in place prior to commencing work for which the temporary railing and crash cushions are required.

The first order of work shall be to place the order for the communication system routing and electrical equipment, to perform the jointly conducted pre-construction check with the Engineer according to the provisions under "Maintaining Existing and Temporary Electrical Systems," as described under "Service," of these special provisions, and to perform the communication system routing (modify) work according to the provisions under "communication system routing (modify)," as described elsewhere in these special provisions, prior to the commencement of any road works.

The Contractor shall furnish the Engineer with a statement from the vendor that the order for fiber optic cables, communication system routing equipment, and the electrical materials required for this contract has been received and accepted by the vendor; and the statement shall be furnished within 15 calendar days after the contract has been approved by the Attorney General, or the attorney appointed and authorized to represent the Department of Transportation. The statement shall give the date that the electrical materials will be shipped. If the Contractor has the necessary materials on hand, the Contractor will not be required to furnish the vendor's statement.

The Contractor shall notify the Engineer to arrange for an electrical inspector, 24 hours prior to starting electrical work.

Attention is directed to "Communication System Cut-Over" elsewhere in these special provisions regarding orderly disconnection of existing communications system routing equipment and the cut over connection, activation and testing of the modified communications system routing.

No later than 20 days after approval of the contract, the Contractor shall submit in advance to the Engineer:

1. A list of materials, including, but not limited to, fiber optic cable splice closures, fiber optic cables, twisted pair cable splice closures, and twisted pair cables, that would be used in the event of damage caused by Contractor's works, or others, to the existing communications system routing.
2. A plan to meet the requirements of Communications System Routing restrictions, as described under "Maintaining Existing Communication Systems Routing Facilities," elsewhere in these special provisions.
3. A proposed schedule specifying the timetable of construction activities as described under "Communication Systems Routing (Modify)," elsewhere in these special provisions.

The Engineer, in consultation with the District 7 Office of TMC Support, will have 20 days to review, comment, reject, or approve each item on the list of materials, the plan for Communications System Routing restrictions, and the proposed schedule for the of construction activity timetable.

Should the Engineer fail to complete the review within 20 days, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the list of materials, the plan for Communications System Routing restrictions, and the proposed schedule for the of construction activity timetable, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications

The Contractor will resubmit for any rejected items within 10 days.

Attention is directed to "Maintaining Traffic" and "Temporary Pavement Delineation" of these special provisions .

At the end of each working day if a difference in excess of 45-mm exists between the elevation of the existing pavement and the elevation of excavations within 2.4 m of the traveled way, material shall be placed and compacted against the vertical cuts adjacent to the traveled way. During excavation operations, native material may be used for this purpose; however, once placing of the structural section commences, structural material shall be used. The material shall be placed to the level of the elevation of the top of existing pavement and tapered at a slope of 1:4 (vertical:horizontal) or flatter to the bottom of the excavation. Full compensation for placing the material on a 1:4 slope, regardless of the number of times the material is required, and subsequent removing or reshaping of the material to the lines and grades shown on the plans shall be considered as included in the contract price paid for the materials involved and no additional compensation will be allowed therefor. No payment will be made for material placed in excess of that required for the structural section.

At those locations exposed to public traffic where guard railings are to be constructed, or removed , the Contractor shall schedule operations so that at the end of each working day there shall be no post holes open nor shall there be any railing posts installed without the blocks and rail elements assembled and mounted thereon.

Not less than 20 days prior to planting the plants, the Contractor shall furnish the Engineer a statement from the vendor that the order for the plants required for this contract, including inspection plants, has been received and accepted by the vendor. The statement from the vendor shall include the names, sizes, and quantities of plants ordered and the anticipated date of delivery.

The Contractor shall place orders for replacement plants with the vendor at the appropriate time so that the roots of the replacement plants are not in a root-bound condition.

Attention is directed to "Irrigation Systems Functional Test" of these special provisions, regarding restrictions for planting operations.

Attention is directed to "Locate Existing Crossovers and Conduits" of these special provisions regarding locating existing irrigation water line crossovers and conduits shown on the plans to be incorporated in the new work. Existing irrigation water line crossovers and conduits shall be located prior to performing work on the soundwalls.

Attention is directed to "Existing Highway Irrigation Facilities" of these special provisions regarding the checking of existing irrigation facilities that are to remain in place, prior to the start of any work.

Clearing, grubbing, and earthwork operations shall not be performed in areas where existing irrigation facilities are to remain in place until existing irrigation facilities have been checked for proper operation in conformance with the provisions in "Existing Highway Irrigation Facilities" of these special provisions.

Existing conduits to be extended shall be located in conformance with the provisions in "Extend Irrigation Crossovers" of these special provisions prior to the start of other work in these areas.

Attention is directed to Section 20-5.027B, "Wiring Plans and Diagrams," of the Standard Specifications regarding submittal of working drawings.

Attention is directed to "Irrigation Controller Enclosure Cabinet" of these special provisions regarding preinstalling irrigation components in the irrigation controller enclosure cabinet prior to field installation.

## **10-1.02 WATER POLLUTION CONTROL**

Water pollution control work shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications and these special provisions.

Water pollution control work shall conform to the requirements in the "Storm Water Pollution Prevention Plan (SWPPP) and Water Pollution Control Program (WPCP) Preparation Manual" and the "Construction Site Best Management Practices (BMPs) Manual," and addenda thereto issued up to, and including, the date of advertisement of the project. These manuals are hereinafter referred to respectively as the "Preparation Manual" and the "Construction Site BMPs Manual," and collectively, as the "Manuals." Copies of the Manuals may be obtained from the Department of Transportation, Material Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520, and may also be obtained from the Department's Internet website at: <http://www.dot.ca.gov/hq/construc/stormwater.html>.

The Contractor shall know and fully comply with applicable provisions of the Manuals, and Federal, State, and local regulations and requirements that govern the Contractor's operations and storm water and non-storm water discharges from both the project site and areas of disturbance outside the project limits during construction. Attention is directed to Sections 7-1.01, "Laws to be Observed," and 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

Water pollution control requirements shall apply to storm water and non-storm water discharges from areas outside the project site which are directly related to construction activities for this contract including, but not limited to, asphalt batch plants, material borrow areas, concrete plants, staging areas, storage yards and access roads. The Contractor shall comply with the Manuals for those areas and shall implement, inspect and maintain the required water pollution control practices. Installing, inspecting and maintaining water pollution control practices on areas outside the highway right of way not specifically arranged and provided for by the Department for the execution of this contract, will not be paid for.

The Contractor shall be responsible for penalties assessed or levied on the Contractor or the Department as a result of the Contractor's failure to comply with the provisions in this section "Water Pollution Control" including, but not limited to, compliance with the applicable provisions of the Manuals, and Federal, State and local regulations and requirements as set forth therein.

Penalties as used in this section shall include fines, penalties and damages, whether proposed, assessed, or levied against the Department or the Contractor, including those levied under the Federal Clean Water Act and the State Porter-Cologne Water Quality Control Act, by governmental agencies or as a result of citizen suits. Penalties shall also include payments made or costs incurred in settlement for alleged violations of the Manuals, or applicable laws, regulations, or requirements. Costs incurred could include sums spent instead of penalties, in mitigation or to remediate or correct violations.

### **RETENTION OF FUNDS**

Notwithstanding any other remedies authorized by law, the Department may retain money due the Contractor under the contract, in an amount determined by the Department, up to and including the entire amount of Penalties proposed, assessed, or levied as a result of the Contractor's violation of the Manuals, or Federal or State law, regulations or requirements. Funds may be retained by the Department until final disposition has been made as to the Penalties. The Contractor shall remain liable for the full amount of Penalties until such time as they are finally resolved with the entity seeking the Penalties.

Retention of funds for failure to conform to the provisions in this section, "Water Pollution Control," shall be in addition to the other retention amounts required by the contract. The amounts retained for the Contractor's failure to conform to provisions in this section will be released for payment on the next monthly estimate for partial payment following the date when an approved WPCP has been implemented and maintained, and when water pollution has been adequately controlled, as determined by the Engineer.

When a regulatory agency identifies a failure to comply with the Manuals, or other Federal, State or local requirements, the Department may retain money due the Contractor, subject to the following:

- A. The Department will give the Contractor 30 days notice of the Department's intention to retain funds from partial payments which may become due to the Contractor prior to acceptance of the contract. Retention of funds from payments made after acceptance of the contract may be made without prior notice to the Contractor.
- B. No retention of additional amounts out of partial payments will be made if the amount to be retained does not exceed the amount being withheld from partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications.
- C. If the Department has retained funds, and it is subsequently determined that the State is not subject to the entire amount of the Costs and Liabilities assessed or proposed in connection with the matter for which the retention was made, the Department shall be liable for interest on the amount retained for the period of the retention. The interest rate payable shall be 6 percent per annum.

During the first estimate period that the Contractor fails to conform to the provisions in this section, "Water Pollution Control," the Department may retain an amount equal to 25 percent of the estimated value of the contract work performed.

The Contractor shall notify the Engineer immediately upon request from the regulatory agencies to enter, inspect, sample, monitor, or otherwise access the project site or the Contractor's records pertaining to water pollution control work. The Contractor and the Department shall provide copies of correspondence, notices of violations, enforcement actions or proposed fines by regulatory agencies to the requesting regulatory agency.

#### **WATER POLLUTION CONTROL PROGRAM PREPARATION, APPROVAL AND AMENDMENTS**

As part of the water pollution control work, a Water Pollution Control Program (WPCP) is required for this contract. The WPCP shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications, the requirements in the Manuals, and these special provisions. Upon the Engineer's approval of the WPCP, the WPCP shall be considered to fulfill the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications for development and submittal of a Water Pollution Control Program.

No work having potential to cause water pollution, shall be performed until the WPCP has been approved by the Engineer. Approval shall not constitute a finding that the WPCP complies with applicable requirements of the Manuals and applicable Federal, State and local laws, regulations, and requirements.

The Contractor shall designate a Water Pollution Control Manager. The Water Pollution Control Manager shall be responsible for the preparation of the WPCP and required modifications or amendments, and shall be responsible for the implementation and adequate functioning of the various water pollution control practices employed. The Contractor may designate different Water Pollution Control Managers to prepare the WPCP and to implement the water pollution control practices. The Water Pollution Control Managers shall serve as the primary contact for issues related to the WPCP or its implementation. The Contractor shall assure that the Water Pollution Manager(s) have adequate training and qualifications necessary to prepare the WPCP, implement and maintain water pollution control practices.

Within 10 working days after the approval of the contract, the Contractor shall submit 3 copies of the draft WPCP to the Engineer. The Engineer will have 10 working days to review the WPCP. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the WPCP within 10 working days of receipt of the Engineer's comments. The Engineer will have 5 working days to review the revisions. Upon the Engineer's approval of the WPCP, 4 approved copies of the WPCP, incorporating the required changes, shall be submitted to the Engineer. In order to allow construction activities to proceed, the Engineer may conditionally approve the WPCP while minor revisions are being completed. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for resulting losses, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The WPCP shall incorporate water pollution control practices in the following categories:

- A. Soil stabilization.
- B. Sediment control.
- C. Wind erosion control.
- D. Tracking control.
- E. Non-storm water management.
- F. Waste management and materials pollution control.

The Contractor shall develop a Water Pollution Control Schedule that describes the timing of grading or other work activities that could affect water pollution. The Water Pollution Control Schedule shall be updated by the Contractor to reflect changes in the Contractor's operations that would affect the necessary implementation of water pollution control practices.

The Contractor shall complete the BMP checklists for each of the six categories presented in Section 3 of the Preparation Manual and shall incorporate the completed checklists and water pollution control practices into Sections 30.1, 30.2, and 30.3 of the WPCP. Water pollution control practices include the "Minimum Requirements" and other Contractor-selected water pollution control practices from the BMP checklists and "Project-Specific Minimum Requirements" identified in the Water Pollution Control Cost Break-Down of this section.

The WPCP shall include, but not be limited to, the items described in the Manuals and related information contained in the contract documents. The Contractor shall prepare an amendment to the WPCP when there is a change in construction activities or operations which may affect the discharge of pollutants to surface waters, ground waters, municipal storm drain systems, or when the Contractor's activities or operations violate Federal, State or local regulations, or when directed by the Engineer. Amendments shall identify additional water pollution control practices or revised operations, including those areas or operations not identified in the initially approved WPCP. Amendments to the WPCP shall be prepared and submitted for

review and approval within a time approved by the Engineer, but in no case longer than the time specified for the initial submittal and review of the WPCP.

The Contractor shall keep one copy of the approved WPCP and approved amendments at the project site. The WPCP shall be made available upon request by a representative of the Regional Water Quality Control Board, State Water Resources Control Board, United States Environmental Protection Agency, or the local storm water management agency. Requests by the public shall be directed to the Engineer.

### **COST BREAK-DOWN**

The Contractor shall include a Water Pollution Control Cost Break-Down in the WPCP which itemizes the contract lump sum for water pollution control work. The Contractor shall use the Water Pollution Control Cost Break-Down provided in this section as the basis for the cost break-down submitted with the WPCP. The Contractor shall use the Water Pollution Control Cost Break-Down to identify items, quantities and values for water pollution control work, excluding Temporary Water Pollution Control Practices for which there is a separate bid item. The Contractor shall be responsible for the accuracy of the quantities and values used in the cost break-down submitted with the WPCP. Partial payment for the item of water pollution control will not be made until the Water Pollution Control Cost Break-Down is approved by the Engineer.

Line items indicated in the Water Pollution Control Cost Break-Down in this section with a specified Estimated Quantity shall be considered a "Project-Specific Minimum Requirement." The Contractor shall incorporate the items with Contractor-designated quantities and values into the Water Pollution Control Cost Break-Down submitted with the WPCP.

Line items indicated in the Water Pollution Control Cost Break-Down in this section without a specified Estimated Quantity shall be considered by the Contractor for selection to meet the applicable "Minimum Requirements" as defined in the Manuals, or for other water pollution control work as identified in the BMP checklists presented in Section 3 of the Preparation Manual. In the Water Pollution Control Cost Break-Down submitted with the WPCP, the Contractor shall list only those water pollution control practices selected for the project, including quantities and values required to complete the work for those items.

The sum of the amounts for the items of work listed in the Water Pollution Control Cost Break-Down shall be equal to the contract lump sum price bid for water pollution control. Overhead and profit, shall be included in each individual item listed in the cost break-down.

## WATER POLLUTION CONTROL COST BREAK-DOWN

Contract No. 07-053514

ITEM	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY	VALUE	AMOUNT
SS-3	Hydraulic Mulch	M2			
SS-4	Hydroseeding	M2			
SS-5	Soil Binders	M2			
SS-6	Straw Mulch	M2			
SS-7	Geotextiles, Plastic Covers & Erosion Control Blankets/Mats	M2			
SS-8	Wood Mulching	M2			
SS-9	Earth Dikes/Drainage Swales & Lined Ditches	M			
SS-10	Outlet Protection/Velocity Dissipation Devices	EA			
SS-11	Slope Drains	EA			
SC-1	Silt Fence	M			
SC-2	Desilting Basin	EA			
SC-3	Sediment Trap	EA			
SC-4	Check Dam	EA			
SC-5	Fiber Rolls	M			
SC-6	Gravel Bag Berm	M			
SC-7	Street Sweeping and Vacuuming	LS			
SC-8	Sandbag Barrier	M			
SC-9	Straw Bale Barrier	M			
SC-10	Storm Drain Inlet Protection	EA			
WE-1	Wind Erosion Control	LS			
TC-1	Stabilized Construction Entrance/Exit	EA			
TC-2	Stabilized Construction Roadway	EA			
TC-3	Entrance/Outlet Tire Wash	EA			
NS-1	Water Conservation Practices	LS			
NS-2	Dewatering Operations	EA			
NS-3	Paving and Grinding Operations	LS			
NS-4	Temporary Stream Crossing	EA			
NS-5	Clear Water Diversion	EA			
NS-6	Illicit Connection/Illegal Discharge Detection and Reporting	LS			

Contract No. 07-053514

ITEM	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY	VALUE	AMOUNT
NS-7	Potable Water/Irrigation	LS			
NS-8	Vehicle and Equipment Cleaning	LS			
NS-9	Vehicle and Equipment Fueling	LS			
NS-10	Vehicle and Equipment Maintenance	LS			
WM-1	Material Delivery and Storage	LS			
WM-2	Material Use	LS			
WM-3	Stockpile Management	LS			
WM-4	Spill Prevention and Control	LS			
WM-5	Solid Waste Management	LS			
WM-6	Hazardous Waste Management	LS			
WM-7	Contaminated Soil Management	LS			
WM-8	Concrete Waste Management	LS			
WM-9	Sanitary/Septic Waste Management	LS			
WM-10	Liquid Waste Management	LS			

**TOTAL** \_\_\_\_\_

Adjustments in the items of work and quantities listed in the approved cost break-down shall be made when required to address amendments to the WPCP, except when the adjusted items are paid for as extra work.

No adjustment in compensation will be made to the contract lump sum price paid for water pollution control due to differences between the quantities shown in the approved cost break-down and the quantities required to complete the work as shown on the approved WPCP. No adjustment in compensation will be made for ordered changes to correct WPCP work resulting from the Contractor's own operations or from the Contractor's negligence.

The approved cost break-down will be used to determine partial payments during the progress of the work and as the basis for calculating the adjustment in compensation for the item of water pollution control due to increases or decreases of quantities ordered by the Engineer. When an ordered change increases or decreases the quantities of an approved cost break-down item, the adjustment in compensation will be determined in the same manner specified for increases and decreases in the quantity of a contract item of work in conformance with the provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications. If an ordered change requires a new item which is not on the approved cost break-down, the adjustment in compensation will be determined in the same manner specified for extra work in conformance with Section 4-1.03D, "Extra Work," of the Standard Specifications.

If requested by the Contractor and approved by the Engineer, changes to the water pollution control practices listed in the approved cost break-down, including addition of new water pollution control practices, will be allowed. Changes shall be included in the approved amendment of the WPCP. If the requested changes result in a net cost increase to the lump sum price for water pollution control, an adjustment in compensation will be made without change to the water pollution control item. The net cost increase to the water pollution control item will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

### **WPCP IMPLEMENTATION**

Unless otherwise specified, upon approval of the WPCP, the Contractor shall be responsible throughout the duration of the project for installing, constructing, inspecting, maintaining, removing, and disposing of the water pollution control practices specified in the WPCP and in the amendments. Unless otherwise directed by the Engineer, the Contractor's responsibility for WPCP implementation shall continue throughout any temporary suspension of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. Requirements for installation, construction, inspection, maintenance, removal, and disposal of water pollution control practices shall conform to the requirements in the Manuals and these special provisions.

If the Contractor or the Engineer identifies a deficiency in the implementation of the approved WPCP or amendments, the deficiency shall be corrected immediately. The deficiency may be corrected at a later date and time if requested by the Contractor and approved by the Engineer in writing, but shall be corrected prior to the onset of precipitation. If the Contractor fails to correct the identified deficiency by the date agreed or prior to the onset of precipitation, the project shall be in nonconformance with this section. Attention is directed to Section 5-1.01, "Authority of Engineer," of the Standard Specifications, and to "Retention of Funds" of this section for possible nonconformance penalties.

If the Contractor fails to conform to the provisions of this section, "Water Pollution Control," the Engineer may order the suspension of construction operations until the project complies with the requirements of this section.

Implementation of water pollution control practices may vary by season. The Construction Site BMPs Manual and these special provisions shall be followed for control practice selection of year-round, rainy season and non-rainy season water pollution control practices.

#### **Year-Round Implementation Requirements**

The Contractor shall have a year-round program for implementing, inspecting and maintaining water pollution control practices for wind erosion control, tracking control, non-storm water management, and waste management and materials pollution control.

The National Weather Service weather forecast shall be monitored and used by the Contractor on a daily basis. An alternative weather forecast proposed by the Contractor may be used if approved by the Engineer. If precipitation is predicted, the necessary water pollution control practices shall be deployed prior to the onset of the precipitation.

Disturbed soil areas shall be considered active whenever the soil disturbing activities have occurred, continue to occur or will occur during the ensuing 21 days. Nonactive areas shall be protected as prescribed in the Construction Site BMPs Manual within 14 days of cessation of soil disturbing activities or prior to the onset of precipitation, whichever occurs first.

#### **Rainy Season Implementation Requirements**

Soil stabilization and sediment control practices conforming to the requirements of these special provisions shall be provided throughout the rainy season, defined as between October 1 and May 1.

An implementation schedule of required soil stabilization and sediment control practices for disturbed soil areas shall be completed no later than 20 days prior to the beginning of each rainy season. The implementation schedule shall identify the soil stabilization and sediment control practices and the dates when the implementation will be 25 percent, 50 percent and 100 percent complete, respectively. For construction activities beginning during the rainy season, the Contractor shall implement applicable soil stabilization and sediment control practices.

### **Non-Rainy Season Implementation Requirements**

The non-rainy season shall be defined as days outside the defined rainy season. The Contractor's attention is directed to the Construction Site BMPs Manual for soil stabilization and sediment control implementation requirements on disturbed soil areas during the non-rainy season. Disturbed soil areas within the project shall be protected in conformance with the requirements in the Construction Site BMPs Manual with an effective combination of soil stabilization and sediment control.

### **MAINTENANCE**

To ensure the proper implementation and functioning of water pollution control practices, the Contractor shall regularly inspect and maintain the construction site for the water pollution control practices identified in the WPCP. The construction site shall be inspected by the Contractor as follows:

- A. Prior to a forecast storm.
- B. After a precipitation event which causes site runoff.
- C. At 24 hour intervals during extended precipitation events.
- D. Routinely, a minimum of once every two weeks outside of the defined rainy season.
- E. Routinely, a minimum of once every week during the defined rainy season.

The Contractor shall use the Storm Water Quality Construction Site Inspection Checklist provided in the Preparation Manual or an alternative inspection checklist provided by the Engineer. One copy of each site inspection record shall be submitted to the Engineer within 24 hours of completing the inspection.

### **REPORTING REQUIREMENTS**

#### **Report of Discharges, Notices or Orders**

If the Contractor identifies discharges into surface waters or drainage systems in a manner causing, or potentially causing, a condition of pollution, or if the project receives a written notice or order from a regulatory agency, the Contractor shall immediately inform the Engineer. The Contractor shall submit a written report to the Engineer within 7 days of the discharge event, notice or order. The report shall include the following information:

- A. The date, time, location, nature of the operation, and type of discharge, including the cause or nature of the notice or order.
- B. The water pollution control practices deployed before the discharge event, or prior to receiving the notice or order.
- C. The date of deployment and type of water pollution control practices deployed after the discharge event, or after receiving the notice or order, including additional measures installed or planned to reduce or prevent reoccurrence.
- D. An implementation and maintenance schedule for affected water pollution control practices.

#### **Report of First-Time Non-Storm Water Discharge**

The Contractor shall notify the Engineer at least 3 days in advance of first-time non-storm water discharge events. The Contractor shall notify the Engineer of the operations causing non-storm water discharges and shall obtain field approval for first-time non-storm water discharges. Non-storm water discharges shall be monitored at first-time occurrences and routinely thereafter.

### **PAYMENT**

The contract lump sum price paid for prepare water pollution control program shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals for doing all the work involved in developing, preparing, obtaining approval of, revising, and amending the WPCP, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Attention is directed to Section 9-1.06, "Partial Payments," and Section 9-1.07, "Payment After Acceptance," of the Standard Specifications. Payments for Prepare Water Pollution Control Program will be made as follows:

- A. After the WPCP has been approved by the Engineer, 75 percent of the contract item price for Prepare Water Pollution Control Program will be included in the monthly partial payment estimate.
- B. After acceptance of the contract in conformance with the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, payment for the remaining 25 percent of the contract item price for Prepare Water Pollution Control Program will be made in conformance with the provisions in Section 9-1.07.

The contract lump sum price paid for water pollution control shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing, constructing, maintaining, removing, and disposing of water pollution control practices, including non-storm water management, and waste management and materials pollution water pollution control practices, except those for which there is a contract item of work as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Water pollution control practices for which there is a contract item of work will be measured and paid for as that contract item of work.

**10-1.03 TEMPORARY SUPPORTS**

Temporary supports for existing structures during bridge removal, reconstruction, and retrofit work shall be designed, furnished, constructed, monitored, maintained, and removed in conformance with the provisions in these special provisions.

Construction sequence and application of temporary support jacking loads shall be as shown on the plans. Proposed changes to the construction sequence and application of temporary support jacking loads shall be subject to the Engineer's approval.

Temporary supports shall include jacking assemblies and appurtenant items necessary to jack and support the structures.

Attention is directed to the sections "Order of Work" and "Maintaining Traffic" of these special provisions regarding the construction sequences and the required openings in temporary supports for the use of public traffic.

Approval by the Engineer of the temporary support working drawings or temporary support inspection performed by the Engineer will in no way relieve the Contractor of full responsibility for the temporary supports.

**TEMPORARY SUPPORT DESIGN AND DRAWINGS**

The Contractor shall submit to the Engineer working drawings and design calculations for the temporary supports. Such drawings and design calculations shall be signed by an engineer who is registered as a Civil Engineer in the State of California. The temporary support working drawings and design calculations shall conform to the requirements in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The number of sets of drawings and design calculations and times for review for temporary supports shall be the same as specified for falsework working drawings in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications.

In addition to the requirements in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications, the following requirements shall apply:

- A. The time to be provided for the Engineer's review of the working drawings for specific structures, or portions thereof, shall be as follows:

Structure or Portion of Structure	Review Time - Weeks
Location A Euclid Avenue Undercrossing	5
Location B Euclid Avenue Off-Ramp Undercrossing	5

Working drawings for any part of the temporary supports shall include stress sheets, anchor bolt layouts, shop details, and erection and removal plans.

The temporary support working drawings shall include descriptions and values of all loads, including construction equipment loads, descriptions of equipment to be used, complete details and calculations for jacking and supporting the existing structure, and descriptions of the displacement monitoring system. The displacement monitoring system shall include equipment to be used, location of control points, method and schedule of taking measurements, and shall also include provisions to jack the structure should settlement occur in the temporary supports.

A redundant system of supports shall be provided during the entire jacking operation for backup should any of the jacks fail. The redundant system shall include stacks of steel plates added as necessary to maintain the redundant supports at each jack location within 6 mm of the jacking sill or corbels.

For temporary supports over railroads, approval by the Engineer of the temporary support drawings will be contingent upon the drawings being satisfactory to the railroad company involved.

When footing type foundations are to be used, the Contractor shall determine the bearing value of the soil and shall show the values assumed in the design of the temporary supports on the temporary support drawings. Anticipated temporary support foundation settlement shall be shown on the temporary support drawings.

When pile type foundations are to be used, the temporary support drawings shall show the maximum horizontal distance that the top of a temporary support pile may be pulled in order to position it under its cap. The temporary support plans shall also show the maximum allowed deviation of the top of the pile, in its final position, from a vertical line through the point of fixity of the pile.

The Contractor may use the permanent piles as part of the temporary support foundation. Permanent piles shall not be moved or adjusted from the locations shown on the plans. Any use of the permanent piles and the loads imposed on them shall be shown on the temporary support drawings. Should the Contractor propose to provide piles longer than required for the work in order to support the temporary supports above the elevation of the top of the footing and later cut off the piles at their final elevation, shear devices adequate to transfer all pile reactions into the footing will be required.

Temporary support footings shall be designed to carry the load imposed upon them without exceeding the estimated soil bearing values and anticipated settlements.

Bracing shall be provided, as necessary, to withstand all imposed loads during erection and removal of any temporary supports. The temporary support drawings shall show provisions for such temporary bracing or methods to be used to conform to these requirements during each phase of erection and removal. Wind loads shall be included in the design of such bracing or methods. Wind loads shall conform to the applicable provisions in Section 51-1.06A(1), "Design Loads," of the Standard Specifications.

The temporary support design calculations shall show a summary of computed stresses in the (1) temporary supports, (2) connections between temporary supports and the existing structure and (3) existing load supporting members. The computed stresses shall include the effect of the jacking sequence. The temporary support design calculations shall also include a lateral stiffness assessment of the temporary support system and conform to the design values shown on the plans.

The design of temporary supports will not be approved unless it is based on the use of loads and conditions which are no less severe than those described in "Temporary Support Design Criteria," of these special provisions and on the use of allowable stresses which are no greater than those described in Section 51-1.06A(2), "Design Stresses, Loadings, and Deflections," of the Standard Specifications.

If falsework loads are imposed on temporary supports, the temporary supports shall also satisfy the deflection criteria described in Section 51-1.06A(2), "Design Stresses, Loadings, and Deflections," of the Standard Specifications.

### **TEMPORARY SUPPORT DESIGN CRITERIA**

The temporary supports shall support the initial jacking loads and the minimum temporary support design loads and the minimum lateral design forces shown on the plans. The vertical design loads shall be adjusted for the weight of temporary supports and jacks, construction equipment loads and additional loads imposed by the Contractor's operations. The construction equipment loads shall be the actual weight of the construction equipment but in no case shall be less than  $960 \text{ N/m}^2$  of deck surface area of the frame involved. A frame is defined as the portion of the bridge between expansion joints.

The temporary supports shall resist the specified lateral design forces applied at the point where the column to be removed meets the superstructure. The lateral design forces to be resisted shall be increased to be compatible with the temporary support lateral stiffness if the stiffness exceeds the specified minimum. The temporary supports resisting transverse lateral loads shall be placed within a distance of not more than 0.5 of the span length from the existing bent. The temporary supports resisting longitudinal lateral loads shall be placed within the frame having columns removed.

The existing structure shall be mechanically connected to the temporary supports. The temporary supports shall be mechanically connected to their foundations. The mechanical connections shall be capable of resisting the lateral temporary support design forces. Friction forces developed between the existing structure and temporary supports shall not be used to reduce the lateral forces and shall not be considered as an effective mechanical connection. The mechanical connections shall be designed to tolerate adjustments to the temporary support frame throughout the use of the temporary supports.

If the concrete is to be prestressed, the temporary supports shall be designed to support any increased or readjusted loads caused by the prestressing forces.

### **Manufactured Assemblies**

Manufactured assemblies shall conform to the provisions in Section 51-1.06A(2), "Design Stresses, Loadings, and Deflections," of the Standard Specifications and these special provisions.

Each jack shall be equipped with either a pressure gage or a load cell for determining the jacking force. Pressure gages shall have an accurately reading dial at least 150 mm in diameter. Each jack shall be calibrated by a private laboratory

approved by the Transportation Laboratory within 6 months prior to use and after each repair. Each jack and its gage shall be calibrated as a unit with the cylinder extension in the approximate position that it will be at final jacking force and shall be accompanied by a certified calibration chart. Load cells shall be calibrated and provided with an indicator by which the jacking force is determined.

### **SPECIAL LOCATIONS**

Attention is directed to Section 51-1.06A(3), "Special Locations," of the Standard Specifications. All reference to falsework in this section shall also apply to temporary supports.

### **TEMPORARY SUPPORT CONSTRUCTION**

Attention is directed to paragraphs 1 through 7 of Section 51-1.06B, "Falsework Construction," of the Standard Specifications. All reference to falsework in these paragraphs shall also apply to temporary supports.

Welding, welder qualification, and inspection of welding for all steel members shall conform to the requirements of ANSI/AASHTO/AWS D1.1.

Prior to proceeding with bridge removal, an engineer for the Contractor who is registered as a Civil Engineer in the State of California shall inspect the temporary supports, including jacking and displacement monitoring systems, for conformity with the working drawings. The Contractor's registered engineer shall certify in writing that the temporary supports, including jacking and displacement monitoring systems, conform to the working drawings, and that the material and workmanship are satisfactory for the purpose intended. A copy of this certification shall be available at the site of the work at all times.

The Contractor's registered engineer shall be present at the bridge site at all times when jacking operations or adjustments are in progress and when bridge removal operations are in progress. The Contractor's registered engineer shall inspect the jacking and removal operation and report in writing on a daily basis the progress of the operation and the status of the remaining structure. A copy of the daily report shall be available at the site of the work at all times. Should an unplanned event occur, the Contractor's registered engineer shall submit immediately to the Engineer for approval, the procedure or proposed operation to correct or remedy the occurrence.

The Contractor shall perform an initial survey as part of the displacement monitoring system to record the location of the existing structure prior to the commencement of any work. Two copies of the survey shall be signed by an engineer, who is registered as a Civil Engineer in the State of California, and submitted to the Engineer.

Vandal-resistant displacement monitoring equipment shall be provided and maintained. Vertical and horizontal displacements of the temporary supports and the existing structure shall be monitored continuously during jacking operations and shall be accurately measured and recorded at least weekly during removal and reconstruction work. As a minimum, elevations shall be taken prior to the start of jacking operations, immediately after jacking is complete, after bridge removal is complete, before connecting the retrofitted superstructure to the substructure, and after the temporary supports have been removed. As a minimum, the existing structure shall be monitored at the bent and at mid span of both adjoining spans. Control points at each location shall be located near the center and at both edges of the superstructure. The records of vertical and horizontal displacement shall be signed by an engineer who is registered as a Civil Engineer in the State of California and available to the Engineer at the jobsite during normal working hours, and a copy of the record shall be delivered to the Engineer at the completion of reconstructing each bent.

A force equal to the initial jacking load or the dead load shown on the plans shall be applied to the structure by the temporary support system and held until all initial compression and settlement of the system is completed before bridge removal work at the location being supported is begun.

Jacking operations shall be carefully controlled and monitored to ensure that the jacking loads are applied simultaneously to prevent distortion and excessive stresses that would damage the structure. The superstructure shall be jacked as necessary to maintain the total vertical displacements at control points to less than 6 mm from the elevations recorded prior to jacking or as modified by the Engineer.

Should unanticipated displacements, cracking or other damage occur, the construction shall be discontinued until corrective measures satisfactory to the Engineer are performed. Damage to the structure as a result of the Contractor's operations shall be repaired by the Contractor in conformance with the provisions in Section 7-1.11, "Preservation of Property," of the Standard Specifications.

Following completion of the reconstruction, the monitored control points shall not deviate from the vertical position by more than 6 mm from the initial survey elevations or the elevations as modified by the Engineer.

### **REMOVING TEMPORARY SUPPORTS**

Attention is directed to Section 51-1.06C, "Removing Falsework," of the Standard Specifications. All references to falsework in this section shall also apply to temporary supports, except that when public traffic is carried on the structure on

temporary supports no temporary supports shall be released until the supported concrete has attained 100 percent of the specified strength.

Attachments shall be removed from the existing structure and concrete surfaces restored to original conditions, except where permanent alterations are shown on the plans.

#### **PAYMENT**

The contract lump sum price paid for temporary supports (Location A and Location B) shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in designing, constructing, maintaining, and removing the temporary supports, including jacking the existing structure and monitoring displacements, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

#### **10-1.04 TEMPORARY FENCE (TYPE CL-1.8)**

Temporary fence shall be furnished, constructed, maintained, and later removed as shown on the plans, as specified in these special provisions and as directed by the Engineer.

Temporary fence shall be installed on the same day that the existing fence is removed.

Temporary fence constructed shall consist of chain link fence (Type CL-1.8) with wood or plastic slats inserted vertically in the chain link fabric. The slats shall be approximately 60 mm wide with a length sufficient to fill the vertical opening of the fabric. The slats shall be inserted vertically in the mesh openings so that the slats fit snugly and shall be fastened in a manner to prevent easy removal or displacement.

Except as otherwise specified in this section, temporary fence shall conform to the plan details and the specifications for permanent fence of similar character as provided in Section 80, "Fences," of the Standard Specifications.

Used materials may be installed provided the used materials are good, sound and are suitable for the purpose intended, as determined by the Engineer.

Materials may be commercial quality provided the dimensions and sizes of the materials are equal to, or greater than, the dimensions and sizes shown on the plans or specified herein.

Posts shall be metal.

Galvanizing and painting of steel items will not be required.

Concrete footings for metal posts will not be required.

Temporary fence that is damaged during the progress of the work shall be repaired or replaced by the Contractor at the Contractor's expense.

When no longer required for the work, as determined by the Engineer, temporary fence shall be removed. Removed facilities shall become the property of the Contractor and shall be removed from the site of the work, except as otherwise provided in this section.

Attention is directed to "Reconstruct Property Side Yard Walls or Fences" of these special provisions

Holes caused by the removal of temporary fence shall be backfilled in conformance with the provisions in the second paragraph of Section 15-1.02, "Preservation of Property," of the Standard Specifications.

Temporary fence (Type CL-1.8) will be measured and paid for in the same manner specified for permanent fence of similar character as provided in Section 80, "Fences," of the Standard Specifications.

Full compensation for furnishing and inserting slats in the chain link fabric, maintaining, removing, and disposing of temporary fence shall be considered as included in the contract price paid per meter for temporary fence (Type CL-1.8) and no additional compensation will be allowed therefor.

#### **10-1.05 PRESERVATION OF PROPERTY**

Attention is directed to Section 7-1.11, "Preservation of Property," of the Standard Specifications and these special provisions.

Existing trees, shrubs and other plants, that are not to be removed as shown on the plans or specified in these special provisions, and are injured or damaged by reason of the Contractor's operations, shall be replaced by the Contractor. The minimum size of tree replacement shall be No. 15 container and the minimum size of shrub replacement shall be No. 15 container. Replacement ground cover plants shall be from flats and shall be planted 300 mm on center. Replacement planting shall conform to the requirements in Section 20-4.07, "Replacement," of the Standard Specifications. The Contractor shall water replacement plants in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Damaged or injured plants shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications. At the option of the Contractor, removed trees and shrubs may be reduced to chips.

Replacement planting of injured or damaged trees, shrubs, and other plants shall be completed prior to the start of the plant establishment period. Replacement planting shall conform to the provisions in Section 20-4.05, "Planting," of the Standard Specifications.

#### **10-1.06 RELIEF FROM MAINTENANCE AND RESPONSIBILITY**

The Contractor may be relieved of the duty of maintenance and protection for those items not directly connected with plant establishment work, except highway planting and irrigation systems in conformance with the provisions in Section 7-1.15, "Relief From Maintenance and Responsibility," of the Standard Specifications.

#### **10-1.07 COOPERATION**

Attention is directed to Section 7-1.14, "Cooperation," and Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications and these special provisions.

It is anticipated that work by another contractor (Contract No.07-496104) to construct soundwall in Los Angeles on Route 60 from Euclid Ave to Rowan Ave (KP 1.6 to KP 3.9) may be in progress adjacent to or within the limits of this project during progress of the work on this contract.

#### **10-1.08 PROGRESS SCHEDULE (CRITICAL PATH METHOD)**

The Contractor shall submit to the Engineer practicable critical path method (CPM) progress schedules in conformance with these special provisions. Whenever the term "schedule" is used in this section it shall mean CPM progress schedule.

The provisions in Section 8-1.04, "Progress Schedule," of the Standard Specifications shall not apply.

#### **DEFINITIONS**

The following definitions shall apply to this section:

- A. **ACTIVITY.**—A task, event or other project element on a schedule that contributes to completing the project. Activities have a description, start date, finish date, duration and one or more logic ties.
- B. **BASELINE SCHEDULE.**—The initial schedule representing the Contractor's work plan on the first working day of the project.
- C. **CONTRACT COMPLETION DATE.**—The current extended date for completion of the contract shown on the weekly statement of working days furnished by the Engineer in conformance with the provisions in Section 8-1.06, "Time of Completion," of the Standard Specifications.
- D. **CRITICAL PATH.**—The longest continuous chain of activities for the project that has the least amount of total float of all chains. In general, a delay on the critical path will extend the scheduled completion date.
- E. **CRITICAL PATH METHOD (CPM).**—A network based planning technique using activity durations and the relationships between activities to mathematically calculate a schedule for the entire project.
- F. **DATA DATE.**—The day after the date through which a schedule is current. Everything occurring earlier than the data date is "as-built" and everything on or after the data date is "planned."
- G. **FLOAT.**—The difference between the earliest and latest allowable start or finish times for an activity.
- H. **MILESTONE.**—An event activity that has zero duration and is typically used to represent the beginning or end of a certain stage of the project.
- I. **NEAR CRITICAL PATH.**—A chain of activities with total float exceeding that of the critical path but having no more than 10 working days of total float.
- J. **SCHEDULED COMPLETION DATE.**—The planned project finish date shown on the current accepted schedule.
- K. **TOTAL FLOAT.**—The amount of time that an activity or chain of activities can be delayed before extending the scheduled completion date.
- L. **UPDATE SCHEDULE.**—A current schedule developed from the baseline or subsequent schedule through regular monthly review to incorporate as-built progress and any planned changes.

#### **GENERAL REQUIREMENTS**

The Contractor shall submit to the Engineer baseline, monthly update and final update schedules, each consistent in all respects with the time and order of work requirements of the contract. The project work shall be executed in the sequence indicated on the current accepted schedule.

Schedules shall show the order in which the Contractor proposes to carry out the work with logical links between time-scaled work activities, and calculations made using the critical path method to determine the controlling operation or operations. The Contractor is responsible for assuring that all activity sequences are logical and that each schedule shows a coordinated plan for complete performance of the work.

The Contractor shall produce schedules using computer software and shall furnish compatible software for the Engineer's exclusive possession and use. The Contractor shall furnish network diagrams and schedule data as parts of each schedule submittal.

Schedules shall include, but not be limited to, applicable activities that show the following:

- A. Project characteristics, salient features, or interfaces, including those with outside entities, that could affect time of completion.
- B. Project start date, scheduled completion date and other milestones.
- C. Work performed by the Contractor, subcontractors and suppliers.
- D. Submittal development, delivery, review and approval, including those from the Contractor, subcontractors and suppliers.
- E. Procurement, delivery, installation and testing of materials, plants and equipment.
- F. Testing and settlement periods.
- G. Utility notification and relocation.
- H. Erection and removal of falsework and shoring.
- I. Major traffic stage switches.
- J. Finishing roadway and final cleanup.

Schedule activities shall include the following:

- A. A clear and legible description.
- B. Start and finish dates.
- C. A duration of not less than one working day, except for event activities, and not more than 20 working days, unless otherwise authorized by the Engineer.
- D. At least one predecessor and one successor activity, except for project start and finish milestones.
- E. Required constraints.

The Engineer's review and acceptance of schedules shall not waive any contract requirements and shall not relieve the Contractor of any obligation thereunder or responsibility for submitting complete and accurate information. Schedules that are rejected shall be corrected by the Contractor and resubmitted to the Engineer within 5 working days of notification by the Engineer, at which time a new review period of one week will begin.

Errors or omissions on schedules shall not relieve the Contractor from finishing all work within the time limit specified for completion of the contract. If, after a schedule has been accepted by the Engineer, either the Contractor or the Engineer discover that any aspect of the schedule has an error or omission, it shall be corrected by the Contractor on the next update schedule.

### **COMPUTER SOFTWARE**

The Contractor shall submit to the Engineer for approval a description of proposed software before delivery. The software shall be the current version of Primavera SureTrak Project Manager for Windows, or equal, and shall be compatible with Windows NT (version 4.0) operating system. If software other than SureTrak is proposed, it shall be capable of generating files that can be imported into SureTrak.

The Contractor shall furnish schedule software and all original software instruction manuals to the Engineer with submittal of the baseline schedule. The schedule software will be returned to the Contractor within 4 weeks of submittal of the final update schedule. The State will compensate the Contractor in conformance with the provisions in Section 4-1.03, "Extra Work," of the Standard Specifications for replacement of software which is damaged, lost or stolen after delivery to the Engineer.

### **NETWORK DIAGRAMS, REPORTS AND DATA**

The Contractor shall include the following for each schedule submittal:

- A. Two sets of originally plotted, time-scaled network diagrams.
- B. One 1.44-megabyte 90 mm (3.5 inch) floppy diskette containing the schedule data.

The time-scaled network diagrams shall conform to the following:

- A. Show a continuous flow of information from left to right.
- B. Be based on early start and early finish dates of activities.

- C. Clearly show the primary paths of criticality using graphical presentation.
- D. Be prepared on B-size sheets, 280 mm x 430 mm (11 inch x 17 inch), or larger size.
- E. Include a title block and a timeline on each page.

### **BASELINE SCHEDULE**

The Contractor shall submit to the Engineer a baseline schedule within 20 working days of approval of the contract. The Contractor shall allow 3 weeks for the Engineer's review after the baseline schedule and all support data are submitted. Beginning the week the baseline schedule is first submitted, the Contractor shall meet with the Engineer weekly to discuss and resolve schedule issues until the baseline schedule is accepted.

The baseline schedule shall include the entire scope of work and shall show how the Contractor plans to complete all work contemplated. The baseline schedule shall show the activities that define the critical path. Multiple critical paths and near-critical paths shall be kept to a minimum. A total of not more than 50 percent of the baseline schedule activities shall be critical or near critical, unless otherwise authorized by the Engineer.

The baseline schedule shall not extend beyond the number of working days originally provided in these special provisions. The baseline schedule shall have a data date of the first working day of the contract and not include any completed work to date. The baseline schedule shall not attribute negative float or negative lag to any activity.

### **UPDATE SCHEDULE**

The Contractor shall submit an update schedule and meet with the Engineer to review contract progress, on or before the first day of each month, beginning one month after the baseline schedule is accepted. The Contractor shall allow 2 weeks for the Engineer's review after the update schedule and all support data are submitted, except that the review period shall not start until any previous month's required schedule is accepted. Update schedules that are not accepted or rejected within the review period will be considered accepted by the Engineer.

The update schedule shall have a data date of the twenty-first day of the month or other date established by the Engineer. The update schedule shall show the status of work actually completed to date and the work yet to be performed as planned. In addition, the update schedule shall show any proposed schedule modifications including adding or deleting activities or changing activity constraints, durations or logic. The Contractor shall state in writing the reasons for any changes to activities and the critical path that result in a delay to the scheduled completion date compared to the previous accepted schedule.

### **FINAL UPDATE SCHEDULE**

The Contractor shall submit a final update, as-built schedule with actual start and finish dates for the activities, within 30 days after completion of contract work. The Contractor shall provide a written certificate with this submittal signed by the Contractor's project manager and an officer of the company stating, "To my knowledge and belief, the enclosed final update schedule reflects the actual start and finish dates of the actual activities for the project contained herein." An officer of the company may delegate in writing the authority to sign the certificate to a responsible manager.

### **RETENTION**

The Department will retain an amount equal to 25 percent of the estimated value of the work performed during each estimate period in which the Contractor fails to submit an acceptable schedule conforming to the requirements of these special provisions as determined by the Engineer. Schedule retentions will be released for payment on the next monthly estimate for partial payment following the date that acceptable schedules are submitted to the Engineer or as otherwise specified herein. Upon completion of all contract work and submittal of the final update schedule and certification, any remaining retained funds associated with this section, "Progress Schedule (Critical Path Method)", will be released for payment. Retentions held in conformance with this section shall be in addition to other retentions provided for in the contract. No interest will be due the Contractor on retention amounts.

### **PAYMENT**

Full compensation for the required schedules and software shall be considered as included in the contract prices paid for the various items of work involved, and no additional compensation will be allowed therefor.

### **10-1.09 OBSTRUCTIONS**

Attention is directed to Section 8-1.10, "Utility and Non-Highway Facilities," and Section 15, "Existing Highway Facilities," and Section 51-1.19, "Utility Facilities," of the Standard Specifications and these special provisions.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to performing any excavation or other work

close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

It is anticipated that the following utility facilities will be relocated prior to the dates shown:

Utility	Location	Date
Guy Wire	1+88.20 SW LOL "C"	10/30/02
Guy Wire	4+85.30 SW LOL "D"	10/30/02
Guy Wire	6+14.50 SW LOL "D"	10/30/02

The Contractor shall notify the Engineer in writing at least 30 days in advance of the date that work near utility facilities begins. The Engineer will, in turn, notify the owners of the utility facilities.

The utility facilities listed in the following table, and other utility facilities that possibly exist at locations which might interfere with the drilling operations or substructure construction, will not be rearranged in advance of or during construction operations. Should the Contractor desire to have any of the utility facilities rearranged or temporarily deactivated for his convenience, the Contractor shall make the necessary arrangements as provided in Section 8-1.10:

Utility Facility	Location
Water Line to be protected in place	2+84.11
Manhole to be protected in place	2+84.11

Full compensation for conforming to the requirements of this section, not otherwise provided for, shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

**10-1.10 DUST CONTROL**

Dust control shall conform to the provisions in Section 10, "Dust Control," of the Standard Specifications.

**10-1.11 MOBILIZATION**

Mobilization shall conform to the provisions in Section 11, "Mobilization," of the Standard Specifications.

**10-1.12 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES**

Flagging, signs, and all other traffic control devices furnished, installed, maintained, and removed when no longer required shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Category 1 traffic control devices are defined as those devices that are small and lightweight (less than 45 kg), and have been in common use for many years. The devices shall be known to be crashworthy by crash testing, crash testing of similar devices, or years of demonstrable safe performance. Category 1 traffic control devices include traffic cones, plastic drums, portable delineators, and channelizers.

If requested by the Engineer, the Contractor shall provide written self-certification for crashworthiness of Category 1 traffic control devices. Self-certification shall be provided by the manufacturer or Contractor and shall include the following: date, Federal Aid number (if applicable), expenditure authorization, district, county, route and kilometer post of project limits; company name of certifying vendor, street address, city, state and zip code; printed name, signature and title of certifying person; and an indication of which Category 1 traffic control devices will be used on the project. The Contractor may obtain a standard form for self-certification from the Engineer.

Category 2 traffic control devices are defined as those items that are small and lightweight (less than 45 kg), that are not expected to produce significant vehicular velocity change, but may otherwise be potentially hazardous. Category 2 traffic control devices include: barricades and portable sign supports.

Category 2 devices purchased on or after October 1, 2000 shall be on the Federal Highway Administration (FHWA) Acceptable Crashworthy Category 2 Hardware for Work Zones list. This list is maintained by FHWA and can be located at the following internet address: <http://safety.fhwa.dot.gov/fourthlevel/hardware/listing.cfm?code=workzone>. The Department maintains a secondary list at the following internet address: <http://www.dot.ca.gov/hq/traffops/signtech/signdel/pdf.htm>.

Category 2 devices that have not received FHWA acceptance, and were purchased before October 1, 2000, may continue to be used until they complete their useful service life or until January 1, 2003, whichever comes first. Category 2 devices in use that have received FHWA acceptance shall be labeled with the FHWA acceptance letter number and the name of the manufacturer by the start of the project. The label shall be readable. After January 1, 2003, all Category 2 devices without a label shall not be used on the project.

If requested by the Engineer, the Contractor shall provide a written list of Category 2 devices to be used on the project at least 5 days prior to beginning any work using the devices. For each type of device, the list shall indicate the FHWA acceptance letter number and the name of the manufacturer.

Full compensation for providing self-certification for crashworthiness of Category 1 traffic control devices and for providing a list of Category 2 devices used on the project and labeling Category 2 devices as specified shall be considered as included in the prices paid for the various contract items of work requiring the use of the Category 1 or Category 2 traffic control devices and no additional compensation will be allowed therefor.

**10-1.13 CONSTRUCTION AREA SIGNS**

Construction area signs shall be furnished, installed, maintained, and removed when no longer required in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. Type II retroreflective sheeting shall not be used on construction area sign panels.

Attention is directed to "Construction Project Information Signs" of these special provisions regarding the number and type of construction project information signs to be furnished, erected, maintained, and removed and disposed of.

The Contractor shall notify the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to commencing excavation for construction area sign posts. The regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444
	1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133
	1-800-227-2600

Excavations required to install construction area signs shall be performed by hand methods without the use of power equipment, except that power equipment may be used if it is determined there are no utility facilities in the area of the proposed post holes.

Sign substrates for stationary mounted construction area signs may be fabricated from fiberglass reinforced plastic as specified under "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

The Contractor may be required to cover certain signs during the progress of the work. Signs that are no longer required or that convey inaccurate information to the public shall be immediately covered or removed, or the information shall be corrected. Covers for construction area signs shall be of sufficient size and density to completely block out the complete face of the signs. The retroreflective face of the covered signs shall not be visible either during the day or at night. Covers shall be fastened securely so that the signs remain covered during inclement weather. Covers shall be replaced when they no longer cover the signs properly.

**10-1.14 MAINTAINING TRAFFIC**

Attention is directed to Sections 7-1.08, "Public Convenience," 7-1.09, "Public Safety," and 12, "Construction Area Traffic Control Devices," of the Standard Specifications and to the provisions in "Public Safety", "Portable Changeable Message Sign" of these special provisions and these special provisions. Nothing in these special provisions shall be construed as relieving the Contractor from the responsibilities specified in Section 7-1.09.

Lane closures shall conform to the provisions in section "Traffic Control System for Lane Closure" of these special provisions.

In addition to the provisions set forth in "Public Safety" of these special provisions, whenever work to be performed on the freeway traveled way (except the work of installing, maintaining and removing traffic control devices) is within 1.8 m of the adjacent traffic lane, the adjacent traffic lane shall be closed.

Personal vehicles of the Contractor's employees shall not be parked within the freeway right of way.

The Contractor shall notify local authorities of the Contractor's intent to begin work at least 5 days before work is begun. The Contractor shall cooperate with local authorities relative to handling traffic through the area and shall make arrangements relative to keeping the working area clear of parked vehicles.

Whenever vehicles or equipment are parked on the shoulder within 1.8 m of a traffic lane, the shoulder area shall be closed as shown on the plans.

Except as otherwise provided in these special provisions, Table Z (Lane Closure Restrictions for Designated Legal Holidays and Special Days) or as shown on the Traffic Handling Plans, freeway lanes, connectors, and ramps shall be closed only during the hours shown on Charts 1 through 9 included in this section "Maintaining Traffic." Except work required under Sections 7-1.08 and 7-1.09, work that interferes with public traffic shall be performed only during the hours shown for lane closures.

Except as otherwise provided in these special provisions, at his option, the Contractor may work during the hours designated as "No lane closure permitted; no work permitted ..." shown on Charts 1 provided temporary traffic screens are installed on top of temporary railings (Type K), as shown on the plans, except on the right side of traffic within the limits of a right horizontal curve where radius is less than 610 meters as viewed in the direction of travel and on the left side of traffic within the limits of a left horizontal curve where radius is less than 610 meters as viewed in the direction of travel. Temporary traffic screens shall be furnished, installed, maintained, and removed at the Contractor's expense. Temporary traffic screen panels shall be new or used CDX Grade, or better, plywood or weather resistant strandboard mounted and anchored on temporary railing (Type K). Wale boards shall be new or used Douglas fir, rough sawn, Construction Grade, or better. Pipe screen supports shall be new or used galvanized steel pipe Schedule 40. Nuts, bolts, and washers shall be cadmium plated. Screws shall be black or cadmium plated flat head, cross slotted screws with full thread length.

When the 7<sup>th</sup> St and 8<sup>th</sup> St on-ramps to southbound Route 5 freeway are closed at the same time, the Contractor, as his expense, shall furnish and install special signs for entrance ramp closures (sign SP-4) as directed by the Engineer.

Special advance notice publicity signs (sign SP-1), as shown on the plans shall be posted as directed by the Engineer, a minimum of 7 days prior to the actual ramp or connector closure. When work is not actively in progress, the SP-1 sign shall be removed or covered.

Full compensation for furnishing, erecting, maintaining, and removing special advance notice publicity signs (SP-1), special portable freeway detour signs (SP-2) and special signs for exit ramp closures (SP-3 or SP-5), as shown on the plans or in these special provisions shall be considered as included in the contract lump sum price paid for traffic control system and no additional payment will be made therefor.

All aforementioned special signs shall become the property of the Contractor at the conclusion of this project and shall be removed from the worksite.

No work that encroaches onto the traveled ways shall be allowed from 3 hours before to 2 hours following special events, or games listed below, unless otherwise permitted by the Engineer.

Venue/Special Event	Affected Routes	Route Limits
Los Angeles Marathon	10	Routes 5/10/60/101 to Route 405
	101	Routes 5/10/60/101 to Barham Blvd
Los Angeles Coliseum	10	Crenshaw Blvd to Routes 5/10/60/101
Staple Center/ LA Convention Center	10	Crenshaw Blvd to Routes 5/10/60/101 Interchange
Cinco De Mayo or any parades or festivals in Downtown LA	5	Routes 5/10/60/101 to Broadway
	10	Routes 5/10/60/101 to Crenshaw Blvd

No work on city streets that interferes with traffic shall be performed between 5:00 a.m. and 8:00 p.m.

Designated legal holidays are: January 1st, the third Monday in February, the last Monday in May, July 4th, the first Monday in September, November 11th, Thanksgiving Day, and December 25th. When a designated legal holiday falls on a Sunday, the following Monday shall be a designated legal holiday. When November 11th falls on a Saturday, the preceding Friday shall be a designated legal holiday.

Minor deviations from the requirements of this section concerning hours of work which do not significantly change the cost of the work may be permitted upon the written request of the Contractor, if in the opinion of the Engineer, public traffic

will be better served and the work expedited. These deviations shall not be adopted by the Contractor until the Engineer has approved the deviations in writing. All other modifications will be made by contract change order.

Special Days are Martin Luther King Day, Lincoln's Birthday, Cesar Chavez Day, and Columbus Day.

## Table Z

<b>Lane Closure Restrictions for Designated Legal Holidays and Special Days</b>											
Each row represents an individual legal holiday or special day situation	<b>Thu</b>	<b>Fri</b>	<b>Sat</b>	<b>Sun</b>	<b>Mon</b>	<b>Tues</b>	<b>Wed</b>	<b>Thr</b>	<b>Fri</b>	<b>Sat</b>	<b>Sun</b>
	x	<b>H</b> xx	xx	xx							
		<b>SD</b> xx									
	x	xx	<b>H</b> xx	xx							
			<b>SD</b> xx								
		x	xx	<b>H</b> xx	xx						
				<b>SD</b> xx							
		x	xx	xx	<b>H</b> <b>SD</b> xx						
		x	xx			<b>H</b> xx					
						<b>SD</b> xx					
						x	<b>H</b> xx				
							<b>SD</b> xx				
							x	<b>H</b> xx	xx		xx
								<b>SD</b> xx			

**H** = Designated Legal Holiday

**SD** = Special Day

	Refer to lane closure charts
X	The full width of the traveled way shall be open for use by public traffic after 5:00 a.m.
Xx	The full width of the traveled way shall be open for use by public traffic.

At locations where pedestrian openings through falsework are designated, falsework lighting shall be installed in conformance with the provisions in Section 86-6.11, "Falsework Lighting," of the Standard Specifications.

Openings shall be provided through bridge falsework for the use of public traffic at each location where falsework is constructed over the streets or routes listed in the following table. The type, minimum width, height, and number of openings at each location, and the location and maximum spacing of falsework lighting, if required for each opening, shall conform to the requirements in the table. The width of vehicular openings shall be the clear width between temporary railings or other protective work.

Euclid Avenue Undercrossing  
Br. No. 53-0601

	Number	Width	Height
Vehicle Openings	1	9.75	4.6
Pedestrian Openings	2	1.8	3.0

Soto Street Undercrossing  
Br. No. 53-1390R

	Number	Width	Height
Vehicle Openings	2	9.75	4.6
Pedestrian Openings	2	1.8	3.0

Marietta Street Undercrossing  
Br. No. 53-1392L

	Number	Width	Height
Vehicle Openings	1	9.75	4.6
Pedestrian Openings	2	3.0/1.8	3.0

The exact location of openings will be determined by the Engineer.

<b>Chart No. 1</b>																								
<b>Lane Requirements and Hours of Work</b>																								
Location: Southbound Route 5; from 7 <sup>th</sup> St on-ramp to 8 <sup>th</sup> St on-ramp																								
FROM HOUR TO HOUR	a.m.												p.m.											
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11
Mondays through Thursdays	1	1	1	1	1		X	X	X	X	X	X	X	X	X	X	X	X	X	X				1
Fridays	1	1	1	1	1		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X			
Saturdays	1	1	1	1	1	1		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
Sundays	1	1	1	1	1	1	1			X	X	X	X	X	X	X	X	X	X	X	X			1

Legend:

1	Provide at least one through freeway lane open in direction of travel
	No lane closure permitted; work permitted anywhere that does not require freeway lane closure
X	No lane closure permitted; no work permitted on southbound roadway

REMARKS: Number of Through Traffic Lanes – 2

<b>Chart No. 2</b>																								
<b>Connector Lane Requirements and Hours of Work</b>																								
Location: N/B Route 5 to N/B Route 5; from Euclid Ave UC to 7 <sup>th</sup> St. off-ramp																								
FROM HOUR TO HOUR	a.m.												p.m.											
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11
Mondays through Thursdays	C	C	C	C	1																			1
Fridays	C	C	C	C	1																			
Saturdays	C	C	C	C	C	1	1																	
Sundays	1	C	C	C	C	C	1	1																1

Legend:

1	Provide at least one connector lane open in the direction of travel
C	Connector may be closed
	Work permitted that does not require connector lane closure

REMARKS: When the connector is closed, detour traffic to continue northbound on Route 101 fwy; exit at the 4<sup>th</sup> St off-ramp; east on 4th St to the on-ramp to northbound Route 5 fwy. Place a portable changeable message sign inside the closure between the first and second advisor arrowboards with the message: "NORTH 5 / EXIT / CLOSED – DETOUR / N 101 / TO 4TH ST". Keep the N/B 5 to W/B 10 connector open by providing a slip on-ramp to W/B 10 connector.

A minimum of 4 special freeway detour signs shall be posted along the detour route as directed by the Engineer.

**Chart No. 3  
Connector Closure Hours**

Location: Northbound Route 5 to Northbound Route 101

FROM HOUR TO HOUR	a.m.												p.m.											
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11
Mondays through Thursdays	C	C	C	C	C																			C
Fridays	C	C	C	C	C																			
Saturdays	C	C	C	C	C	C	C																	
Sundays	C	C	C	C	C	C	C	C																C

**Legend:**

C	Connector may be closed
	Work permitted that does not require connector lane closure

**REMARKS:**

Detour traffic to westbound Route 10 fwy to northbound Route 110 fwy to northbound Route 101. Place a portable changeable message sign on the right shoulder of northbound Route 5 freeway in advance of the connector by Call Box #156 with the message: "N 101 / EXIT / CLOSED – DETOUR / WEST 10 / TO N 110".

<b>Chart No. 4</b>																									
<b>Connector Closure Hours</b>																									
Location: Northbound Route 5 to Westbound Route 10																									
FROM HOUR TO HOUR	a.m.											p.m.													
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	C	C	C	C	C																				C
Fridays	C	C	C	C	C																				C
Saturdays	C	C	C	C	C	C	C																		C
Sundays	C	C	C	C	C	C	C	C																	C
<b>Legend:</b>																									
C	Connector may be closed																								
	Work permitted that does not require connector lane closure																								
<b>REMARKS:</b>																									
Detour traffic onto northbound Route 5 freeway and exit at 4 <sup>th</sup> St. off-ramp; west on 4 <sup>th</sup> St. to the on-ramp to southbound Route 5 freeway. Place a portable changeable message sign on the right shoulder of northbound Route 5 freeway in advance of the connector by Call Box #156 with the message; "WEST 10 / EXIT / CLOSED – DETOUR / N 5 TO / 4TH ST".																									
A minimum of 2 special freeway detour signs shall be posted along the detour route as directed by the Engineer.																									

<b>Chart No. 5</b>																									
<b>Connector Closure Hours</b>																									
Location: Southbound Route 101 to Southbound Route 5																									
FROM HOUR TO HOUR	a.m.											p.m.													
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	C	C	C	C	C																				
Fridays	C	C	C	C	C																				
Saturdays	C	C	C	C	C	C																			
Sundays	C	C	C	C	C	C	C	C																	
<b>Legend:</b>																									
C	Connector may be closed																								
	Work permitted that does not require connector lane closure																								
<b>REMARKS:</b>																									
Detour traffic onto eastbound Route 60 freeway to southbound Route 710 freeway to southbound Route 5 freeway. Place a portable changeable message sign on the right shoulder of southbound Route 101 freeway in advance of the connector by Call Box #5R with the message; "SOUTH 5 / EXIT / CLOSED – DETOUR / EAST 60 / TO S 710".																									

<b>Chart No. 6</b>																											
<b>Connector Closure Hours</b>																											
Location: Westbound Route 60 to Northbound Route 5																											
FROM HOUR TO HOUR	a.m.												p.m.														
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12		
Mondays through Thursdays	C	C	C	C	C																			C	C	C	
Fridays	C	C	C	C	C																				C	C	
Saturdays	C	C	C	C	C	C	C	C																	C	C	
Sundays	C	C	C	C	C	C	C	C	C																C	C	C
<b>Legend:</b>																											
C	Connector may be closed																										
	Work permitted that does not require connector lane closure																										
<b>REMARKS:</b>																											
Detour traffic to exit at Soto St. off-ramp; north on Soto St.; west on 7 <sup>th</sup> St. to the on-ramp to northbound Route 5 freeway. Place a portable changeable message sign on the right shoulder of westbound Route 60 freeway in advance of the connector by Call Box #15 with the message "NORTH 5 / EXIT / CLOSED – DETOUR / USE / SOTO ST".																											
A minimum of 3 special freeway detour signs shall be posted along the detour route as directed by the Engineer.																											

<b>Chart No. 7</b>																												
<b>Ramp Closure Hours</b>																												
Location: Northbound Route 5 freeway; 7 <sup>th</sup> St. on-ramp.																												
FROM HOUR TO HOUR	a.m.												p.m.															
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12			
Mondays through Thursdays	C	C	C	C	C	C																		C	C	C	C	
Fridays	C	C	C	C	C	C																			C	C	C	
Saturdays	C	C	C	C	C	C	C	C	C																C	C	C	
Sundays	C	C	C	C	C	C	C	C	C	C															C	C	C	C
<b>Legend:</b>																												
C	Ramp may be closed																											
	Work permitted anywhere that does not require ramp lane closure																											
<b>REMARKS:</b>																												
When the ramp is closed, public traffic shall be detoured to the next available on-ramp downstream of the closed ramp. A minimum of 6 special freeway detour signs shall be posted along the detour route as directed by the Engineer.																												

<b>Chart No. 8 Ramp Closure Hours</b>																									
Location: Southbound Route 101 freeway, Euclid Ave. off-ramp																									
FROM HOUR TO HOUR	a.m.												p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	C	C	C	C	C	C						C	C	C	C	C					C	C	C	C	C
Fridays	C	C	C	C	C	C						C	C	C	C	C					C	C	C	C	C
Saturdays	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Sundays	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C

Legend:

C	Ramp may be closed
	Work permitted anywhere that does not require ramp lane closure

REMARKS:  
The full width of the traveled way shall be open for use by public traffic when construction operations are not actively in progress.

<b>Chart No. 9 Ramp Closure Hours</b>																									
Location: Southbound Route 5 freeway; 7 <sup>th</sup> St and 8 <sup>th</sup> St. on-ramps																									
FROM HOUR TO HOUR	a.m.												p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	C	C	C	C	C	C						C	C	C	C	C					C	C	C	C	C
Fridays	C	C	C	C	C	C						C	C	C	C	C					C	C	C	C	C
Saturdays	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Sundays	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C

Legend:

C	Ramp may be closed
	Work permitted anywhere that does not require ramp lane closure

REMARKS: When the ramp is closed, public traffic shall be detoured to the next available on-ramp downstream of the closed ramp. A minimum of 6 special freeway detour signs shall be posted along the detour route as directed by the Engineer.  
The full width of the traveled way shall be open for use by public traffic when construction operations are not actively in progress.

Pedestrian access facilities shall be provided through construction areas within the right of way as shown on the plans and as specified herein. Pedestrian walkways shall be surfaced with asphalt concrete, portland cement concrete or timber. The surface shall be skid resistant and free of irregularities. Hand railings shall be provided on each side of pedestrian walkways as necessary to protect pedestrian traffic from hazards due to construction operations or adjacent vehicular traffic. Protective overhead covering shall be provided as necessary to insure protection from falling objects and drip from overhead structures.

In addition to the required openings through falsework, pedestrian facilities shall be provided during pile driving, footing, wall, and other bridge construction operations. At least one walkway shall be available at all times. If the Contractor's operations require the closure of one walkway, then another walkway shall be provided nearby, off the traveled roadway.

Railings shall be constructed of wood, S4S, and shall be painted white. Railings and walkways shall be maintained in good condition. Walkways shall be kept clear of obstructions.

Full compensation for providing pedestrian facilities shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

#### **10-1.15 CLOSURE REQUIREMENTS AND CONDITIONS**

Lane closures shall conform to the provisions in "Maintaining Traffic" of these special provisions and these special provisions.

The term closure, as used herein, is defined as the closure of a traffic lane or lanes, including ramp or connector lanes, within a single traffic control system.

#### **CLOSURE SCHEDULE**

By noon Monday, the Contractor shall submit a written schedule of planned closures for the following week period, defined as Friday noon through the following Friday noon.

The Closure Schedule shall show the locations and times when the proposed closures are to be in effect. The Contractor shall use the Closure Schedule request forms furnished by the Engineer. Closure Schedules submitted to the Engineer with incomplete, unintelligible or inaccurate information will be returned for correction and resubmittal. The Contractor will be notified of disapproved closures or closures that require coordination with other parties as a condition of approval.

Amendments to the Closure Schedule, including adding additional closures, shall be submitted to the Engineer, in writing, at least 3 working days in advance of a planned closure. Approval of amendments to the Closure Schedule will be at the discretion of the Engineer.

The Contractor shall confirm, in writing, all scheduled closures by no later than 8:00 a.m. 3 working days prior to the date on which the closure is to be made. Approval or denial of scheduled closures will be made no later than 4:00 p.m. 2 working days prior to the date on which the closure is to be made. Closures not confirmed or approved will not be allowed.

Confirmed closures that are cancelled due to unsuitable weather may be rescheduled at the discretion of the Engineer for the following working day.

#### **CONTINGENCY PLAN**

The Contractor shall prepare a contingency plan for reopening closures to public traffic. The Contractor shall submit the contingency plan for a given operation to the Engineer within one working day of the Engineer's request.

#### **LATE REOPENING OF CLOSURES**

If a closure is not reopened to public traffic by the specified time, work shall be suspended in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. The Contractor shall not make any further closures until the Engineer has accepted a work plan, submitted by the Contractor, that will insure that future closures will be reopened to public traffic at the specified time. The Engineer will have 2 working days to accept or reject the Contractor's proposed work plan. The Contractor will not be entitled to any compensation for the suspension of work resulting from the late reopening of closures.

For each 10-minute interval, or fraction thereof past the time specified to reopen the closure, the Department will deduct \$2,500 per interval from moneys due or that may become due the Contractor under the contract.

#### **COMPENSATION**

The Contractor shall notify the Engineer of any delay in the Contractor's operations due to the following conditions, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of those conditions, and the Contractor's loss due to that delay could not have been avoided by rescheduling the affected closure or by judicious handling of forces, equipment and plant, the delay will be considered a right of way delay within the meaning of Section 8-1.09, "Right of Way Delays," and compensation for the delay will be determined in conformance with the provisions in Section 8-1.09:

- A. The Contractor's proposed Closure Schedule is denied and his planned closures are within the time frame allowed for closures in "Maintaining Traffic" of these special provisions, except that the Contractor will not be entitled to any compensation for amendments to the Closure Schedule that are not approved.
- B. The Contractor is denied a confirmed closure.

Should the Engineer direct the Contractor to remove a closure prior to the time designated in the approved Closure Schedule, any delay to the Contractor's schedule due to removal of the closure will be considered a right of way delay within the meaning of Section 8-1.09, "Right of Way Delays," and compensation for the delay will be determined in conformance with the provisions in Section 8-1.09.

### **10-1.16 TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE**

A traffic control system shall consist of closing traffic lanes and ramps in conformance with the details shown on the plans, the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications, the provisions under "Maintaining Traffic" and "Construction Area Signs" of these special provisions, and these special provisions.

The provisions in this section will not relieve the Contractor of responsibility for providing additional devices or taking measures as may be necessary to comply with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications.

When performing traffic control where the median shoulder is less than 2.4 meters, the Contractor shall conform to the requirements under the moving type lane closure for truck mounted attenuator (TMA).

During traffic stripe operations and pavement marker placement operations using bituminous adhesive, traffic shall be controlled, at the option of the Contractor, with either stationary or moving lane closures. During other operations, traffic shall be controlled with stationary lane closures. Attention is directed to the provisions in Section 84-1.04, "Protection From Damage," and Section 85-1.06, "Placement," of the Standard Specifications.

If components in the traffic control system are displaced or cease to operate or function as specified, from any cause, during the progress of the work, the Contractor shall immediately repair the components to the original condition or replace the components and shall restore the components to the original location.

#### **STATIONARY LANE CLOSURE**

When lane and ramp closures are made for work periods only, at the end of each work period, components of the traffic control system, except portable delineators placed along open trenches or excavation adjacent to the traveled way, shall be removed from the traveled way and shoulder. If the Contractor so elects, the components may be stored at selected central locations, designated by the Engineer within the limits of the highway right of way.

Each vehicle used to place, maintain and remove components of a traffic control system on multilane highways shall be equipped with a Type II flashing arrow sign which shall be in operation when the vehicle is being used for placing, maintaining or removing the components. Vehicles equipped with Type II flashing arrow sign not involved in placing, maintaining or removing the components when operated within a stationary type lane closure shall only display the caution display mode. The sign shall be controllable by the operator of the vehicle while the vehicle is in motion. The flashing arrow sign shown on the plans shall not be used on the vehicles which are doing the placing, maintaining and removing of components of a traffic control system and shall be in place before a lane closure requiring the sign's use is completed.

The 150-m section of a lane closure, shown along lane lines between the 300-m lane closure tapers on the plans entitled "Traffic Control System for Lane Closures on Freeways and Expressways" and "Traffic Control System for Lane and Complete Closures on Freeways and Expressways" shall not be used.

#### **MOVING LANE CLOSURE**

Flashing arrow signs used in moving lane closures shall be truck-mounted. Changeable message signs used in moving lane closure operations shall conform to the provisions in Section 12-3.12, "Portable Changeable Message Signs," of the Standard Specifications, except the signs shall be truck-mounted and the full operation height of the bottom of the sign may be less than 2.1 m above the ground, but should be as high as practicable.

Flashing arrow signs shall be in the caution display mode when used on 2-lane, 2-way highways.

Truck-mounted attenuators (TMA) for use in moving lane closures shall be any of the following approved models, or equal:

- A. Hexfoam TMA Series 3000, Alpha 1000 TMA Series 1000 and Alpha 2001 TMA Series 2001, manufactured by Energy Absorption Systems, Inc., One East Wacker Drive, Chicago, IL 60601-2076, Telephone (312) 467-6750.
  1. Distributor (Northern): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, Telephone 1-800-884-8274, FAX (916) 387-9734.
  2. Distributor (Southern): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805, Telephone 1-800-222-8274.
- B. Cal T-001 Model 2 or Model 3, manufacturer and distributor: Hexcel Corporation, 11711 Dublin Boulevard, P.O. Box 2312, Dublin, CA 94568, Telephone (510) 828-4200.
- C. Renco Rengard Model Nos. CAM 8-815 and RAM 8-815, manufacturer and distributor: Renco Inc., 1582 Pflugerville Loop Road, P.O. Box 730, Pflugerville, TX 78660-0730, Telephone 1-800-654-8182.

Each TMA shall be individually identified with the manufacturer's name, address, TMA model number, and a specific serial number. The names and numbers shall each be a minimum 13 mm high and located on the left (street) side at the lower front corner. The TMA shall have a message next to the name and model number in 13 mm high letters which states, "The bottom of this TMA shall be \_\_\_\_\_ mm ± \_\_\_\_\_ mm above the ground at all points for proper impact performance." Any TMA which is damaged or appears to be in poor condition shall not be used unless recertified by the manufacturer. The Engineer shall be the sole judge as to whether used TMAs supplied under this contract need recertification. Each unit shall be certified by the manufacturer to meet the requirements for TMA in conformance with the standards established by the Transportation Laboratory.

Approvals for new TMA designs proposed as equal to the above approved models shall be in conformance with the procedures (including crash testing) established by the Transportation Laboratory. For information regarding submittal of new designs for evaluation contact: Transportation Laboratory, 5900 Folsom Boulevard, Sacramento, California 95819.

New TMAs proposed as equal to approved TMAs or approved TMAs determined by the Engineer to need recertification shall not be used until approved or recertified by the Transportation Laboratory.

## **PAYMENT**

The contract lump sum price paid for traffic control system shall include full compensation for furnishing all labor, materials (including signs), tools, equipment, and incidentals, and for doing all the work involved in placing, removing, storing, maintaining, moving to new locations, replacing and disposing of the components of the traffic control system shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The adjustment provisions in Section 4-1.03, "Changes," of the Standard Specifications shall not apply to the item of traffic control system. Adjustments in compensation for traffic control system will be made only for increased or decreased traffic control system required by changes ordered by the Engineer and will be made on the basis of the cost of the increased or decreased traffic control necessary. The adjustment will be made on a force account basis as provided in Section 9-1.03, "Force Account Payment," of the Standard Specifications for increased work and estimated on the same basis in the case of decreased work.

Traffic control system required by work which is classed as extra work, as provided in Section 4-1.03D of the Standard Specifications, will be paid for as a part of the extra work.

## **10-1.17 TEMPORARY PAVEMENT DELINEATION**

Temporary pavement delineation shall be furnished, placed, maintained, and removed in conformance with the provisions in Section 12-3.01, "General," of the Standard Specifications and these special provisions. Nothing in these special provisions shall be construed as reducing the minimum standards specified in the Manual of Traffic Controls published by the Department or as relieving the Contractor from the responsibilities specified in Section 7-1.09, "Public Safety," of the Standard Specifications.

## **GENERAL**

Whenever the work causes obliteration of pavement delineation, temporary or permanent pavement delineation shall be in place prior to opening the traveled way to public traffic. Laneline or centerline pavement delineation shall be provided at all times for traveled ways open to public traffic. On multilane roadways (freeways and expressways) edgeline delineation shall be provided at all times for traveled ways open to public traffic.

The Contractor shall perform the work necessary to establish the alignment of temporary pavement delineation, including required lines or marks. Surfaces to receive temporary pavement delineation shall be dry and free of dirt and loose material. Temporary pavement delineation shall not be applied over existing pavement delineation or other temporary pavement delineation. Temporary pavement delineation shall be maintained until superseded or replaced with a new pattern of temporary pavement delineation or permanent pavement delineation.

Temporary pavement markers, including underlying adhesive, and removable traffic tape which are applied to the final layer of surfacing or existing pavement to remain in place or which conflicts with a subsequent or new traffic pattern for the area shall be removed when no longer required for the direction of public traffic, as determined by the Engineer.

## **TEMPORARY LANELINE DELINEATION**

Whenever lanelines are obliterated and temporary pavement delineation to replace the lines is not shown on the plans, the minimum laneline delineation to be provided for that area shall be temporary pavement markers placed at longitudinal intervals of not more than 7.3 m. The temporary pavement markers shall be the same color as the laneline the pavement markers replace. Temporary pavement markers shall be, at the option of the Contractor, one of the temporary pavement markers listed for short term day/night use (14 days or less) or long term day/night use (6 months or less) in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. The temporary pavement markers shall be placed

in conformance with the manufacturer's instructions. Temporary pavement markers for long term day/night use (6 months or less) shall be cemented to the surfacing with the adhesive recommended by the manufacturer, except epoxy adhesive shall not be used to place the temporary pavement markers in areas where removal of the temporary pavement markers will be required.

Temporary laneline delineation consisting entirely of temporary pavement markers listed for short term day/night use (14 days or less), shall be placed on longitudinal intervals of not more than 7.3 m and shall be used for a maximum of 14 days on lanes opened to public traffic. Prior to the end of the 14 days the permanent pavement delineation shall be placed. If the permanent pavement delineation is not placed within the 14 days, the Contractor shall replace the temporary pavement markers and provide additional temporary pavement delineation and shall bear the cost thereof. The additional temporary pavement delineation to be provided shall be equivalent to the pattern specified for the permanent pavement delineation for the area, as determined by the Engineer.

Full compensation for furnishing, placing, maintaining, and removing the temporary pavement markers (including underlying adhesive, layout (dribble) lines to establish alignment of temporary pavement markers or used for temporary laneline delineation) for those areas where temporary laneline delineation is not shown on the plans and for providing equivalent patterns of permanent traffic lines for those areas when required, shall be considered as included in the contract prices paid for the items of work that obliterated the laneline pavement delineation and no separate payment will be made therefor.

### **TEMPORARY EDGELINE DELINEATION**

On multilane roadways (freeways and expressways), whenever edgelines are obliterated and temporary pavement delineation to replace those edgelines is not shown on the plans, the edgeline delineation to be provided for those areas adjacent to lanes open to public traffic shall be as follows:

- A. Temporary pavement delineation for right edgelines shall, at the option of the Contractor, consist of either a solid 100-mm wide traffic stripe of the same color as the stripe the temporary edgeline delineation replaces, or traffic cones, portable delineators or channelizers placed at longitudinal intervals not to exceed 30 m.
- B. Temporary pavement delineation for left edgelines shall, at the option of the Contractor, consist of either solid 100-mm wide traffic stripe of the same color as the stripe the temporary edgeline delineation replaces, traffic cones, portable delineators or channelizers placed at longitudinal intervals not to exceed 30 m or temporary pavement markers placed at longitudinal intervals of not more than 1.8 m. Temporary pavement markers used for temporary left edgeline delineation shall be one of the types of temporary pavement markers listed for short term day/night use (14 days or less) or long term day/night use (6 months or less) in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Traffic stripe (100-mm wide) placed as temporary edgeline delineation which will require removal shall conform to the provisions of "Temporary Traffic Stripe (Tape)" of these special provisions. The quantity of temporary traffic stripe (tape) or temporary traffic stripe (paint) used for this temporary edgeline delineation will not be included in the quantities of tape or paint to be paid for.

The lateral offset for traffic cones, portable delineators or channelizers used for temporary edgeline delineation shall be as determined by the Engineer. If traffic cones or portable delineators are used as temporary pavement delineation for edgelines, the Contractor shall provide personnel to remain at the project site to maintain the cones or delineators during the hours of the day that the portable delineators are in use.

Channelizers used for temporary edgeline delineation shall be the surface mounted type and shall be orange in color. Channelizer bases shall be cemented to the pavement in the same manner provided for cementing pavement markers to pavement in "Pavement Markers" of these special provisions, except epoxy adhesive shall not be used to place channelizers on the top layer of pavement. Channelizers shall be, at the Contractor's option, one of the surface mount types (900 mm) listed in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Temporary edgeline delineation shall be removed when no longer required for the direction of public traffic as determined by the Engineer.

Full compensation for furnishing, placing, maintaining, and removing temporary edgeline delineation, including underlying adhesive, for those areas where temporary edgeline delineation is not shown on the plans shall be considered as included in the contract prices paid for the items of work that obliterated the edgeline pavement delineation and no separate payment will be made therefor.

### **TEMPORARY TRAFFIC STRIPE (TAPE)**

Temporary traffic stripe consisting of removable traffic stripe tape shall be applied at the locations shown on the plans. The temporary traffic stripe tape shall be complete in place at the location shown prior to opening the traveled way to public traffic.

Removable traffic stripe tape shall be the temporary removable traffic stripe tape listed in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Removable traffic stripe tape shall be applied in conformance with the manufacturer's installation instructions and shall be rolled slowly with a rubber tired vehicle or roller to ensure complete contact with the pavement surface. Traffic stripe tape shall be applied straight on tangent alignment and on a true arc on curved alignment. Traffic stripe tape shall not be applied when the air or pavement temperature is less than 10°C, unless the installation procedures to be used are approved by the Engineer, prior to beginning installation of the tape.

When removable traffic stripe tape is specified for temporary left edgeline delineation, temporary pavement markers placed at longitudinal intervals of not more than 1.8 m may be used in place of the temporary traffic stripe tape. Temporary pavement markers shall be one of the types of temporary pavement markers listed for long term day/night use (6 months or less) in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. When temporary pavement markers are used in place of tape, payment for those temporary pavement markers will be made on the basis of the theoretical length of the temporary traffic stripe (tape) required for the left edgeline which the temporary pavement markers replace.

### **TEMPORARY PAVEMENT MARKERS**

Temporary pavement markers shall be applied at the locations shown on the plans. The pavement markers shall be applied complete in place at the locations shown prior to opening the traveled way to public traffic.

Temporary pavement markers shown on the plans shall be, at the option of the Contractor, one of the temporary pavement markers for long term day/night use (6 months or less) listed in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Temporary pavement markers shall be placed in conformance with the manufacturer's instructions and shall be cemented to the surfacing with the adhesive recommended by the manufacturer, except epoxy adhesive shall not be used in areas where removal of the pavement markers will be required.

Where the temporary pavement delineation shown on the plans for lanelines or centerlines consists entirely of a pattern of broken traffic stripe and pavement markers, the Contractor may use groups of the temporary pavement markers for long term day/night use (6 months or less) in place of the temporary traffic stripe tape or painted temporary traffic stripe. The groups of pavement markers shall be spaced as shown on the plans for a similar pattern of permanent traffic line, except pavement markers shown to be placed in the gap between the broken traffic stripe shall be placed as part of the group to delineate the pattern of broken temporary traffic stripe. The kind of laneline and centerline delineation selected by the Contractor shall be continuous within a given location. Payment for those temporary pavement markers used in place of temporary traffic stripe will be made on the basis of the theoretical length of the patterns of temporary traffic stripe (tape) or temporary traffic stripe (paint).

Retroreflective pavement markers conforming to the provisions in "Pavement Markers" of these special provisions may be used in place of temporary pavement markers for long term day/night use (6 months or less) except to simulate patterns of broken traffic stripe. Placement of the retroreflective pavement markers used for temporary pavement markers shall conform to the provisions in "Pavement Markers" of these special provisions except the waiting period provisions before placing the pavement markers on new asphalt concrete surfacing as specified in Section 85-1.06, "Placement," of the Standard Specifications shall not apply and epoxy adhesive shall not be used to place pavement markers in areas where removal of the pavement markers will be required.

### **MEASUREMENT AND PAYMENT**

Temporary traffic stripe (tape) will be measured and paid for by the meter, measured along the line of the stripe, with deductions for gaps in broken traffic stripes. Double and 200-mm temporary traffic stripes, shown on the plans as tape, will be measured as 2 temporary traffic stripes (tape).

Temporary pavement markers, shown on the plans, will be measured and paid for by the unit in the same manner specified for retroreflective pavement markers in Section 85-1.08, "Measurement," and Section 85-1.09, "Payment," of the Standard Specifications. Temporary pavement markers used for temporary laneline and centerline delineation for areas which are not shown on the plans will not be included in the quantities of temporary pavement markers to be paid for. Full compensation for removing temporary pavement markers, when no longer required, shall be considered as included in the contract unit price paid for temporary pavement marker and no separate payment will be made therefor.

The contract price paid per meter for temporary traffic stripe (tape) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in applying, maintaining and

removing temporary traffic stripe tape, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

#### **10-1.18 BARRICADE**

Barricades shall be furnished, placed and maintained at the locations shown on the plans, specified in the Standard Specifications or in these special provisions or where designated by the Engineer. Barricades shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to "Prequalified and Tested Signing and Delineation Materials" of these special provisions regarding retroreflective sheeting for barricades.

Construction area sign and marker panels conforming to the provisions in Section 12-3.06, "Construction Area Signs," of the Standard Specifications shall be installed on barricades in a manner determined by the Engineer at the locations shown on the plans.

Sign panels for construction area signs and marker panels installed on barricades shall conform to the provisions in Section 12-3.06A, "Stationary Mounted Signs," of the Standard Specifications.

Full compensation for furnishing, installing, maintaining, and removing construction area signs and marker panels on barricades shall be considered as included in the contract unit price paid for the type of barricade involved and no separate payment will be made therefor.

Barricades shown on the plans as part of a traffic control system will be paid for as provided in "Traffic Control System for Lane Closure" of these special provisions and will not be included in the count for payment of barricades.

#### **10-1.19 PORTABLE CHANGEABLE MESSAGE SIGN**

Portable changeable message signs shall be furnished, placed, operated, and maintained at those locations provided for in these special provisions or where designated by the Engineer in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to Charts 2 through 6 in "Maintaining Traffic" of these special provisions regarding the use and locations of the portable changeable message signs.

The message displayed on the portable changeable message sign, as specified in these special provisions or as directed by the Engineer shall not be displayed until 5 minutes prior to the actual closure installation as permitted by these special provisions. Portable changeable message sign shall have either a 24 hour timer control or remote control capability.

The Contractor shall provide a representative on the job site with a cellular phone who is capable of modifying the message as directed by the Engineer for each work shift which requires a portable changeable message sign.

Full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing, placing, operating, maintaining, repairing, replacing, transporting from location to location, modifying the message, and removing portable changeable message signs as specified in these special provisions as shown on the plan shall be considered as included in the contract lump sum price paid for traffic control system and no separate payment will be made therefor.

#### **10-1.20 TEMPORARY RAILING**

Temporary railing (Type K) shall be placed as shown on the plans, as specified in the Standard Specifications or these special provisions or where ordered by the Engineer and shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Temporary railing (Type K) shall be anchored as shown on the plans. Full compensation for anchoring temporary railing (Type K) shall be considered as included in the contract price paid per meter for temporary railing (Type K) and no additional compensation will be allowed therefor.

Reflectors on temporary railing (Type K) shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Temporary railing (Type K), conforming to the details shown on Standard Plan T3 may be used. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance and vertical holes are not drilled in the top of the temporary railing to secure temporary traffic screen to the temporary railing.

Attention is directed to "Public Safety" and "Order of Work" of these special provisions.

Temporary railing (Type K) placed in conformance with the provisions in "Public Safety" of these special provisions will be neither measured nor paid for.

Temporary railing (Type K) and temporary crash cushions placed nearby the new concrete barrier shall not be removed until that section of concrete barrier reaches its full design strength.

### **10-1.21 CHANNELIZER**

Channelizers shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Channelizers shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

When no longer required for the work as determined by the Engineer, channelizers and underlying adhesive used to cement the channelizer bases to the pavement shall be removed. Removed channelizers and adhesive shall become the property of the Contractor and shall be removed from the site of work.

### **10-1.22 TEMPORARY CRASH CUSHION MODULE**

This work shall consist of furnishing, installing, and maintaining sand filled temporary crash cushion modules in groupings or arrays at each location shown on the plans, as specified in these special provisions or where designated by the Engineer. The grouping or array of sand filled modules shall form a complete sand filled temporary crash cushion in conformance with the details shown on the plans and these special provisions.

Attention is directed to "Public Safety", "Order of Work", and "Temporary Railing" of these special provisions.

Whenever the work or the Contractor's operations establishes a fixed obstacle, the exposed fixed obstacle shall be protected with a sand filled temporary crash cushion. The sand filled temporary crash cushion shall be in place prior to opening the lanes adjacent to the fixed obstacle to public traffic.

Sand filled temporary crash cushions shall be maintained in place at each location, including times when work is not actively in progress. Sand filled temporary crash cushions may be removed during a work period for access to the work provided that the exposed fixed obstacle is 4.6 m or more from a lane carrying public traffic and the temporary crash cushion is reset to protect the obstacle prior to the end of the work period in which the fixed obstacle was exposed. When no longer required, as determined by the Engineer, sand filled temporary crash cushions shall be removed from the site of the work.

At the Contractor's option, the modules for use in sand filled temporary crash cushions shall be either Energite III Inertial Modules, Fitch Inertial Modules or Traffix Sand Barrels manufactured after March 31, 1997, or equal:

A. Energite III and Fitch Inertial Modules, manufactured by Energy Absorption Systems, Inc., One East Wacker Drive, Chicago, IL 60601-2076. Telephone 1-312-467-6750, FAX 1-800-770-6755

1. Distributor (North): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828. Telephone 1-800-884-8274, FAX 1-916-387-9734
2. Distributor (South): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805. Telephone 1-800-222-8274, FAX 1-714-937-1070

B. Traffix Sand Barrels, manufactured by Traffix Devices, Inc., 220 Calle Pintoresco, San Clemente, CA 92672. Telephone 1-949 361-5663, FAX 1-949 361-9205

1. Distributor (North): United Rentals, Inc., 1533 Berger Drive, San Jose, CA 95112. Telephone 1-408 287-4303, FAX 1-408 287-1929
2. Distributor (South): Statewide Safety & Sign, Inc., P.O. Box 1440, Pismo Beach, CA 93448. Telephone 1-800-559-7080, FAX 1-805 929-5786

Modules contained in each temporary crash cushion shall be of the same type at each location. The color of the modules shall be the standard yellow color, as furnished by the vendor, with black lids. The modules shall exhibit good workmanship free from structural flaws and objectionable surface defects. The modules need not be new. Good used undamaged modules conforming to color and quality of the types specified herein may be utilized. If used Fitch modules requiring a seal are furnished, the top edge of the seal shall be securely fastened to the wall of the module by a continuous strip of heavy duty tape.

Modules shall be filled with sand in conformance with the manufacturer's directions, and to the sand capacity in kilograms for each module shown on the plans. Sand for filling the modules shall be clean washed concrete sand of commercial quality. At the time of placing in the modules, the sand shall contain not more than 7 percent water as determined by California Test 226.

Modules damaged due to the Contractor's operations shall be repaired immediately by the Contractor at the Contractor's expense. Modules damaged beyond repair, as determined by the Engineer, due to the Contractor's operations shall be removed and replaced by the Contractor at the Contractor's expense.

Temporary crash cushion modules shall be placed on movable pallets or frames conforming to the dimensions shown on the plans. The pallets or frames shall provide a full bearing base beneath the modules. The modules and supporting pallets or frames shall not be moved by sliding or skidding along the pavement or bridge deck.

A Type R or P marker panel shall be attached to the front of the crash cushion as shown on the plans, when the closest point of the crash cushion array is within 3.6 m of the traveled way. The marker panel, when required, shall be firmly fastened to the crash cushion with commercial quality hardware or by other methods determined by the Engineer.

At the completion of the project, temporary crash cushion modules, sand filling, pallets or frames, and marker panels shall become the property of the Contractor and shall be removed from the site of the work. Temporary crash cushion modules shall not be installed in the permanent work.

Temporary crash cushion modules will be measured by the unit as determined from the actual count of modules used in the work or ordered by the Engineer at each location. Temporary crash cushion modules placed in conformance with the provisions in "Public Safety" of these special provisions and modules placed in excess of the number specified or shown will not be measured nor paid for.

Repairing modules damaged by public traffic will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Modules damaged beyond repair by public traffic, when ordered by the Engineer, shall be removed and replaced immediately by the Contractor. Modules replaced due to damage by public traffic will be measured and paid for as temporary crash cushion module.

If the Engineer orders a lateral move of the sand filled temporary crash cushions and the repositioning is not shown on the plans, moving the sand filled temporary crash cushion will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications and these temporary crash cushion modules will not be counted for payment in the new position.

The contract unit price paid for temporary crash cushion module shall include full compensation for furnishing all labor, materials (including sand, pallets or frames and marker panels), tools, equipment, and incidentals, and for doing all the work involved in furnishing, installing, maintaining, moving, and resetting during a work period for access to the work, and removing from the site of the work when no longer required (including those damaged by public traffic) sand filled temporary crash cushion modules, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **10-1.23 EXISTING HIGHWAY FACILITIES**

The work performed in connection with various existing highway facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Plans of the existing bridges may be requested by fax from the Office of Structure Maintenance and Investigations, 1801 30th Street, Sacramento, CA, Fax (916) 227-8357, and are available at the Office of Structure Maintenance and Investigations, Los Angeles, CA, Telephone (213) 897-6156.

Plans of the existing bridges available to the Contractor are reproductions of the original contract plans with significant changes noted and working drawings and do not necessarily show normal construction tolerances and variances. Where dimensions of new construction required by this contract are dependent on the dimensions of the existing bridges, the Contractor shall verify the controlling field dimensions and shall be responsible for adjusting dimensions of the work to fit existing conditions.

#### **REMOVE CHAIN LINK FENCE**

Existing chain link fence, where shown on the plans to be removed, shall be removed and disposed of.

Existing concrete anchors shall be completely removed and disposed of. Full compensation for removing concrete anchors shall be considered as included in the contract price paid per meter for remove chain link fence and no separate payment will be made therefor.

#### **REMOVE METAL BEAM GUARD RAILING**

Existing metal beam guard railing, where shown on the plans to be removed, shall be removed and disposed of.

Existing concrete anchors shall be completely removed and disposed of. Full compensation for removing concrete anchors shall be considered as included in the contract price paid per meter for remove metal beam guard railing and no separate payment will be made therefor.

Full compensation for removing cable anchor assemblies, terminal anchor assemblies shall be considered as included in the contract price paid per meter for remove metal beam guard railing and no separate payment will be made therefor.

#### **REMOVE PAVEMENT MARKER**

Existing pavement markers, including underlying adhesive, when no longer required for traffic lane delineation as determined by the Engineer, shall be removed and disposed of.

### **REMOVE CONCRETE MASONRY BLOCK WALL**

Existing concrete masonry block wall, including footings, where shown on the plans, shall be removed and disposed of. Remove concrete masonry block wall will be measured and paid for by the meter along the wall line before removal.

Full compensation for backfilling and compacting holes resulting from the removal of concrete masonry block wall footing shall be considered as included in the contract price paid per meter for remove concrete masonry block wall and no additional compensation will be allowed therefor.

Concrete masonry block wall removed shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

### **REMOVE RETAINING WALL**

Existing retaining wall, including footings, where shown on the plans to be removed, shall be removed and disposed of.

Full compensation for backfilling and compacting holes resulting from the removal of retaining wall footings shall be considered as included in the contract price paid per meter for remove retaining wall and no additional compensation will be allowed therefor.

Full compensation for removing reinforcing steel encountered in the retaining wall to be removed shall be considered as included in the contract price paid per meter for remove retaining wall and no additional compensation will be allowed therefor.

### **REMOVE THERMOPLASTIC TRAFFIC STRIPE**

Thermoplastic traffic stripe shall be removed at the locations shown on the plans and as directed by the Engineer.

Attention is directed to "Water Pollution Control" of these special provisions.

Waste from removal of yellow thermoplastic traffic stripe contains lead chromate in average concentrations greater than or equal to 350 mg/kg and less than 1000 mg/kg Total Lead. Yellow thermoplastic traffic stripe exist as shown on the plans. Residue produced when yellow thermoplastic are removed may contain heavy metals in concentrations that exceed thresholds established by the California Health and Safety Code and may produce toxic fumes when heated.

The removed yellow thermoplastic shall be disposed of at a Class 1 disposal facility or a Class 2 disposal facility permitted by the Regional Water Quality Control Board in conformance with the requirements of the disposal facility operator within 60 days after accumulating 100 kg of residue and dust. The Contractor shall make necessary arrangements with the operator of the disposal facility to test the yellow thermoplastic residue as required by the facility and these special provisions. Testing shall include, at a minimum, (1) Total Lead and Chromium by EPA Method 7000 series and (2) Soluble Lead and Chromium by California Waste Extraction Test. From the first 3360 L of waste or portion thereof, if less than 3360 L of waste are produced, a minimum of four randomly selected samples shall be taken and analyzed. From each additional 840 L of waste or portion thereof, if less than 840 L are produced, a minimum of one additional random sample shall be taken and analyzed. The Contractor shall submit the name and location of the disposal facility and analytical laboratory along with the testing requirements to the Engineer not less than 15 days prior to the start of removal of yellow thermoplastic traffic stripe. The analytical laboratory shall be certified by the Department of Health Services Environmental Laboratory Accreditation Program. Test results shall be provided to the Engineer for review prior to signing a waste profile as requested by the disposal facility, prior to issuing an EPA identification number, and prior to allowing removal of the waste from the site.

The Contractor shall prepare a project specific Lead Compliance Plan to prevent or minimize worker exposure to lead while handling removed yellow thermoplastic residue. Attention is directed to Title 8, California Code of Regulations, Section 1532.1, "Lead," for specific Cal-OSHA requirements when working with lead.

The Lead Compliance Plan shall contain the elements listed in Title 8, California Code of Regulations, Section 1532.1(e)(2)(B). Before submission to the Engineer, the Lead Compliance Plan shall be approved by an Industrial Hygienist certified in Comprehensive Practice by the American Board of Industrial Hygiene. The Plan shall be submitted to the Engineer at least 7 days prior to beginning removal of yellow thermoplastic.

Prior to removing yellow thermoplastic traffic stripe, personnel who have no prior training, including State personnel, shall complete a safety training program provided by the Contractor that meets the requirements of Title 8, California Code of Regulations, Section 1532.1, "Lead," and the Contractor's Lead Compliance Program.

Personal protective equipment, training, and washing facilities required by the Contractor's Lead Compliance Plan shall be supplied to State personnel by the Contractor. The number of State personnel will be 3.

Where grinding or other methods approved by the Engineer are used to remove yellow thermoplastic traffic stripe, the removed residue, including dust, shall be contained and collected immediately. Sweeping equipment shall not be used. Collection shall be by a high efficiency particulate air (HEPA) filter equipped vacuum attachment operated concurrently with the removal operations or other equally effective methods approved by the Engineer. The Contractor shall submit a written work plan for the removal, storage, and disposal of yellow thermoplastic traffic stripe to the Engineer for approval not less

than 15 days prior to the start of the removal operations. Removal operations shall not be started until the Engineer has approved the work plan.

The removed yellow thermoplastic traffic stripe residue shall be stored and labeled in covered containers. Labels shall conform to the provisions of Title 22, California Code of Regulations, Sections 66262.31 and 66262.32. Labels shall be marked with date when the waste is generated, the words "Hazardous Waste", composition and physical state of the waste (for example, asphalt grindings with thermoplastic or paint), the word "Toxic", the name and address of the Engineer, the Engineer's telephone number, contract number, and Contractor or subcontractor. The containers shall be a type approved by the United States Department of Transportation for the transportation and temporary storage of the removed residue. The containers shall be handled so that no spillage will occur. The containers shall be stored in a secured enclosure at a location within the project limits until disposal, as approved by the Engineer.

If the yellow thermoplastic traffic stripe residue is transported to a Class 1 disposal facility, a manifest shall be used, and the transporter shall be registered with the California Department of Toxic Substance Control. The Engineer will obtain the United States Environmental Protection Agency Identification Number and sign all manifests as the generator within 2 working days of receiving sample test results and approving the test methods.

Nothing in these special provisions shall relieve the Contractor of the Contractor's responsibilities as specified in Section 7-1.09, "Public Safety," of the Standard Specifications.

Attention is directed to "Material Containing Aerially Deposited Lead" of these special provisions regarding payment for the Lead Compliance Plan.

Full compensation for providing a written work plan for the removal, storage, and disposal of yellow thermoplastic traffic stripe shall be considered as included in the contract items paid per meter for remove yellow thermoplastic traffic stripe and no separate payment will be made therefor.

#### **REMOVE DRAINAGE FACILITY**

Existing pipes and inlets where shown on the plans to be removed, shall be completely removed and disposed of.

#### **REMOVE ROADSIDE SIGN**

Existing roadside signs, at those locations shown on the plans to be removed, shall be removed and disposed of.

Sign panels shown on the plans shall be removed and reused in the work as shown on the plans.

Existing roadside signs shall not be removed until replacement signs have been installed or until the existing signs are no longer required for the direction of public traffic, unless otherwise directed by the Engineer.

Full compensation for removing and reusing sign panels shall be considered as included in the contract price paid for the item of work requiring reuse of the sign panels.

#### **RECONSTRUCT PROPERTY SIDE YARD WALLS OR FENCES**

Existing property boundary side yard walls or fences within the temporary construction easements as shown on the plans shall be removed and reconstructed. Side yard walls or fences shall be removed as necessary to perform construction work as shown on the plans.

Prior to removal of temporary fence, the Contractor shall extend and connect the side yard walls or fencing to the newly constructed sound wall by using like materials either new or existing, so that the reconstructed property boundary side yard walls or fences match the existing walls or fences in height, color, dimensions and types.

Walls or fences removed in excess of that required for reconstructing shall be disposed of.

The Contractor shall provide sufficient number of control points prior to removal, to reestablish the alignment of the property fence line. The Contractor shall record the aesthetic features of the removed side yard fences or walls so that the reconstructed fences or walls will match.

Full compensation for reconstructing and extending property (including furnishing new materials) side yard walls or fences shall be considered as included in the contract price paid per square meter for the type of sound wall involved and no separate payment will be made therefor.

#### **ADJUST MANHOLE TO GRADE**

Frames and covers of existing manholes shall be adjusted to grade in conformance with the provisions in Section 15-2.05, "Reconstruction," of the Standard Specifications.

#### **BRIDGE REMOVAL (PORTION)**

Removing bridges or portions of bridges shall conform to the provisions in Section 15-4, "Bridge Removal," of the Standard Specifications and these special provisions.

Attention is directed to "Material Containing Aerial Deposited Lead" of these special provisions for Type Z-2 material resulting from removal operations for bridge removal (portion) within the limits shown on the plans.

Bridge removal (portion) are required at the following locations:

LOCATION A  
EUCLID AVENUE UNDERCROSSING  
(BRIDGE NUMBER 53-0601)

Bridge removal (portion) shall consist of removing portion of existing reinforced concrete box girder bridge to the limits shown on the plans.

LOCATION B  
EUCLID AVENUE OFF-RAMP UNDERCROSSING  
(BRIDGE NUMBER 53-1389L)

Bridge removal (portion) shall consist of removing portion of existing reinforced concrete slab bridge and retaining walls to the limits shown on the plans.

LOCATION C  
SOTO STREET UNDERCROSSING  
(BRIDGE NUMBER 53-1390R)

Bridge removal (portion) shall consist of removing portion of existing reinforced concrete box girder bridge and retaining wall to the limits shown on the plans.

LOCATION D  
MARIETTA STREET UNDERCROSSING  
(BRIDGE NUMBER 53-1392L)

Bridge removal (portion) shall consist of removing portion of existing reinforced concrete box girder bridge to the limits shown on the plans.

Removed materials that are not to be salvaged or used in the reconstruction shall become the property of the Contractor and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The Contractor shall submit a complete bridge removal plan to the Engineer for each bridge listed above, detailing procedures, sequences, and all features required to perform the removal in a safe and controlled manner.

The bridge removal plan shall include, but not be limited to the following:

- A. The removal sequence, including staging of removal operations.
- B. Equipment locations on the structure during removal operations.
- C. Temporary support shoring or temporary bracing.
- D. Locations where work is to be performed over traffic or utilities.
- E. Details, locations, and types of protective covers to be used.
- F. Measures to assure that people, property, utilities, and improvements will not be endangered.
- G. Details and measures for preventing material, equipment, and debris from falling onto public traffic.

When protective covers are required for removal of portions of a bridge, or when superstructure removal works on bridges are involved, the Contractor shall submit working drawings, with design calculations, to the Engineer for the proposed bridge removal plan, and the bridge removal plan shall be prepared and signed by an engineer who is registered as a Civil Engineer in the State of California. The design calculations shall be adequate to demonstrate the stability of the structure during all stages of the removal operations. Calculations shall be provided for each stage of bridge removal and shall include dead and live load values assumed in the design of protective covers.

Temporary support shoring, temporary bracing, and protective covers, as required, shall be designed and constructed in conformance with the provisions in Section 51-1.06, "Falsework," of the Standard Specifications and these special provisions.

The assumed horizontal load to be resisted by the temporary support shoring and temporary bracing, for removal operations only, shall be the sum of the actual horizontal loads due to equipment, construction sequence or other causes, and

an allowance for wind, but in no case shall the assumed horizontal load to be resisted in any direction be less than 5 percent of the total dead load of the structure to be removed.

The bridge removal plan shall conform to the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The number of sets of drawings, design calculations, and unless otherwise specified in the following table, the time for reviewing bridge removal plans shall be the same as specified for falsework working drawings in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications.

The time to be provided for the Engineer's review of the bridge removal plans for removing specific structures, or portions thereof, shall be as follows:

Structure or Portion of Structure	Review Time - Weeks
Euclid Avenue Undercrossing	5
Euclid Avenue Off-Ramp Undercrossing	5

The following additional requirements apply to the removal of bridges or portions of bridges that are over or adjacent to roadways that may be closed to public traffic for only brief periods of time:

- A. The closure of roadways to public traffic shall conform to the provisions in "Maintaining Traffic" of these special provisions.
- B. Prior to closing a roadway to traffic to accommodate bridge removal operations, the Contractor shall have all necessary workers, materials, and equipment at the site as needed to proceed with the removal work in an expeditious manner. While the roadway is closed to public traffic, work shall be pursued promptly and without interruption until the roadway is reopened to public traffic.
- C. Bridge removal operations shall be performed during periods of time that the roadway is closed to public traffic except as specified herein for preliminary work.
- D. Preliminary work shall be limited to operations that will not reduce the structural strength or stability of the bridge, or any element thereof, to a level that in the judgment of the Engineer would constitute a hazard to the public. This preliminary work shall also be limited to operations that cannot cause debris or any other material to fall onto the roadway. Protective covers may be used to perform preliminary work such as chipping or cutting the superstructure into segments, provided the covers are of sufficient strength to support all loads and are sufficiently tight to prevent dust and fine material from sifting down onto the traveled way. Protective covers shall extend at least 1.2 m beyond the limit of the work underway. Bottom slabs of box girders may be considered to be protective covers for preliminary work performed on the top slab inside the limits of the exterior girders.
- E. Temporary support shoring and temporary bracing shall be used in conjunction with preliminary work when necessary to insure the stability of the bridge.
- F. Temporary support shoring, temporary bracing, and protective covers shall not encroach closer than 2.4 m horizontally from the edge or 4.6 m vertically above any traffic lane or shoulder that is open to public traffic.
- G. During periods when the roadway is closed to public traffic, debris from bridge removal operations may be allowed to fall directly onto the lower roadway provided adequate protection is furnished for all highway facilities. The minimum protection for paved areas shall be a 0.6-m thick earthen pad or a 25-mm thick steel plate placed over the area where debris can fall. Prior to reopening the roadway to public traffic, all debris, protective pads, and devices shall be removed and the roadway swept clean with wet power sweepers or equivalent methods.

For bridge removal that requires the Contractor's registered engineer to prepare and sign the bridge removal plan, the Contractor's registered engineer shall be present at all times when bridge removal operations are in progress. The Contractor's registered engineer shall inspect the bridge removal operation and report in writing on a daily basis the progress of the operation and the status of the remaining structure. A copy of the daily report shall be available at the site of the work at all times. Should an unplanned event occur or the bridge operation deviate from the approved bridge removal plan, the Contractor's registered engineer shall submit immediately to the Engineer for approval, the procedure of operation proposed to correct or remedy the occurrence.

Full compensation for conforming to the handling, removal, hauling and disposal of structure excavation (Type Z-2) (Aerially Deposited Lead) resulting from bridge removal (portion) shall be considered as included in the contract lump sum price paid for bridge removal (portion) at the locations listed in the Engineer's Estimate, and no additional compensation will be allowed therefor.

## **CLEAN BRIDGE DECK**

This work shall consist of cleaning the portland cement concrete bridge deck surface as shown on the plans and as specified in these special provisions.

The deck surface shall be cleaned by abrasive blasting and shall be dry when blast cleaning is performed.

Traffic stripes, pavement markings, and pavement markers shall be removed as specified in these special provisions during the process of cleaning the deck.

Where abrasive blasting is being performed within 3 m of a lane occupied by public traffic, the residue including dust shall be removed immediately after contact between the abrasive and the surface being treated. The removal shall be by a vacuum attachment operating concurrently with the abrasive blasting operation.

Nothing in these special provisions shall relieve the Contractor from the responsibilities provided in Section 7-1.09, "Public Safety," of the Standard Specifications.

After abrasive cleaning, loose material shall be blown from visible cracks using high pressure air, and the entire deck surface shall be cleaned by manual or power sweeping.

Equipment shall be fitted with suitable traps, filters, drip pans, or other devices as necessary to prevent oil or other deleterious material from being deposited on the deck.

If the surface becomes contaminated at any time prior to placing the penetrating sealer, the affected surface shall be cleaned by abrasive blasting followed by manual or power sweeping.

Except otherwise provided, removed materials shall become the property of the Contractor and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Cleaning bridge deck surface will be measured by the square meter of surface that is cleaned, based on field measurement of the completed work.

The contract price paid per square meter for clean bridge deck shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in cleaning the bridge deck, including removing contrast treatment except slurry or chip seal contrast treatment, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## **REMOVE CONCRETE**

Concrete curb and concrete gutter where shown on the plans to be removed, shall be removed.

Removing concrete curb and concrete gutter will be measured by the meter, measured along the curb or gutter before removal operations.

Concrete removed shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

## **REMOVE CONCRETE BARRIER**

Concrete barrier (Type 1A) where shown on the plans to be removed, shall be removed.

Removing concrete barrier (Type 1A) will be measured by the meter, measured along the barrier before removal operations.

Concrete removed shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

## **10-1.24 CLEARING AND GRUBBING**

Clearing and grubbing shall conform to the provisions in Section 16, "Clearing and Grubbing," of the Standard Specifications and these special provisions.

Attention is directed to "Aerially Deposited Lead" of these special provisions.

Existing vegetation outside the areas to be cleared and grubbed shall be protected from injury or damage resulting from the Contractor's operations.

Nothing herein shall be construed as relieving the Contractor of the Contractor's responsibility for final cleanup of the highway as provided in Section 4-1.02, "Final Cleaning Up," of the Standard Specifications.

## **10-1.25 EARTHWORK**

Earthwork shall conform to the provisions in Section 19, "Earthwork," of the Standard Specifications and these special provisions.

Surplus excavated material not designated or determined to contain aerially deposited lead shall become the property of the Contractor and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Where a portion of the existing surfacing is to be removed, the outline of the area to be removed shall be cut on a neat line with a power-driven saw to a minimum depth of 50 mm before removing the surfacing. Full compensation for cutting the existing surfacing shall be considered as included in the contract price paid per cubic meter for roadway excavation and no additional compensation will be allowed therefor.

Reinforcement or metal attached to reinforced concrete rubble placed in embankments shall not protrude above the grading plane. Prior to placement within 0.6-m below the grading plane of embankments, reinforcement or metal shall be trimmed to no greater than 20 mm from the face of reinforced concrete rubble. Full compensation for trimming reinforcement or metal shall be considered as included in the contract prices paid per cubic meter for the types of excavation shown in the Engineer's estimate, or the contract prices paid for furnishing and placing imported borrow or embankment material, as the case may be, and no additional compensation will be allowed therefor.

If structure excavation or structure backfill involved in bridges is not otherwise designated by type, and payment for the structure excavation or structure backfill has not otherwise been provided for in the Standard Specifications or these special provisions, the structure excavation or structure backfill will be paid for at the contract price per cubic meter for structure excavation (bridge), or structure backfill (bridge).

#### **10-1.26 CONTROLLED LOW STRENGTH MATERIAL**

Controlled low strength material shall consist of a workable mixture of aggregate, cementitious materials, and water and shall conform to the provisions for slurry cement backfill in Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications and these special provisions.

At the option of the Contractor, controlled low strength material may be used as structure backfill for pipe culverts, except that controlled low strength material shall not be used as structure backfill for aluminum and aluminum-coated culverts nor for culverts having a diameter or span greater than 6.1 m.

When controlled low strength material is used for structure backfill, the width of the excavation shown on the plans may be reduced so that the clear distance between the outside of the pipe and the side of the excavation, on each side of the pipe, is a minimum of 300 mm. This minimum may be reduced to 150 mm when the height of cover is less than or equal to 6.1 m or the pipe diameter or span is less than 1050 mm.

Controlled low strength material in new construction shall not be permanently placed higher than the basement soil. For trenches in existing pavements, permanent placement shall be no higher than the bottom of the existing pavement permeable drainage layer. If a drainage layer does not exist, permanent placement in existing pavements shall be no higher than 25 mm below the bottom of the existing asphalt concrete surfacing or no higher than the top of base below the existing portland cement concrete pavement. The minimum height that controlled low strength material shall be placed, relative to the culvert invert, is 0.5 diameter or 0.5 height for rigid culverts and 0.7 diameter or 0.7 height for flexible culverts.

When controlled low strength material is proposed for use, the Contractor shall submit a mix design and test data to the Engineer for approval prior to excavating the trench for which controlled low strength material is proposed for use. The test data and mix design shall provide for the following:

- A. A 28-day compressive strength between 345 kPa and 690 kPa for pipe culverts having a height of cover of 6.1 m or less and a minimum 28-day compressive strength of 690 kPa for pipe culverts having a height of cover greater than 6.1 m. Compressive strength shall be determined in conformance with the requirements in ASTM Designation: D 4832.
- B. When controlled low strength material is used as structure backfill for pipe culverts, the sections of pipe culvert in contact with the controlled low strength material shall conform to the requirements of Chapter 850 of the Highway Design Manual using the minimum resistivity, pH, chloride content, and sulfate content of the hardened controlled low strength material. Minimum resistivity and pH shall be determined in conformance with the requirements of California Test 643. The chloride content shall be determined in conformance with the requirements of California Test 422 and the sulfate content shall be determined in conformance with the requirements of California Test 417.
- C. Cement shall be any type of portland cement conforming to the requirements in ASTM Designation: C 150; or any type of blended hydraulic cement conforming to the requirements in ASTM Designation: C 595M or the physical requirements in ASTM Designation: C 1157M. Testing of cement will not be required.
- D. Admixtures may be used in conformance with the provisions in Section 90-4, "Admixtures," of the Standard Specifications. Chemical admixtures containing chlorides as Cl in excess of one percent by mass of admixture, as determined in conformance with the requirements of California Test 415, shall not be used. If an air-entraining admixture is used, the maximum air content shall be limited to 20 percent. Mineral admixtures shall be used at the Contractor's option.

Materials for controlled low strength material shall be thoroughly machine-mixed in a pugmill, rotary drum or other approved mixer. Mixing shall continue until the cementitious material and water are thoroughly dispersed throughout the

material. Controlled low strength material shall be placed in the work within 3 hours after introduction of the cement to the aggregates.

When controlled low strength material is to be placed within the traveled way or otherwise to be covered by paving or embankment materials, the material shall achieve a maximum indentation diameter of 76 mm prior to covering and opening to public traffic. Penetration resistance shall be measured in conformance with the requirements in ASTM Designation: D 6024.

Controlled low strength material used as structure backfill for pipe culverts will be considered structure backfill for compensation purposes.

#### **10-1.27 MATERIAL CONTAINING AERIALY DEPOSITED LEAD**

Earthwork involving materials containing aerially deposited lead shall conform to the provisions in "Earthwork" and this section "Material Containing Aerially Deposited Lead" of these special provisions.

Attention is directed to "Aerially Deposited Lead" of these special provisions.

Type Z-2 material contains aerially deposited lead in average concentrations (1) greater than or equal to 1000 mg/kg Total Lead, or (2) greater than or equal to 5.0 mg/L Soluble Lead, as tested using the California Waste Extraction Test, and the material is surplus, or (3) greater than or equal to 5.0 mg/L Soluble Lead and greater than 350 mg/kg Total Lead, as tested using the California Waste Extraction Test. Type Z-2 material exists from Station 0+37.18 to Station 01+11.28 NB "SW-1", from Station 02+67.14 to Station 02+73.29 NB "LINE E", from Station 2+73.29 to Station 4+10.98 NB "SW-3", from Station 3+85.86 to Station 4+83.71 NB "SW-9", from Station 5+29.71 to Station 5+35.78 SB "LINE N", from station 5+35.78 to 8+12.96 SB "SW-4", from Station 8+78.26 to 9+88.40 SB "SW-8", from Station 10+81.26 to Station 12+01.68 SB "SW-12", and from a depth of 0 m to 1.5 m below existing grade, or as shown on the plans. These materials are hazardous waste regulated by the State of California and shall be transported to and disposed of at a Class 1 Disposal Site. Materials excavated from these areas shall be transported by a hazardous waste transporter registered with the Department of Toxic Substances Control using the required procedures for creating a manifest of materials. The vehicles used to transport the hazardous materials shall conform to the current certifications of compliance of the Department of Toxic Substances Control.

#### **LEAD COMPLIANCE PLAN**

The Contractor shall prepare a project specific Lead Compliance Plan to prevent or minimize worker exposure to lead while handling material containing aerially deposited lead. Attention is directed to Title 8, California Code of Regulations, Section 1532.1, "Lead," for specific Cal-OSHA requirements when working with lead.

The Lead Compliance Plan shall contain the elements listed in Title 8, California Code of Regulations, Section 1532.1(e)(2)(B). Before submission to the Engineer, the Lead Compliance Plan shall be approved by an Industrial Hygienist certified in Comprehensive Practice by the American Board of Industrial Hygiene. The Plan shall be submitted to the Engineer for review and acceptance at least 15 days prior to beginning work in areas containing aerially deposited lead.

The Lead Compliance Plan shall include perimeter air monitoring incorporating upwind and downwind locations as shown on the plans or as approved by the Engineer. Monitoring shall be by personal air samplers using National Institute of Safety and Health (NIOSH) Method 7082. Sampling shall achieve a detection limit of  $0.05\mu\text{g}/\text{m}^3$  of air per day. Daily monitoring shall take place while the Contractor clears and grubs and performs earthwork operations. A single representative daily sample shall be analyzed for lead. Results shall be analyzed and provided to the Engineer within 24 hours. Average lead concentrations shall not exceed  $1.5\mu\text{g}/\text{m}^3$  of air per day. If concentrations exceed this level the Contractor shall stop work and modify the work to prevent release of lead. Monitoring shall be done under the direction of and data reviewed by and signed by a Certified Industrial Hygienist.

The Contractor shall not work in areas containing aerially deposited lead within the project limits, unless authorized in writing by the Engineer, until the Engineer has accepted the Lead Compliance Plan.

Prior to performing work in areas containing aerially deposited lead, personnel who have no prior training or are not current in their training status, including State personnel, shall complete a safety training program provided by the Contractor. The safety training program shall meet the requirements of Title 8, California Code of Regulations, Section 1532.1, "Lead."

Personal protective equipment, training, and washing facilities required by the Contractor's Lead Compliance Plan shall be supplied to State personnel by the Contractor. The number of State personnel will be 2.

The Engineer will notify the Contractor of acceptance or rejection of any submitted or revised Lead Compliance Plan not more than 10 days after submittal of the plan.

The contract lump sum price paid for Lead Compliance Plan shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in preparing the Lead Compliance Plan, including paying the Certified Industrial Hygienist, and for providing personal protective equipment, training and medical surveillance, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## **EXCAVATION AND TRANSPORTATION PLAN**

Within 15 days after approval of the contract, the Contractor shall submit 3 copies of the Excavation and Transportation Plan to the Engineer. The Engineer will have 7 days to review the Excavation and Transportation Plan. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the Excavation and Transportation Plan within 7 days of receipt of the Engineer's comments. The Engineer will have 7 days to review the revisions. Upon the Engineer's approval of the Excavation and Transportation Plan, 3 additional copies of the Excavation and Transportation Plan incorporating the required changes shall be submitted to the Engineer. Minor changes or clarifications to the initial submittal may be made and attached as amendments to the Excavation and Transportation Plan. In order to allow construction to proceed, the Engineer may conditionally approve the Excavation and Transportation Plan while minor revisions or amendments to the Plan are being completed.

The Contractor shall prepare a written, project specific Excavation and Transportation Plan establishing the procedures the Contractor will use to comply with requirements for excavating, transporting, and placing (or disposing) of material containing aurally deposited lead. The Excavation and Transportation Plan shall conform to the regulations of the Department of Toxic Substance Control and the California Division of Occupational Safety and Health Administration (Cal-OSHA). The sampling and analysis plans shall meet the requirements for the design and development of the sampling plan, statistical analysis, and reporting of test results contained in USEPA, SW 846, "Test Methods for Evaluating Solid Waste," Volume II: Field Manual Physical/Chemical, Chapter Nine, Section 9.1. The plan shall contain, but not be limited to the following elements:

- A. Excavation schedule (by location and date)
- B. Temporary locations of stockpiled material
- C. Sampling and analysis plans for areas after removal of a stockpile
  - 1. Location and number of samples
  - 2. Analytical laboratory
- D. Sampling and analysis plan for post excavation as shown on the plans.
- E. Dust control measures
- F. Air monitoring
  - 1. Location and type of equipment
  - 2. Sampling frequency
  - 3. Analytical laboratory
- G. Transportation equipment and routes
- H. Method for preventing spills and tracking material onto public roads
- I. Truck waiting and staging areas
- J. Site for disposal of hazardous waste
- K. Spill Contingency Plan for material containing aurally deposited lead

## **DUST CONTROL**

Excavation, transportation, placement, and handling of materials containing aurally deposited lead shall result in no visible dust migration. The Contractor shall have a water truck or tank on the job site at all times while clearing and grubbing and performing earthwork operations in work areas containing aurally deposited lead.

Stockpiles of material containing aurally deposited lead shall not be placed where affected by surface run-on or run-off. Stockpiles shall be covered with plastic sheeting 0.33 mm minimum thickness or 0.3 m of non-hazardous material. Stockpiles shall not be placed in environmentally sensitive areas. Stockpiled material shall not enter storm drains, inlets, or waters of the State.

## **MATERIAL TRANSPORTATION**

Prior to traveling on public roads, loose and extraneous material shall be removed from surfaces outside the cargo areas of the transporting vehicles and the cargo shall be covered with tarpaulins, or other cover, as outlined in the approved Excavation and Transportation Plan. The Contractor shall be responsible for costs due to spillage of material containing lead during transport. The Department will not consider the Contractor a generator of these hazardous materials, and the Contractor will not be obligated for further cleanup, removal, or remedial action for such materials handled or disposed of in conformance with the requirements specified in these special provisions and the appropriate State and Federal laws and regulations and county and municipal ordinances and regulations regarding hazardous waste.

## **DISPOSAL**

Surplus materials whose lead content is not known shall be analyzed for aurally deposited lead by the Contractor prior to removing the materials from within the project limits. The Contractor shall submit a sampling and analysis plan and the name of the analytical laboratory to the Engineer at least 15 days prior to beginning sampling or analysis. The Contractor shall use a laboratory certified by the California Department of Health Services. Sampling shall be at a minimum rate of one sample for each 150 m<sup>3</sup> of surplus material and tested for lead using EPA Method 6010 or 7000 series.

Sampling, analyses, and reporting of results for surplus materials not previously sampled will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Materials containing aurally deposited lead shall be disposed of within California. The disposal site shall be operating under a permit issued by the California Environmental Protection Agency (Cal-EPA) Boards.

The Engineer will obtain the Environmental Protection Agency (EPA) Generator Identification Number for hazardous material disposal. The Engineer will sign all hazardous waste manifests. The Contractor shall notify the Engineer five days before the manifests are to be signed.

Sampling, analyzing, transporting, and disposing of materials containing aurally deposited lead excavated outside the pay limits of excavation will be at the Contractor's expense.

## **MEASUREMENT AND PAYMENT**

Quantities of roadway excavation (aurally deposited lead), of the types shown in the Engineer's Estimate, will be measured and paid for in the same manner specified for roadway excavation, in Section 19, "Earthwork," of the Standard Specifications.

Full compensation for preparing an approved Excavation and Transportation Plan, transporting material containing aurally deposited lead reused in the work from location to location, and transporting and disposing of material containing aurally deposited lead shall be considered as included in the contract prices paid per cubic meter for the items of roadway excavation (aurally deposited lead) involved, and no additional compensation will be allowed therefor.

No payment for stockpiling of material containing aurally deposited lead will be made, unless the stockpiling is ordered by the Engineer.

### **10-1.28 EXTEND IRRIGATION CROSSOVERS**

Extend existing irrigation crossovers shall conform to the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications and these special provisions.

Extend irrigation crossovers shall include conduit, water line crossover, and sprinkler control crossover extensions and appurtenances, locating existing irrigation crossovers and pressure testing existing and new water line crossovers. The sizes of conduit, water line crossover, and sprinkler control crossover extensions shall be as shown on the plans.

Before work is started in an area where an existing irrigation crossover conduit is to be extended, the existing conduit shall be located by the Contractor. When exploratory holes are used to locate the existing conduit, the exploratory holes shall be excavated in conformance with the provisions in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

If debris is encountered in the ends of conduits to be extended, the debris shall be removed prior to extending conduits. Removal of debris within the first meter in the conduits shall be at the Contractor's expense. If debris is encountered in the conduit more than one meter from the ends of the conduits to be extended, the additional debris shall be removed as directed by the Engineer and will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Prior to installation of water line crossover extensions, the existing water lines shall be pressure tested for leakage in conformance with the provisions in Section 20-5.03H, "Pressure Testing," of the Standard Specifications. Repairs to the existing water line crossover, when ordered by the Engineer, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Conduit extensions shall be corrugated high density polyethylene (CHDPE) pipe.

Water line crossover extensions shall be plastic pipe (PR 315) (supply line).

Sprinkler control crossover extensions shall be Type 3 electrical conduit.

Conductors shall be removed from existing sprinkler control crossovers to be extended.

After installation of the sprinkler control crossover extensions, new conductors shall be installed without splices in existing and extended sprinkler control crossovers. New conductors shall match the removed conductors in color and size and shall be spliced to the existing conductors in adjacent pull boxes. After the new conductors are installed, the conductors shall be tested in the same manner specified for traffic signal, sign illumination, and lighting circuits in conformance with the provisions in Section 86-2.14B, "Field Testing," of the Standard Specifications.

After water line crossover extensions have been installed, existing and extended water line crossovers shall be retested for leakage in conformance with the provisions in Section 20-5.03H, "Pressure Testing," of the Standard Specifications.

Leaks that develop shall be repaired at the Contractor's expense and the water line crossovers shall be retested until a satisfactory pressure test is achieved.

#### **10-1.29 AGGREGATE BASE**

Aggregate base shall be Class 3 and shall conform to the provisions in Section 26, "Aggregate Bases," of the Standard Specifications and these special provisions.

The restriction that the amount of reclaimed material included in Class 3 aggregate base not exceed 50 percent of the total volume of the aggregate used shall not apply. Aggregate for Class 3 aggregate base may include reclaimed glass. Aggregate base incorporating reclaimed glass shall not be placed at locations where surfacing will not be placed over the aggregate base.

#### **10-1.30 ASPHALT CONCRETE**

Asphalt concrete shall be Type B and shall conform to the provisions in Section 39, "Asphalt Concrete," of the Standard Specifications and these special provisions.

The amount of asphalt binder used in asphalt concrete placed in dikes shall be increased one percent by mass of the aggregate over the amount of asphalt binder determined for use in asphalt concrete placed on the traveled way.

A prime coat of liquid asphalt, MC shall be applied.

Aggregate for asphalt concrete dikes shall be in conformance with the provisions for 9.5-mm Maximum grading in Section 39-2.02, "Aggregate," of the Standard Specifications.

If the Contractor selects the batch mixing method, asphalt concrete shall be produced by the automatic batch mixing method in conformance with the provisions in Section 39-3.03A(2), "Automatic Proportioning," of the Standard Specifications.

If the finished surface of the asphalt concrete on traffic lanes does not meet the specified surface tolerances, the surfacing shall be brought within tolerance by either (1) abrasive grinding (with fog seal coat on the areas which have been ground), (2) removal and replacement or (3) placing an overlay of asphalt concrete. The method will be selected by the Engineer. The corrective work shall be at the Contractor's expense.

If abrasive grinding is used to bring the finished surface to the specified surface tolerances, additional grinding shall be performed, as necessary, to extend the area ground in each lateral direction so that the lateral limits of grinding are at a constant offset from, and parallel to, the nearest lane line or pavement edge, and in each longitudinal direction so that the grinding begins and ends at lines normal to the pavement centerline, within any ground area. Ground areas shall be neat rectangular areas of uniform surface appearance. Abrasive grinding shall conform to the provisions in the first paragraph and the last 4 paragraphs in Section 42-2.02, "Construction," of the Standard Specifications.

#### **10-1.31 PILING**

##### **GENERAL**

Piling shall conform to the provisions in Section 49, "Piling," of the Standard Specifications, and these special provisions.

Unless otherwise specified, welding of any work performed in conformance with the provisions in Section 49, "Piling," of the Standard Specifications, shall be in conformance with the requirements in AWS D1.1.

Foundation recommendations are included in the "Information Handout" available to the Contractor as provided for in Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," of the Standard Specifications.

Attention is directed to "Welding" of these special provisions.

At the option of the Contractor, vibratory hammers or oscillators may be used to install piles or permanent casings.

Difficult pile installation is anticipated due to the presence of caving soils underground utilities, aerially deposited lead materials, the requirements of sound control, and traffic control.

##### **CAST-IN-DRILLED-HOLE CONCRETE PILES**

Cast-in-drilled-hole concrete piling shall conform to the provisions in Section 49-4, "Cast-In-Place Concrete Piles," of the Standard Specifications and these special provisions.

The provisions of "Welding" of these special provisions shall not apply to temporary steel casings.

Cast-in-drilled-hole concrete piles 600 mm in diameter or larger may be constructed by excavation and depositing concrete under slurry.

Pile construction in uncased drilled holes shall be completed within the same day that excavation of the drilled holes is begun.

## **Materials**

Concrete deposited under slurry shall have a nominal penetration equal to or greater than 90 mm. Concrete shall be proportioned to prevent excessive bleed water and segregation.

Concrete deposited under slurry shall contain not less than 400 kg of cementitious material per cubic meter.

The combined aggregate grading used in concrete for cast-in-drilled-hole concrete piling shall be either the 25-mm maximum grading, the 12.5-mm maximum grading, or the 9.5-mm maximum grading and shall conform to the requirements in Section 90-3 "Aggregate Gradings," of the Standard Specifications.

## **Mineral Slurry**

Mineral slurry shall be mixed and thoroughly hydrated in slurry tanks, and slurry shall be sampled from the slurry tanks and tested before placement in the drilled hole.

Slurry shall be recirculated or continuously agitated in the drilled hole to maintain the specified properties.

Recirculation shall include removal of drill cuttings from the slurry before discharging the slurry back into the drilled hole. When recirculation is used, the slurry shall be sampled and tested at least every 2 hours after beginning its use until tests show that the samples taken from the slurry tank and from near the bottom of the hole have consistent specified properties. Subsequently, slurry shall be sampled at least twice per shift as long as the specified properties remain consistent.

Slurry that is not recirculated in the drilled hole shall be sampled and tested at least every 2 hours after beginning its use. The slurry shall be sampled midheight and near the bottom of the hole. Slurry shall be recirculated when tests show that the samples taken from midheight and near the bottom of the hole do not have consistent specified properties.

Slurry shall also be sampled and tested prior to final cleaning of the bottom of the hole and again just prior to placing concrete. Samples shall be taken from midheight and near the bottom of the hole. Cleaning of the bottom of the hole and placement of the concrete shall not start until tests show that the samples taken from midheight and near the bottom of the hole have consistent specified properties.

Mineral slurry shall be tested for conformance to the requirements shown in the following table:

MINERAL SLURRY		
PROPERTY	REQUIREMENT	TEST
Density (kg/m <sup>3</sup> ) - before placement in the drilled hole - during drilling - prior to final cleaning - immediately prior to placing concrete	1030* to 1110*  1030* to 1200*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter) bentonite attapulgate	29 to 53  29 to 42	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	8 to 10.5	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning - immediately prior to placing concrete	less than or equal to 4.0	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m <sup>3</sup> . Slurry temperature shall be at least 4 degrees Celsius when tested.		

Any caked slurry on the sides or bottom of hole shall be removed before placing reinforcement. If concrete is not placed immediately after placing reinforcement, the reinforcement shall be removed and cleaned of slurry, the sides of the drilled hole cleaned of caked slurry, and the reinforcement again placed in the hole for concrete placement.

### Synthetic Slurry

Synthetic slurries shall be used in conformance with the manufacturer's recommendations and these special provisions. The following synthetic slurries may be used:

PRODUCT	MANUFACTURER
SlurryPro CDP	KB Technologies Ltd. Suite 216 735 Broad Street Chattanooga, TN 37402 (800) 525-5237
Super Mud	PDS Company c/o Champion Equipment Company 8140 East Rosecrans Ave. Paramount, CA 90723 (562) 634-8180
Shore Pac GCV	CETCO Drilling Products Group 1350 West Shure Drive Arlington Heights, IL 60004 (847) 392-5800

Inclusion of a synthetic slurry on the above list may be obtained by meeting the Department's requirements for synthetic slurries. The requirements can be obtained from the Office of Structure Design, P.O. Box 942874, Sacramento, CA 94274-0001.

Synthetic slurries listed may not be appropriate for a given site.

Synthetic slurries shall not be used in holes drilled in primarily soft or very soft cohesive soils as determined by the Engineer.

A manufacturer's representative, as approved by the Engineer, shall provide technical assistance for the use of their product, shall be at the site prior to introduction of the synthetic slurry into a drilled hole, and shall remain at the site until released by the Engineer.

Synthetic slurries shall be sampled and tested at both mid-height and near the bottom of the drilled hole. Samples shall be taken and tested during drilling as necessary to verify the control of the properties of the slurry. Samples shall be taken and tested when drilling is complete, but prior to final cleaning of the bottom of the hole. When samples are in conformance with the requirements shown in the following tables for each slurry product, the bottom of the hole shall be cleaned and any loose or settled material removed. Samples shall be obtained and tested after final cleaning with steel reinforcement in place and just prior to placing concrete.

SlurryPro CDP synthetic slurries shall be tested for conformance to the requirements shown in the following table:

SLURRYPRO CDP KB Technologies Ltd.		
PROPERTY	REQUIREMENT	TEST
Density (kg/m <sup>3</sup> ) - during drilling  - prior to final cleaning - just prior to placing concrete	less than or equal to 1075*  less than or equal to 1025*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter) - during drilling  -prior to final cleaning - just prior to placing concrete	53 to 127  less than or equal to 74	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	6 to 11.5	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning - just prior to placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m <sup>3</sup> . Slurry temperature shall be at least 4 degrees Celsius when tested.		

Super Mud synthetic slurries shall be tested for conformance to the requirements shown in the following table:

SUPER MUD PDS Company		
PROPERTY	REQUIREMENT	TEST
Density (kg/m <sup>3</sup> ) - prior to final cleaning - just prior to placing concrete	less than or equal to 1025*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter) - during drilling - prior to final cleaning - just prior to placing concrete	34 to 64  less than or equal to 64	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	8 to 10.0	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning -just prior to placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
<p>*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m<sup>3</sup>. Slurry temperature shall be at least 4 degrees Celsius when tested.</p>		

Shore Pac GCV synthetic slurries shall be tested for conformance to the requirements shown in the following table:

Shore Pac GCV CETCO Drilling Products Group		
PROPERTY	REQUIREMENT	TEST
Density (kg/m <sup>3</sup> ) - prior to final cleaning - just prior to placing concrete	less than or equal to 1025*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter) - during drilling  - prior to final cleaning - just prior to placing concrete	35 to 78  less than or equal to 60	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	8.0 to 11.0	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning -just prior to placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m <sup>3</sup> . Slurry temperature shall be at least 4 degrees Celsius when tested.		

#### Water Slurry

At the option of the Contractor water may be used as slurry when casing is used for the entire length of the drilled hole. Water slurry shall be tested for conformance to the requirements shown in the following table:

WATER SLURRY		
PROPERTY	REQUIREMENT	TEST

Density (kg/m <sup>3</sup> ) - prior to final cleaning - just prior to placing concrete	1017 *	Mud Weight (Density) API 13B-1 Section 1
Sand Content (percent) - prior to final cleaning -just prior to placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, salt water slurry may be used, and the allowable densities may be increased up to 32 kg/m <sup>3</sup> .		

### Construction

The Contractor shall submit a placing plan to the Engineer for approval prior to producing the test batch for cast-in-drilled-hole concrete piling and at least 10 working days prior to constructing piling. The plan shall include complete description, details, and supporting calculations as listed below:

#### A. Requirements for all cast-in-drilled hole concrete piling:

1. Concrete mix design, certified test data, and trial batch reports.
2. Drilling or coring methods and equipment.
3. Proposed method for casing installation and removal when necessary.
4. Plan view drawing of pile showing reinforcement and inspection pipes, if required.
5. Methods for placing, positioning, and supporting bar reinforcement.
6. Methods and equipment for accurately determining the depth of concrete and actual and theoretical volume placed, including effects on volume of concrete when any casings are withdrawn.
7. Methods and equipment for verifying that the bottom of the drilled hole is clean prior to placing concrete.
8. Methods and equipment for preventing upward movement of reinforcement, including the Contractor's means of detecting and measuring upward movement during concrete placement operations.

#### B. Additional requirements when concrete is placed under slurry:

1. Concrete batching, delivery, and placing systems including time schedules and capacities therefor. Time schedules shall include the time required for each concrete placing operation at each pile.
2. Concrete placing rate calculations. When requested by the Engineer, calculations shall be based on the initial pump pressures or static head on the concrete and losses throughout the placing system, including anticipated head of slurry and concrete to be displaced.
3. Suppliers test reports on the physical and chemical properties of the slurry and any proposed slurry chemical additives including Material Safety Data Sheet.
4. Slurry testing equipment and procedures.
5. Removal and disposal of excavation, slurry, and contaminated concrete, including methods and rates of removal.
6. Slurry agitating, recirculating, and cleaning methods and equipment.

In addition to compressive strength requirements, the consistency of the concrete to be deposited under slurry shall be verified before use by producing a batch to be tested. The test batch shall be produced and delivered to the project under conditions and in time periods similar to those expected during the placement of concrete in the piles. Concrete for the test batch shall be placed in an excavated hole or suitable container of adequate size to allow testing in conformance with California Test 533. Depositing of test batch concrete under slurry will not be required. For piles where the time required for each concrete placing operation, as submitted in the placing plan, will be 2 hours or less, the test batch shall demonstrate that the proposed concrete mix design achieves both the specified nominal penetration and a penetration of at least 50 mm after twice that time has elapsed. For piles where the time required for each concrete placing operation, as submitted in the

placing plan, will be more than 2 hours, the test batch shall demonstrate that the proposed concrete mix design achieves both the specified nominal penetration and a penetration of at least 50 mm after that time plus 2 hours has elapsed. The time period shall begin at the start of placement. The concrete shall not be vibrated or agitated during the test period. Upon completion of testing, the concrete shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Concrete deposited under slurry shall not be vibrated until all temporary casing is removed and concrete contaminated with soil, slurry, or other materials is removed. Concrete deposited under slurry shall be vibrated in the upper 2 m of the pile.

The concrete deposited under slurry shall be carefully placed in a compact, monolithic mass and by a method that will prevent washing of the concrete. Placing concrete shall be a continuous operation lasting not more than the time required for each concrete placing operation at each pile, as submitted in the placing plan, unless otherwise approved in writing by the Engineer. The concrete shall be placed with concrete pumps and delivery tube system of adequate number and size to complete the placing of concrete in the time specified. The delivery tube system shall consist of one of the following:

- A. A tremie tube or tubes, each of which are at least 250 mm in diameter, fed by one or more concrete pumps.
- B. One or more concrete pump tubes, each fed by a single concrete pump.

The delivery tube system shall consist of watertight tubes with sufficient rigidity to keep the ends always in the mass of concrete placed. If only one delivery tube is utilized to place the concrete, the tube shall be placed near the center of the drilled hole. Multiple tubes shall be uniformly spaced in the hole. Internal bracing for the steel reinforcing cage shall accommodate the delivery tube system. Tremies shall not be used for piles without space for a 250-mm tube.

Spillage of concrete into the slurry during concrete placing operations shall not be allowed. Delivery tubes shall be capped with a water tight cap, or plugged above the slurry level with a good quality, tight fitting, moving plug that will expel the slurry from the tube as the tube is charged with concrete. The cap or plug shall be designed to be released as the tube is charged. The pump discharge or tremie tube shall extend to the bottom of the hole before charging the tube with concrete. After charging the delivery tube system with concrete, the flow of concrete through a tube shall be induced by slightly raising the discharge end. During concrete placement, the tip of the delivery tube shall be maintained to prevent reentry of the slurry into the tube. Until at least 3 m of concrete has been placed, the tip of the delivery tube shall be within 150 mm of the bottom of the drilled hole, and then the embedment of the tip shall be maintained at least 3 m below the top surface of the concrete. Rapid raising or lowering of the delivery tube shall not be permitted. If the seal is lost or the delivery tube becomes plugged and must be removed, the tube shall be withdrawn, the tube cleaned, the tip of the tube capped to prevent entrance of the slurry, and the operation restarted by pushing the capped tube 3 m into the concrete and then reinitiating the flow of concrete.

When slurry is used, a fully operational standby concrete pump, adequate to complete the work in the time specified, shall be provided at the site during concrete placement. The slurry level shall be maintained within 300 mm of the top of the drilled hole.

A log of concrete placement for each drilled hole shall be maintained by the Contractor when concrete is deposited under slurry. The log shall show the pile location, tip elevation, dates of excavation and concrete placement, total quantity of concrete deposited, length and tip elevation of any casing, and details of any hole stabilization method and materials used. The log shall include a 215 mm x 280 mm sized graph of the concrete placed versus depth of hole filled. The graph shall be plotted continuously throughout placing of concrete. The depth of drilled hole filled shall be plotted vertically with the pile tip oriented at the bottom and the quantity of concrete shall be plotted horizontally. Readings shall be made at least at each 1.5 m of pile depth, and the time of the reading shall be indicated. The graph shall be labeled with the pile location, tip elevation, cutoff elevation, and the dates of excavation and concrete placement. The log shall be delivered to the Engineer within one working day of completion of placing concrete in the pile.

After placing reinforcement and prior to placing concrete in the drilled hole, if drill cuttings settle out of slurry, the bottom of the drilled hole shall be cleaned. The Contractor shall verify that the bottom of the drilled hole is clean.

If temporary casing is used, concrete placed under slurry shall be maintained at a level at least 1.5 m above the bottom of the casing. The withdrawal of casings shall not cause contamination of the concrete with slurry.

Material resulting from using slurry shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

### **Acceptance Testing and Mitigation**

Vertical inspection pipes for acceptance testing shall be provided in all cast-in-drilled-hole concrete piles that are 600 mm in diameter or larger, except when the holes are dry or when the holes are dewatered without the use of temporary casing to control the groundwater.

Inspection pipes shall be Schedule 40 polyvinyl chloride pipe with a nominal inside diameter of 50 mm. Each inspection pipe shall be capped top and bottom and shall have watertight couplers to provide a clean, dry and unobstructed 50-mm diameter clear opening from 1.0 m above the pile cutoff down to the bottom of the reinforcing cage.

Inspection pipes shall be placed around the pile, inside the outermost spiral or hoop reinforcement, and 75 mm clear of the vertical reinforcement, at a uniform spacing not exceeding 840 mm measured along the circle passing through the centers of inspection pipes. A minimum of 2 inspection pipes per pile shall be used. When the vertical reinforcement is not bundled and each bar is not more than 26 mm in diameter, inspection pipes may be placed 50 mm clear of the vertical reinforcement. The inspection pipes shall be placed to provide the maximum diameter circle that passes through the centers of the inspection pipes while maintaining the clear spacing required herein. The pipes shall be installed in straight alignment, parallel to the main reinforcement, and securely fastened in place to prevent misalignment during installation of the reinforcement and placing of concrete in the hole.

The Contractor shall log the location of the inspection pipe couplers with respect to the plane of pile cut off, and these logs shall be delivered to the Engineer upon completion of the placement of concrete in the drilled hole.

After placing concrete and before requesting acceptance tests, each inspection pipe shall be tested by the Contractor in the presence of the Engineer by passing a 48.3-mm diameter rigid cylinder 610 mm long through the complete length of pipe. If the 48.3-mm diameter rigid cylinder fails to pass any of the inspection pipes, the Contractor shall attempt to pass a 32.0-mm diameter rigid cylinder 1.375 m long through the complete length of those pipes in the presence of the Engineer. If an inspection pipe fails to pass the 32.0-mm diameter cylinder, the Contractor shall immediately fill all inspection pipes in the pile with water.

The Contractor shall replace each inspection pipe that does not pass the 32.0-mm diameter cylinder with a 50.8-mm diameter hole cored through the concrete for the entire length of the pile. Cored holes shall be located as close as possible to the inspection pipes they are replacing, no more than 150 mm inside the reinforcement, and coring shall not damage the pile reinforcement. Cored holes shall be made with a double wall core barrel system utilizing a split tube type inner barrel. Coring with a solid type inner barrel will not be allowed. Coring methods and equipment shall provide intact cores for the entire length of the pile concrete. The coring operation shall be logged by an Engineering Geologist or Civil Engineer licensed in the State of California and experienced in core logging. Coring logs shall include complete descriptions of inclusions and voids encountered during coring, and shall be delivered to the Engineer upon completion. Concrete cores shall be preserved, identified with the exact location the core was recovered from within the pile, and made available for inspection by the Engineer.

Acceptance tests of the concrete will be made by the Engineer, without cost to the Contractor. Acceptance tests will evaluate the homogeneity of the placed concrete. Tests will include gamma-gamma logging. Tests may also include crosshole sonic logging and other means of inspection selected by the Engineer. The Contractor shall not conduct operations within 8.0 m of the gamma-gamma logging operations. The Contractor shall separate reinforcing steel as necessary to allow the Engineer access to the inspection pipes to perform gamma-gamma logging or other acceptance testing. After requesting acceptance tests and providing access to the piling, the Contractor shall allow 3 weeks for the Engineer to conduct these tests and make determination of acceptance if the 48.3-mm diameter cylinder passed all inspection pipes, and 4 weeks if only the 32.0-mm diameter cylinder passed all inspection pipes. Should the Engineer fail to complete these tests within the time allowance, and if in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in inspection, the delay will be considered a right of way delay as specified in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

All inspection pipes and cored holes in a pile shall be dewatered and filled with grout after notification by the Engineer that the pile is acceptable. Placement and removal of water in the inspection pipes shall be at the Contractor's expense. Grout shall conform to the provisions in Section 50-1.09, "Bonding and Grouting," of the Standard Specifications. The inspection pipes and holes shall be filled using grout tubes that extend to the bottom of the pipe or hole or into the grout already placed.

If acceptance testing performed by the Engineer determines that a pile does not meet the requirements of the specifications, then that pile will be rejected and all depositing of concrete under slurry or concrete placed using temporary casing for the purpose of controlling groundwater shall be suspended until written changes to the methods of pile construction are approved in writing by the Engineer.

The Contractor shall submit to the Engineer for approval a mitigation plan for repair, supplementation, or replacement for each rejected cast-in-drilled-hole concrete pile, and this plan shall conform to the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. Prior to submitting this mitigation plan, the Engineer will hold a repair feasibility meeting with the Contractor to discuss the feasibility of repairing rejected piling. The Engineer will consider the size of the defect, the location of the defect, and the design information and corrosion protection considerations for the pile. This information will be made available to the Contractor, if appropriate, for the development of the mitigation plan. If the Engineer determines that it is not feasible to repair the rejected pile, the Contractor shall not include repair as a means of mitigation and shall proceed with the submittal of a mitigation plan for replacement or supplementation of the rejected pile.

If the Engineer determines that a rejected pile does not require mitigation due to structural, geotechnical, or corrosion concerns, the Contractor may elect to 1) repair the pile per the approved mitigation plan, or 2) not repair anomalies found

during acceptance testing of that pile. For such unrepaired piles, the Contractor shall pay to the State, \$400 per cubic meter for the portion of the pile affected by the anomalies. The volume, in cubic meters, of the portion of the pile affected by the anomalies, shall be calculated as the area of the cross-section of the pile affected by each anomaly, in square meters, as determined by the Engineer, multiplied by the distance, in meters, from the top of each anomaly to the specified tip of the pile. If the volume calculated for one anomaly overlaps the volume calculated for additional anomalies within the pile, the calculated volume for the overlap shall only be counted once. In no case shall the amount of the payment to the State for any such pile be less than \$400. The Department may deduct the amount from any moneys due, or that may become due the Contractor under the contract.

Pile mitigation plans shall include the following:

- A. The designation and location of the pile addressed by the mitigation plan.
- B. A review of the structural, geotechnical, and corrosion design requirements of the rejected pile.
- C. A step by step description of the mitigation work to be performed, including drawings if necessary.
- D. An assessment of how the proposed mitigation work will address the structural, geotechnical, and corrosion design requirements of the rejected pile.
- E. Methods for preservation or restoration of existing earthen materials.
- F. A list of affected facilities, if any, with methods and equipment for protection of these facilities during mitigation.
- G. The State assigned contract number, bridge number, full name of the structure as shown on the contract plans, District-County-Route-Kilometer Post, and the Contractor's (and Subcontractor's if applicable) name on each sheet.
- H. A list of materials, with quantity estimates, and personnel, with qualifications, to be used to perform the mitigation work.
- I. The seal and signature of an engineer who is licensed as a Civil Engineer by the State of California.

For rejected piles to be repaired, the Contractor shall submit a pile mitigation plan that contains the following additional information:

- A. An assessment of the nature and size of the anomalies in the rejected pile.
- B. Provisions for access for additional pile testing if required by the Engineer.

For rejected piles to be replaced or supplemented, the Contractor shall submit a pile mitigation plan that contains the following additional information:

- A. The proposed location and size of additional piling.
- B. Structural details and calculations for any modification to the structure to accommodate the replacement or supplemental piling.

All provisions for cast-in-drilled-hole concrete piling shall apply to replacement piling.

The Contractor shall allow the Engineer 3 weeks to review the mitigation plan after a complete submittal has been received.

Should the Engineer fail to review the complete pile mitigation submittal within the time specified, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the pile mitigation plan, an extension of time commensurate with the delay in completion of the work thus caused will be granted in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

When repairs are performed, the Contractor shall submit a mitigation report to the Engineer within 10 days of completion of the repair. This report shall state exactly what repair work was performed and quantify the success of the repairs relative to the submitted mitigation plan. The mitigation report shall be stamped and signed by an engineer that is licensed as a Civil Engineer by the State of California. The mitigation report shall show the State assigned contract number, bridge number, full name of the structure as shown on the contract plans, District-County-Route-Kilometer Post, and the Contractor (and Subcontractor if applicable) name on each sheet. The Engineer will be the sole judge as to whether a mitigation proposal is acceptable, the mitigation efforts are successful, and to whether additional repairs, removal and replacement, or construction of a supplemental foundation is required.

#### **MEASUREMENT AND PAYMENT (PILING)**

Measurement and payment for the various types and classes of piles shall conform to the provisions in Sections 49-6.01, "Measurement," and 49-6.02, "Payment," of the Standard Specifications and these special provisions.

Payment for cast-in-place concrete piling shall conform to the provisions in Section 49-6.02, "Payment," of the Standard Specifications except that, when the diameter of cast-in-place concrete piling is shown on the plans as 600 mm or larger, reinforcement in the piling will be paid for by the kilogram as bar reinforcing steel (bridge).

No additional compensation or extension of time will be made for additional foundation investigation, installation and testing of indicator piling, cutting off piling and restoring the foundation investigation and indicator pile sites, and review of request by the Engineer.

Full compensation for slurry, depositing concrete under slurry, test batches, inspection pipes, filling inspection holes and pipes with grout, drilling oversized cast-in-drilled-hole concrete piling, filling cave-ins and oversized piles with concrete, and redrilling through concrete, shall be considered as included in the contract prices paid per meter for cast-in-drilled-hole concrete piling of the types and sizes listed in the Engineer's Estimate, and no additional compensation will be allowed therefor.

### **10-1.32 CONCRETE STRUCTURES**

Portland cement concrete structures shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

#### **GENERAL**

Shotcrete shall not be used as an alternative construction method for reinforced concrete members unless otherwise specified.

When a roughened concrete surface is shown on the plans, the existing concrete surface shall be roughened to a full amplitude of approximately 6 mm by abrasive blasting, water blasting, or mechanical equipment.

#### **CONCRETE BARRIER SLABS**

Concrete barrier slabs shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

Steel components of abutment ties including plates, nuts, washers and rods shall conform to the provisions in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

Building paper shall be commercial quality No. 30 asphalt felt.

Polyvinyl chloride (PVC) conduit used to encase the abutment tie rod shall be commercial quality.

Bar reinforcement or abutment tie rods in drilled holes shall be bonded in conformance with the standard provisions for drilling and bonding dowels in Section 83-2.02D(1), "General," of the Standard Specifications.

If reinforcement is encountered during drilling before the specified depth is attained, the Engineer shall be notified. Unless the Engineer approves coring through the reinforcement, the hole will be rejected and a new hole, in which reinforcement is not encountered, shall be drilled adjacent to the rejected hole to the depth shown on the plans.

The top surface of concrete barrier slabs shall be finished in conformance with the provisions in Section 51-1.17, "Finishing Bridge Decks," of the Standard Specifications. The finished top surface shall not vary more than 6 mm from the lower edge of a 3.6-m straightedge placed parallel with the centerline. Edges of slabs shall be edge finished.

Hardboard and expanded polystyrene shall conform to the provisions in Section 51-1.12D, "Sheet Packing, Preformed Pads and Board Fillers," of the Standard Specifications.

Type AL joint seals shall conform to the provisions in Section 51-1.12F, "Sealed Joints," of the Standard Specifications. The sealant may be mixed by hand-held power-driven agitators and placed by hand methods.

#### **FALSEWORK**

Falsework shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

Temporary lateral bracing shall be provided to stabilize the edge beam at the Euclid Avenue Off-Ramp Undercrossing. The bracing shall be installed prior to the construction of the masonry block wall and shall remain in place until 2 days after the deck closure pour have been placed. The bracing shall be designed to prevent overturning of the edge beam and the sound wall on barrier supported by the edge beam prior to completion of the work and as a minimum shall be capable of resisting a lateral force of 1436 Pa applied full height of sound wall, barrier and edge beam laterally from both direction perpendicular to the sound wall, barrier and edge beam. Edge beam construction shall not be started until the temporary lateral bracing proposed for use by the Contractor has been approved by the Engineer. Full compensation for furnishing and constructing lateral bracing shall be considered as included in the contract price paid per cubic meter for structural concrete, bridge and no additional compensation will be allowed therefor.

The Contractor's engineer who signs the falsework drawings shall also certify in writing that the falsework is constructed in conformance with the approved drawings and the contract specifications prior to placing concrete. This certification shall

include performing any testing necessary to verify the ability of the falsework members to sustain the stresses required by the falsework design. The engineer who signs the drawings may designate a representative to perform this certification. Where falsework contains openings for railroads, vehicular traffic, or pedestrians, the designated representative shall be qualified to perform this work, shall have at least three years of combined experience in falsework design or supervising falsework construction, and shall be registered as a Civil Engineer in the State of California. For other falsework, the designated representative shall be qualified to perform this work and shall have at least three years of combined experience in falsework design or supervising falsework construction. The Contractor shall certify the experience of the designated representative in writing and provide supporting documentation demonstrating the required experience if requested by the Engineer.

### **Welding and Nondestructive Testing**

Welding of steel members, except for previously welded splices and except for when fillet welds are used where load demands are less than or equal to 175 N/mm for each 3 mm of fillet weld, shall conform to AWS D1.1 or other recognized welding standard. The welding standard to be utilized shall be specified by the Contractor on the working drawings. Previously welded splices for falsework members are defined as splices made prior to the member being shipped to the project site.

Splices made by field welding of steel beams at the project site shall undergo nondestructive testing (NDT). At the option of the Contractor, either ultrasonic testing (UT) or radiographic testing (RT) shall be used as the method of NDT for each field weld and any repair made to a previously welded splice in a steel beam. Testing shall be performed at locations selected by the Contractor. The length of a splice weld where NDT is to be performed, shall be a cumulative weld length equal to 25 percent of the original splice weld length. The cover pass shall be ground smooth at the locations to be tested. The acceptance criteria shall conform to the requirements of AWS D1.1, Section 6, for cyclically loaded nontubular connections subject to tensile stress. If repairs are required in a portion of the weld, additional NDT shall be performed on the repaired sections. The NDT method chosen shall be used for an entire splice evaluation including any required repairs.

For all field welded splices, the Contractor shall furnish to the Engineer a letter of certification which certifies that all welding and NDT, including visual inspection, are in conformance with the specifications and the welding standard shown on the approved working drawings. This letter of certification shall be signed by an engineer who is registered as a Civil Engineer in the State of California and shall be provided prior to placing any concrete for which the falsework is being erected to support.

For previously welded splices, the Contractor shall determine and perform all necessary testing and inspection required to certify the ability of the falsework members to sustain the stresses required by the falsework design. This welding certification shall be in writing, shall be signed by an engineer who is registered as a Civil Engineer in the State of California, and shall be provided prior to placing any concrete for which the falsework is being erected to support.

### **DECK CLOSURE POURS**

Where a deck closure pour is shown on the plans, reinforcement protruding into the closure space and forms for the closure pour shall conform to the following:

- A. During the time of placement of concrete in the deck, other than for the closure pour itself, reinforcing steel which protrudes into the closure space shall be completely free from any connection to the reinforcing steel, concrete, or other attachments of the adjacent structure, including forms. The reinforcing steel shall remain free of any connection for a period of not less than 24 hours following completion of the pour.
- B. Forms for the closure pour shall be supported from the superstructure on both sides of the closure space.

### **DECK CRACK TREATMENT**

The Contractor shall use all means necessary to minimize the development of shrinkage cracks.

The Contractor shall remove all equipment and materials from the deck and clean the surface as necessary for the Engineer to measure the surface crack intensity. Surface crack intensity will be determined by the Engineer after completion of concrete cure, prior to prestressing, and prior to the release of falsework. In any 50-m<sup>2</sup> portion of deck within the limits of the new concrete deck, should the intensity of cracking be such that there are more than 5 m of cracks whose width at any location exceeds 0.5-mm, the deck shall be treated with methacrylate resin. The area of deck to be treated shall have a width that extends for the entire width of new deck inside the concrete barriers and a length that extends at least 1.5 m beyond the furthest single continuous crack outside the 50-m<sup>2</sup> portion, measured from where that crack exceeds 0.5-mm in width, as determined by the Engineer.

Deck crack treatment shall consist of test sealing, and furnishing and applying methacrylate resin in conformance with the requirements of these special provisions. If grinding operation is required, deck treatment shall take place after grinding.

Prior to the start of deck treatment work, the Contractor shall submit for approval by the Engineer, a program for public safety associated with the use of methacrylate resin. The program shall identify materials, equipment, and methods to be

used. The Contractor shall not perform deck treatment work, other than that specifically authorized in writing by the Engineer, until the program has been approved.

If the measures being taken by the Contractor are inadequate to provide for public safety associated with use of methacrylate resin, the Engineer will direct the Contractor to revise the operations and the public safety program. Directions for revisions will be in writing and will specify the items in which the Contractor's program is inadequate. No further deck treatment shall be performed until public safety measures are adequate, and a revised program for public safety has been approved.

The Engineer will notify the Contractor of the approval or rejection of any submitted or revised program for public safety associated with the use of methacrylate resin within 10 working days of receipt of the final submitted program.

The State will not be liable to the Contractor for failure to approve all or any portion of an originally submitted or revised program for public safety associated with the use of methacrylate resin, nor for any delays to the work due to the Contractor's failure to submit an acceptable program for public safety associated with the use of methacrylate resin. If the Engineer does not review or approve the program submitted by the Contractor within the time specified and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the program for public safety, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

### Materials

The material used for treating the deck shall be a low odor, high molecular weight methacrylate resin. Prior to adding initiator, the resin shall have a maximum volatile content of 30 percent when tested in conformance with the requirements in ASTM Designation: D 2369, and shall conform to the following:

PROPERTY	TEST METHOD	REQUIREMENT
Viscosity mPa·s, maximum, (Brookfield RVT with UL adaptor, 50 RPM at 25°C)	ASTM D 2196	0.025
Specific Gravity minimum, at 25°C	ASTM D 1475	0.90
Flash Point °C, minimum	ASTM D 3278	82
Vapor Pressure mm Hg, maximum, at 25°C	ASTM D 323	1.0
Tack-free time minutes, maximum at 25°C	California Test 551	400
PCC Saturated Surface-Dry Bond Strength MPa, minimum at 24 hours and 21±1°C	California Test 551	3.5
* Test shall be performed prior to adding initiator.		

A Material Safety Data Sheet shall be furnished prior to use for each shipment of high molecular weight methacrylate resin.

The promoter and initiator, if supplied separately from the resin, shall not be mixed directly with each other. Containers of promoters and initiators shall not be stored together in a manner that will allow leakage or spillage from one to contact the containers or material of the other.

### Testing

The Contractor shall allow 14 days for sampling and testing by the Engineer of the high molecular weight methacrylate resin prior to proposed use.

The Contractor shall treat a test area within the project limits of approximately 50 m<sup>2</sup> at a location approved by the Engineer. Conditions during the test treatment shall be similar to those expected on the deck. Equipment used in the test shall be similar to those used for the deck treating operations. If the test area is on the traveled way, traffic shall not be allowed on the treated test area until (1) the treated surface is tack free (non-oily), (2) the sand cover adheres sufficiently to resist brushing by hand, and (3) the coefficient of friction of the deck is at least 0.35 when tested in conformance with the requirements in California Test 342.

Should the above requirements for traffic use not be met, the Contractor shall suspend treating of bridge decks until another test area is treated and complies with the requirements.

### **Construction**

Prior to deck treatment with methacrylate resin, the bridge deck surface shall be cleaned by abrasive blasting and all loose material shall be blown from visible cracks using high-pressure air. Concrete curing seals shall be cleaned from the deck surface to be treated, and the deck shall be dry when blast cleaning is performed. If the deck surface becomes contaminated at any time prior to placing the penetrating sealer, the deck surface shall be cleaned by abrasive blasting.

Equipment shall be fitted with suitable traps, filters, drip pans, or other devices as necessary to prevent oil or other deleterious material from being deposited on the deck.

Where abrasive blasting is being performed within 3 m of a lane occupied by public traffic, the residue including dust shall be removed immediately after contact between the abrasive and the surface being treated. The removal shall be by a vacuum attachment operating concurrently with the abrasive blasting operation.

The relative humidity shall be less than 90 percent at time of treatment.

A compatible promoter/initiator system shall be capable of providing a resin gel time of not less than 40 minutes nor more than 1.5 hours at the temperature of application. Gel time shall be adjusted to compensate for the changes in temperature throughout treatment application.

The quantity of resin mixed with promoter and initiator shall be limited to 20 L at a time for manual application.

Machine application of the resin shall be performed by using a two-part resin system using a promoted resin for one part and an initiated resin for the other part. This two-part resin system shall be combined at equal volumes to the spray bars through separate positive displacement pumps. Combining of the 2 components shall be by either static in-line mixers or by external intersecting spray fans. The pump pressure at the spray bars shall not be great enough to cause appreciable atomization of the resin. Compressed air shall not be used to produce the spray. A shroud shall be used to enclose the spray bar apparatus. Hand held spray apparatus shall not be used.

The Contractor shall allow methacrylate resin to be applied only to the specified area. Barrier rails, joints, and drainage facilities shall be adequately protected to prevent contamination by the treatment material. Contaminated items shall be repaired at the Contractor's expense.

The prepared area shall be dry and the surface temperature shall be less than or equal to 38°C when the resin is applied. The rate of application of promoted/initiated resin shall be approximately 2.5 square meters per liter, ± 0.1 square meter per liter.

The deck surfaces to be treated shall be flooded with resin, allowing penetration into the concrete and filling of all cracks. The treatment shall be applied within 5 minutes after complete mixing. A significant increase in viscosity shall be cause for rejection. Excess material shall be redistributed by squeegees or brooms within 10 minutes after application.

After the resin has been applied, at least 20 minutes shall elapse before applying sand. The sand shall be commercial quality dry blast sand. Ninety-five percent of the sand shall pass the 2.36-mm sieve, and 95 percent shall be retained on the 850-µm sieve. The sand shall be applied at a rate of one kilogram per square meter, ± 0.1 kilogram per square meter.

Excess sand shall be removed from the deck surface by vacuuming or sweeping prior to opening to traffic.

Traffic shall not be allowed on the treated area until (1) the treated surface is tack free (non-oily), (2) the sand cover adheres sufficiently to resist brushing by hand, and (3) the coefficient of friction of the deck is at least 0.35 when tested in conformance with the requirements in California Test 342.

### **MEASUREMENT AND PAYMENT**

Measurement and payment for concrete in structures shall conform to the provisions in Section 51-1.22, "Measurement," and Section 51-1.23, "Payment," of the Standard Specifications and these special provisions.

Full compensation for roughening existing concrete surfaces to a full amplitude of approximately 6 mm, where shown on the plans, shall be considered as included in the contract price paid per cubic meter for structural concrete, bridge and no separate payment will be made therefor.

Full compensation for deck crack treatment shall be considered as included in the contract price paid per cubic meter for structural concrete, bridge and no additional compensation will be allowed therefor.

Structural concrete, barrier slab will be measured and paid for in conformance with the provisions in Section 51-1.22, "Measurement," and Section 51-1.23, "Payment," of the Standard Specifications and these special provisions.

Full compensation for furnishing and placing steel components of abutment ties including plates, nuts, washers and rods shall be considered as included in the contract price paid per cubic meter for structural concrete, barrier slab and no separate payment will be made therefore.

Full compensation for drilling and bonding of abutment tie rods shall be considered as included in the contract price paid per cubic meter for structural concrete, barrier slab and no separate payment will be made therefor.

Full compensation for furnishing and installing building paper, PVC conduit, and Type AL joint seals shall be considered as included in the contract price paid per cubic meter for structural concrete, barrier slab and no additional compensation will be allowed therefor.

Placement of asphalt concrete and portland cement concrete on the existing bridge deck and proposed barrier slab where existing pavement is excavated for constructing the proposed structure will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

### **10-1.33 PAVING NOTCH EXTENSION**

This work shall consist of extending existing paving notches in conformance with the details shown on the plans and these special provisions.

Concrete for the paving notch extensions shall conform to the provisions for structure approach slab concrete of these special provisions.

At least 12 hours shall elapse between the time of placing concrete for the paving notch extension and placing concrete for the structure approach slab.

The construction joint between the paving notch extension and the existing abutment shall conform to the provisions for horizontal construction joints in Section 51-1.13, "Bonding," of the Standard Specifications. Concrete shall be placed in the spalled portions of the existing paving notch concurrently with the concrete for the paving notch extension.

Attention is directed to "Reinforcement" of these special provisions.

Structure excavation and backfill shall conform to the provisions in Section 19-3, "Structure Excavation and Backfill," of the Standard Specifications, except for payment.

Drilling of holes and bonding of reinforcing steel dowels shall conform to the provisions for drilling and bonding dowels in Section 83-2.02D(1), "General," of the Standard Specifications. If reinforcement is encountered during drilling before the specified depth is attained, the Engineer shall be notified. Unless the Engineer approves coring through the reinforcement, the hole will be rejected and a new hole, in which reinforcement is not encountered, shall be drilled adjacent to the rejected hole to the depth shown on the plans.

The quantity of concrete for paving notch extension will be measured by the cubic meter as determined in conformance with the dimensions shown on the plans or other dimensions that may be ordered in writing by the Engineer.

The contract price paid per cubic meter for paving notch extension shall include full compensation for furnishing all labor, materials (including concrete for the paving notch spalled areas), tools, equipment, and incidentals, and for doing all the work involved in constructing the paving notch extension, complete in place, including structure excavation and backfill, reinforcement, and drilling and bonding dowels, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **10-1.34 SOUND WALL**

This work shall consist of constructing sound walls of masonry block. Sound walls shall be supported on concrete barriers, retaining walls, piles, or pile caps as shown on the plans.

Attention is directed to "Reconstruct Property Side Yard Walls or Fences" of these special provisions.

The Contractor shall submit 2 sets of elevation and plan layout drawings to the Engineer, as provided in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The drawings shall be to scale and shall show the proposed top and bottom elevation lines. The top and bottom elevation lines shown on the plans are minimum and shall be fully contained in the proposed layout drawings. The drawings shall include, within the limits shown on the plans, the panel sizes, pile spacing, post spacing, footing steps, aesthetic features, locations of expansion joints, and access gates. The Contractor shall allow 2 weeks after complete drawings are submitted for review.

#### **SOUND WALL (MASONRY BLOCK), SOUND WALL (RETAINING WALL) (MASONRY BLOCK), AND SOUND WALL (BARRIER) (MASONRY BLOCK)**

Sound wall (masonry block), sound wall (retaining wall) (masonry block), and sound wall (barrier) (masonry block), consisting of a reinforced hollow unit masonry block stem, shall be constructed in conformance with the provisions in Sections 19, "Earthwork," 52, "Reinforcement," and 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions.

Sound wall masonry unit stems shall be constructed with joints of portland cement mortar. Wall stems shall be constructed with hand laid block. Wall stems shall not be constructed with preassembled panels.

Concrete for sound wallpile caps if required, shall be minor concrete.

Concrete masonry units shall be hollow, load bearing, conforming to the requirements in ASTM Designation: C 90, medium weight classification, Type II. Standard or open end units may be used. Open end units, if used, shall not reduce the spacing of the bar reinforcement as shown on the plans.

The masonry units shall be nominal size and texture and of uniform color. The color shall be tan, selected from the manufacturer's standards.

When high strength concrete masonry units with  $f_m=18.62$  MPa are shown on the plans, the high strength masonry units shall have a minimum compressive strength of 26 MPa based on net area. Each high strength concrete masonry unit shall be identified with a groove embedded in an interior corner. The groove shall extend from a mortar surface for a length of about 50 mm and shall have a depth of about 5 mm.

Expansion joint filler shall conform to the requirements in ASTM Designation: D 1751 or ASTM Designation: D 2000 2AA-805.

Portland cement mortar shall be colored to match the units. Coloring shall be chemically inert, fade resistant mineral oxide or synthetic type.

Portland cement for wall stems shall conform to the provisions in Section 90-2.01, "Portland Cement," of the Standard Specifications.

Hydrated lime shall conform to the requirements in ASTM Designation: C 207, Type S.

Mortar sand shall be commercial quality.

Mortar for laying masonry units shall consist, by volume, of one part portland cement, 0 to 0.5 part hydrated lime, and 2.25 to 3 parts mortar sand. Sufficient water shall be added to make a workable mortar. Each batch of mortar shall be accurately measured and thoroughly mixed. Mortar shall be freshly mixed as required. Mortar shall not be retempered more than one hour after mixing.

Prepackaged mortar materials and mortar containing admixtures may be used when approved in writing by the Engineer, provided the mortar shall not contain more than 0.05 percent soluble chlorides when tested in conformance with California Test 422 nor more than 0.25 percent soluble sulfates, as  $SO_4$ , when tested in conformance with California Test 417.

Prior to laying masonry units using prepackaged mortar materials or mortar containing admixtures, the Contractor shall submit to the Engineer the proposed sources of the materials together with test data from an independent testing laboratory for mortar tested in conformance with California Test 551. The test data shall be from specimens having a moist cure, except, the sample shall not be immersed in lime water. The average 28-day compressive strength of the mortar shall be not less than 18.62 MPa.

Aggregate for grout used to fill masonry units shall consist of fine aggregate and coarse aggregate conforming to the provisions in Section 90-2.02, "Aggregates," of the Standard Specifications. At least 20 percent of the aggregate shall be coarse aggregate. The Contractor shall determine the grading except that 100 percent of the combined grading shall pass the 12.5-mm sieve.

At the option of the Contractor, grout for filling masonry units may be proportioned either by volume or mass. Grout shall contain only enough water to cause the grout to flow and fill the voids without segregation. The maximum amount of free water shall not exceed 0.7 times the weight of the cement for regular strength masonry. The maximum amount of free water shall not exceed 0.6 times the mass of the cement for high strength masonry.

Grout proportioned by volume for regular strength masonry shall consist of at least one part portland cement and 4.5 parts aggregate. Grout proportioned by volume for high strength masonry shall consist of at least one part portland cement and 3.5 parts aggregate. Aggregate volumes shall be based on a loose, air-dry condition.

Grout proportioned by mass for regular strength masonry shall contain not less than 325 kilograms of portland cement per cubic meter. Grout proportioned by mass for high strength masonry shall contain not less than 400 kilograms of portland cement per cubic meter.

Reinforced concrete masonry unit wall stems shall be constructed with portland cement mortar joints in conformance with the following:

- A. Concrete masonry unit construction shall be true and plumb in the lateral direction and shall conform to the grade shown on the plans in the longitudinal direction. Bond beam units or recesses for horizontal reinforcement shall be provided.
- B. Mortar joints shall be approximately 10 mm wide. Walls and cross webs forming cells to be filled with grout shall be full bedded in mortar to prevent leakage of grout. All head and bed joints shall be solidly filled with mortar for a distance in from the face of the wall or unit not less than the thickness of the longitudinal face shells. Head joints shall be shoved tight.
- C. Mortared joints around cells to be filled shall be placed so as to preserve the unobstructed vertical continuity of the grout filling. Any overhanging mortar or other obstruction or debris shall be removed from the inside of such cells.

- D. Reinforcement shall be securely held in position at top and bottom with either wire ties or spacing devices and at intervals not exceeding 192 bar diameters prior to placing any grout. Wire shall be 16-gage (1.57 mm) or heavier. Wooden, aluminum, or plastic spacing devices shall not be used.
- E. Splices in vertical reinforcement shall be made only at the locations shown on the plans.
- F. Only those cells containing reinforcement shall be filled solidly with grout. All grout in the cells shall be consolidated at the time of placement by vibrating, and reconsolidated after excess moisture has been absorbed, but before plasticity is lost. Grout shall not be sliced with a trowel.
- G. Walls shall be constructed in 1.2-m maximum height lifts. Grouting of each lift shall be completed before beginning masonry unit construction for the next lift. The top course of each lift shall consist of a bond beam.
- H. A construction joint shall be constructed at the top of the top course to permit placement of the mortar cap. The mix design for the mortar cap shall be as approved by the Engineer.
- I. Construction joints shall be made when the placing of grout, in grout filled cells, is stopped for more than one hour. The construction joint shall be approximately 12 mm below the top of the last course filled with grout.
- J. Bond beams shall be continuous. The top of unfilled cells under horizontal bond beams shall be covered with metal or plastic lath.
- K. When fresh masonry joins masonry that is partially or totally set, the contact surface shall be cleaned, roughened, and lightly wetted.
- L. Surfaces of concrete on which the masonry walls are to be constructed shall be roughened and cleaned, exposing the aggregate, and shall be flushed with water and allowed to dry to a surface dry condition immediately prior to laying the masonry units.
- M. Where cutting of masonry units is necessary, all cuts shall be made with a masonry saw to neat and true lines. Masonry units with cracking or chipping of the finished exposed surfaces will not be acceptable.
- N. Masonry shall be protected in the same manner specified for concrete structures in Section 90-8, "Protecting Concrete," of the Standard Specifications and these special provisions.
- O. During erection, all cells shall be kept dry in inclement weather by covering partially completed walls. The covering shall be waterproof fabric, plastic or paper sheeting, or other approved material. Wooden boards and planks shall not be used as covering materials. The covering shall extend down each side of masonry walls approximately 0.6-m.
- P. Splashes, stains or spots on the exposed faces of the wall shall be removed.

#### **ACCESS GATES**

Access gates shall conform to the details shown on the plans and these special provisions.

Timber members shall be tongue and groove Douglas fir sub-flooring free of knotholes. The location of knots of adjoining boards shall be staggered. The construction of the gate shall be with the tongue placed in the up position. The tongue of the top board and the groove of the bottom board shall be removed.

Timber members, steel frames, channels, anchorage devices, mounting hardware, gate rollers, corrugated steel pipe, nylon washers, and neoprene tubing shall be of commercial quality.

The 25-mm round ladder rungs with non-skid surface shall consist of No. 25 deformed, diamond pattern, bar reinforcing steel of commercial quality.

Gate rollers shall be rigid casters with self-lubricating bearings and hard rubber wheels.

All metal parts and hardware shall be hot-dip galvanized.

Timber surfaces of the access gates shall be primed and then stained with 2 coats of stain to match the adjacent sound wall. Primer and stain shall be of the top grade primer and stain from an established manufacturer. An established manufacturer is one who has manufactured industrial paints and stains to meet custom specifications for at least 10 years.

Where the back side of the masonry wall is to be split faced, or rough surface blocks, the bond beam above the gate opening upon which the upper gate guide is to be mounted shall have smooth sided blocks.

Material from excavation may be used for backfill outside of the pipe landings. Aggregate filling inside the pipe landings shall be a coarse concrete aggregate of commercial quality. Compacting of the aggregate will not be required.

#### **MEASUREMENT AND PAYMENT**

Sound walls of the types designated in the Engineer's Estimate will be measured by the square meter of wall projected on a vertical plane between the elevation lines shown on the plans or for walls supported on barriers from the top of the barrier to the upper elevation line and length of wall (including the exposed posts, back up wall for access openings, and access gates).

The contract prices paid per square meter for sound walls of the types designated in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the sound wall, complete in place, including all supports (except retaining walls, barriers, and barrier supports),

anchorage, access gates, ladders, corrugated steel pipe landings, excavation, backfill, reinforcement and grade beams, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer. Retaining walls, concrete barrier, and barrier supports supporting sound walls will be measured and paid for as separate items of work.

#### **10-1.35 DRILL AND BOND DOWEL (EPOXY CARTRIDGE)**

Drilling and bonding dowels with epoxy cartridges shall conform to the details shown on the plans and these special provisions.

Reinforcing steel dowels shall conform to the provisions in "Reinforcement" of these special provisions.

Threaded rods used as dowels shall conform to the provisions in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications. The threaded rods shall be installed in conformance with these requirements for dowels specified herein.

The Contractor shall select an epoxy cartridge system which has passed the testing requirements of the International Conference of Building Officials (ICBO) document - AC58 and additional test requirements as specified in the Caltrans Augmentation/Revisions to ICBO AC58. Testing shall be performed by an independent testing facility and the results will be reviewed and approved by the Transportation Laboratory. The Caltrans Augmentation/Revisions to ICBO AC58 document may be obtained by contacting the Transportation Laboratory, telephone: (916) 227-7000.

The epoxy cartridge system used shall be appropriate for the ambient concrete temperature and installation conditions at the time of installation in conformance with the manufacturer's specifications.

Epoxy cartridges shall be accompanied by a Certificate of Compliance as provided in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The certificate shall state that the material complies in all respects to the requirements of ICBO AC58 and Caltrans Augmentation/Revisions to ICBO AC58.

Each epoxy cartridge shall be clearly and permanently marked with the manufacturer's name, model number of the epoxy cartridge system, manufacturing date, and lot number. Each carton of epoxy cartridges shall contain the manufacturer's recommended installation procedures, minimum cure time, and such warning or precautions concerning the contents as may be required by State or Federal Laws and Regulations.

The holes shall be drilled by methods that will not shatter or damage the concrete adjacent to the holes. If reinforcement is encountered during drilling, before the specified depth is attained, the Engineer shall be notified. Unless the Engineer approves, in writing, coring through the reinforcement, the hole will be rejected and a new hole, in which reinforcement is not encountered, shall be drilled adjacent to the rejected hole to the depth recommended by the manufacturer.

The drilled holes shall be cleaned in conformance with the manufacturer's instructions and shall be dry at the time of placing the epoxy cartridge bonding material and the steel dowels. The bonding material shall be a 2-component epoxy system contained in a cartridge having 2 separate chambers and shall be inserted into the hole using a dispensing gun and replaceable mixing nozzle approved by the manufacturer. Unless otherwise specified, the depth of hole and the installation procedure shall be as recommended by the manufacturer. A copy of the manufacturer's recommended installation procedure shall be provided to the Engineer at least 2 days prior to the start of work.

Immediately after inserting the dowels into the epoxy, the dowels shall be supported as necessary to prevent movement during curing and shall remain undisturbed until the epoxy has cured a minimum time as specified by the manufacturer. Dowels that are improperly bonded, as determined by the Engineer, will be rejected. Adjacent new holes shall be drilled, and new dowels shall be placed and securely bonded to the concrete. All work necessary to correct improperly bonded dowels shall be performed at the Contractor's expense.

Unless otherwise provided, dowels to be bonded into drilled holes will be measured and paid for as bar reinforcing steel (bridge).

Unless otherwise provided, drilling and bonding dowels with epoxy cartridges will be measured and paid for by the unit as drill and bond dowel (epoxy cartridge). The number of units to be paid for will be determined from actual count of the completed units in place.

The contract unit price paid for drill and bond dowel (epoxy cartridge) shall include full compensation for furnishing all labor, materials (except dowels), tools, equipment, and incidentals, and for doing all the work involved in drilling the holes and bonding dowels with epoxy cartridges, including coring through reinforcement when approved by the Engineer, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

#### **10-1.36 DRILL AND BOND DOWELS**

Drilling and bonding dowels shall conform to the details shown on the plans, the provisions in Section 83-2.02D(1), "General," of the Standard Specifications, and these special provisions.

Dowels shall conform to the provisions for bar reinforcement in "Reinforcement" of these special provisions.

If reinforcement is encountered during drilling before the specified depth is attained, the Engineer shall be notified. Unless the Engineer approves coring through the reinforcement, the hole will be rejected and a new hole, in which reinforcement is not encountered, shall be drilled adjacent to the rejected hole to the depth shown on the plans.

Unless otherwise provided, dowels to be bonded into drilled holes will be paid for as bar reinforcing steel (bridge).

Unless otherwise provided, drilling and bonding dowels will be measured and paid for by the meter determined by the number and the required depth of holes as shown on the plans or as ordered by the Engineer.

The contract price paid per meter for drill and bond dowel shall include full compensation for furnishing all labor, materials (except reinforcing steel dowels), tools, equipment, and incidentals, and for doing all the work involved in drilling the holes, including coring through reinforcement when approved by the Engineer, and bonding the dowels, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

#### **10-1.37 SEALING JOINTS**

Joints in concrete bridge decks and joints between concrete structures and concrete approach slabs shall be sealed in conformance with the details shown on the plans, the provisions in Section 51, "Concrete Structures," of the Standard Specifications, and these special provisions.

Where polyurethane seals are shown on the plans, a silicone sealant conforming to the provisions in Section 51-1.12F, "Sealed Joints," of the Standard Specifications may be used.

When ordered by the Engineer, a joint seal larger than called for by the Movement Rating shown on the plans shall be furnished and installed. Payment to the Contractor for furnishing the larger seal and for saw cutting the increment of additional depth of groove required will be determined as provided in Section 4-1.03, "Changes," of the Standard Specifications.

#### **10-1.38 REINFORCEMENT**

Reinforcement shall conform to the provisions in Section 52, "Reinforcement," of the Standard Specifications and these special provisions.

##### **ULTIMATE BUTT SPLICES**

Ultimate butt splices shall be either welded or mechanical splices, shall be used at the locations shown on the plans, and shall conform to the provisions in Section 52, "Reinforcement," of the Standard Specifications and these special provisions.

##### **General Requirements**

The Contractor shall designate in writing an ultimate butt splicing Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for 1) the quality of all ultimate butt splicing including the inspection of materials and workmanship performed by the Contractor and all subcontractors; and 2) submitting, receiving, and approving all correspondence, required submittals, and reports regarding ultimate butt splicing to and from the Engineer.

The QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

The length of any type of ultimate mechanical butt splice shall not exceed 10 times the bar diameter of the larger bar to be spliced.

All ultimate prejob, production, and job control sample splices shall be 1) a minimum length of 1.5 meters for reinforcing bars No. 25 or smaller and 2 meters for reinforcing bars No. 29 or larger, with the splice located at mid-point, and 2) suitably identified prior to shipment with weatherproof markings that do not interfere with the Engineer's tamper-proof markings or seals. Any splice that shows signs of tampering will be rejected.

A minimum of one control bar shall be removed from the same bar as, and adjacent to, all ultimate prejob, production, and job control sample splices. Control bars shall be 1) a minimum length of one meter for reinforcing bars No. 25 or smaller and 1.5 meters for reinforcing bars No. 29 or larger, and 2) suitably identified prior to shipment with weatherproof markings that do not interfere with the Engineer's tamper-proof markings or seals. The portion of adjacent bar remaining in the work shall also be identified with weatherproof markings that correspond to its adjacent control bar.

Shorter length sample splice and control bars may be furnished if approved in writing by the Engineer.

Each sample splice and its associated control bar shall be identified and marked as a set. Each set shall be identified as representing a prejob, production, or job control sample splice.

The portion of hoop reinforcing bar, removed to obtain a sample splice and control bar, shall be replaced using a prequalified ultimate mechanical butt splice, or the hoop shall be replaced in kind.

Reinforcing bars, other than hoops, from which sample splices are removed, shall be repaired using ultimate mechanical butt splices conforming to the provisions in "Prejob Test Requirements for Ultimate Butt Splices" specified herein, or the bars shall be replaced in kind. These bars shall be repaired or replaced such that no splices are located in the "No Splice Zone" shown on the plans.

Section 52-1.08E, "Job Control Tests," of the Standard Specifications shall not apply.

The provisions for total slip shall not apply to any ultimate splices that are welded or that are used on hoops.

The independent qualified testing laboratory used to perform the testing of all ultimate butt sample splices and control bars shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors who will provide other services or materials for the project, and shall have the following:

- A. Proper facilities, including a tensile testing machine capable of breaking the largest size of reinforcing bar to be tested.
- B. A device for measuring the total slip of the reinforcing bars across the splice to the nearest 25  $\mu\text{m}$ , that, when placed parallel to the longitudinal axis of the bar is able to simultaneously measure movement across the splice, at 2 locations, 180 degrees apart.
- C. Operators who have received formal training for performing the testing requirements of ASTM Designation: A 370/A 370M and California Test 670.
- D. A record of annual calibration of testing equipment performed by an independent third party that has 1) standards that are traceable to the National Institute of Standards and Technology, and 2) a formal reporting procedure, including published test forms.

#### **Ultimate Butt Splice Test Criteria**

Ultimate prejob, production, and job control sample splices shall be tensile tested in conformance with the requirements described in ASTM Designation: A 370/A 370M and California Test 670.

Ultimate prejob and production sample splices shall rupture in the reinforcing bar either: 1) outside of the affected zone or 2) within the affected zone, provided that the sample has achieved at least 95 percent of the ultimate tensile strength of the control bar associated with the sample. In addition, necking of the bar shall be visibly evident at rupture regardless of whether the bar breaks inside or outside the affected zone.

The affected zone is the portion of the reinforcing bar where any properties of the bar, including the physical, metallurgical, or material characteristics, have been altered by fabrication or installation of the splice.

The ultimate tensile strength of each control bar shall be determined by tensile testing the bar to rupture and shall be determined for all control bars, regardless of where each sample splice ruptures. If 2 control bars are tested for one sample splice, the bar with the lower ultimate tensile strength shall be considered the control bar.

Testing to determine the minimum tensile strength, in conformance with the provisions in the ninth paragraph of Section 52-1.08, "Splicing," of the Standard Specifications, will not be required.

#### **Prejob Test Requirements for Ultimate Butt Splices**

Prior to use in the work, all ultimate butt splices shall conform to the following prejob test requirements:

- A. Eight prejob sample splices for each bar size of each splice type including ultimate mechanical butt splices, ultimate complete joint penetration butt welded splices, and ultimate resistance butt welded splices, that will be used in the work, shall be fabricated by the Contractor. For deformation-dependent types of couplers, 8 sample prejob splices shall also be fabricated for each reinforcing bar size and deformation pattern that will be used in the work.
- B. The sample splices shall be fabricated using the same splice materials, position, operators, location, and equipment, and following the same procedures as will be used to make the splices in the work. In addition, for resistance butt welded splices, the sample splices shall have the weld flash removed and be epoxy-coated as specified elsewhere in these special provisions.
- C. At the option of the Contractor, operator qualification tests may be performed simultaneously with the preparation of prejob sample splices.
- D. If different diameters of hoops are shown on the plans, prejob sample splices, as described above, will only be required for the smallest hoop diameter. In addition, these splices shall be fabricated using the same radius as shown on the plans for these hoops.
- E. Unless otherwise directed in writing by the Engineer, 4 prejob sample splices and control bar sets shall be shipped to the Transportation Laboratory and the remaining 4 sets shall be tested by the Contractor's independent qualified testing laboratory.

- F. Each group of 4 sets from a prejob test shall be securely bundled together and identified by location and contract number with weatherproof markings prior to shipment. Bundles containing fewer than 4 sets will not be tested by the Transportation Laboratory, nor shall they be tested by the independent laboratory.
- G. All 8 sample splices from each prejob test shall conform to the provisions in "Ultimate Butt Splice Test Criteria" specified herein.
- H. Prior to performing any tensile tests on prejob test sample splices, one of the 4 samples shall be tested for, and shall conform to, the provisions for total slip. Should this sample not meet these requirements, one retest, in which the 3 remaining samples are tested for total slip, will be allowed. All 3 of these remaining samples tested shall conform to the aforementioned slip requirements.
- I. For each bundle of 4 sets, a Prejob Test Report shall be prepared by the independent testing laboratory performing the testing. The report shall 1) be signed by an engineer who represents the laboratory and is registered as a Civil Engineer in the State of California; 2) include, as a minimum, the following information for each set: contract number, bridge number, bar size, type of splice, length of mechanical splice, physical condition of test sample splice and control bar, any notable defects, limits of affected zone, total measured slip, location of visible necking area, ultimate strength of each splice, ultimate strength and 95 percent of this ultimate strength for each control bar, and a comparison between 95 percent of the ultimate strength of each control bar and the ultimate strength of its associated splice; and 3) be submitted to the QCM for review and approval, and then to the Engineer.
- J. Test results for each bundle of 4 sets will be reported in writing to the Contractor within 10 working days after receipt of the bundle by the Transportation Laboratory. In the event that more than one bundle is received on the same day, 2 additional working days shall be allowed for providing test results for each additional bundle received. A test report will be made for each bundle received.
- K. Should the Engineer fail to provide the test results within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in providing the test results, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

#### **Production Test Requirements for Ultimate Butt Splices**

Production tests shall be performed for all ultimate butt splices used in the work. A production test shall consist of 4 sets of sample splices and control bars removed from each lot of completed splices, except when quality assurance tests are performed.

A lot of ultimate butt splices is defined as 1) 150, or fraction thereof, of the same type of ultimate mechanical butt splices used for each bar size and each bar deformation pattern that is used in the work or 2) 150, or fraction thereof, of ultimate complete joint penetration butt welded splices, or ultimate resistance butt welded splices for each bar size used in the work. If different diameters of hoop reinforcement are shown on the plans, separate lots shall be used for each different hoop diameter.

After all splices in a lot have been completed and the bars have been epoxy-coated, the QCM shall notify the Engineer in writing that all couplers in this lot conform to the specifications and are ready for testing. The sample splices will either be selected by the Engineer at the job site or a fabrication facility, provided the facility is located within an 80-km radius of the jobsite.

After notification has been received, the Engineer will randomly select the 4 sample splices to be removed from the lot and place tamper-proof markings or seals on them. The Contractor or QCM shall select the adjacent control bar for each sample splice bar, and the Engineer will place tamper-proof markings or seals on them. These ultimate production sample splices and control bars shall be removed by the Contractor, and tested by an independent qualified testing laboratory, in the presence of either the Engineer or the Engineer's authorized representative.

The Engineer or the Engineer's authorized representative will be at the independent qualified testing laboratory within a maximum of 5 working days after receiving written notification that the samples are at the laboratory and ready for testing. Should the Engineer or the Engineer's authorized representative fail to be at the laboratory within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of this action, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

A sample splice or control bar from any set will be rejected if any tamper-proof marking or seal is disturbed prior to testing.

The 4 sets from each production test shall be securely bundled together and identified with a completed sample identification card prior to shipment to the independent laboratory. The card will be furnished by the Engineer. Bundles of samples containing fewer than 4 sets of splices shall not be tested.

A Production Test Report for all testing performed on each lot shall be prepared by the independent testing laboratory performing the testing and submitted to the QCM for review and approval. The report shall be signed by an engineer who

represents the laboratory and is registered as a Civil Engineer in the State of California. The report shall include, as a minimum, the following information for each set: contract number, bridge number, lot number and location, bar size, type of splice, length of mechanical splice, physical condition of test sample splice and control bar, any notable defects, limits of affected zone, total measured slip, location of visible necking area, ultimate strength of each splice, ultimate strength and 95 percent of this ultimate strength for each control bar, and a comparison between 95 percent of the ultimate strength of each control bar and the ultimate strength of its associated splice.

The QCM must review, approve, and forward each Production Test Report to the Engineer for review before any splices represented by the report are encased in concrete. The Engineer shall have 3 working days to review each Production Test Report and respond in writing after a complete report has been received. Should the Contractor elect to encase any splices prior to receiving notification from the Engineer, it is expressly understood that the Contractor will not be relieved of the Contractor's responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Any material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase any splices pending notification by the Engineer, and should the Engineer fail to complete the review and provide notification within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in notification, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Prior to performing any tensile tests on production test sample splices, one of the 4 samples shall be tested for, and shall conform to, the provisions for total slip. Should this sample not meet these requirements, one retest, in which the 3 remaining samples are tested for total slip, will be allowed. Should any of the 3 remaining samples not conform to these requirements, all splices in the lot represented by this production test will be rejected.

If 3 or more sample splices from any production test conform to the provisions in "Ultimate Butt Splice Test Criteria" specified herein, all splices in the lot represented by this production test will be considered acceptable.

Should only 2 sample splices from any production test conform to the provisions in "Ultimate Butt Splice Test Criteria" specified herein, one additional production test shall be performed on the same lot of splices. Should any of the 4 sample splices from this additional test fail to conform to these provisions, all splices in the lot represented by these production tests will be rejected.

If only one sample splice from any production test conforms to the provisions in "Ultimate Butt Splice Test Criteria" specified herein, all splices in the lot represented by this production test will be rejected.

If a production test for any lot fails, the Contractor will be required to repair or replace all reinforcing bars from which sample splices were removed, complete in place, before the Engineer selects any additional splices from this lot for further testing.

Whenever any lot of ultimate butt splices is rejected, additional ultimate butt splices shall not be used in the work until 1) the QCM performs a complete review of the Contractor's quality control process for these splices, 2) a written report is submitted to the Engineer describing the cause of failure for the splices in this lot and provisions for correcting these failures in future lots, and 3) the Engineer has provided the Contractor with written notification that the report is acceptable. The Engineer shall have 3 working days after receipt of the report to provide notification to the Contractor. Should the Engineer not provide notification within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of this action, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Production tests will not be required on any repaired splice from a lot, regardless of the type of prequalified ultimate mechanical butt splice used to make the repair.

Should an additional production test be required, the Engineer may select any repaired splice for use in the additional production test.

### **Quality Assurance Test Requirements for Ultimate Butt Splices**

For the first production test performed, and for at least one, randomly selected by the Engineer, of every 5 additional production tests, or portion thereof, performed thereafter, the Contractor shall concurrently prepare 4 additional ultimate job control sample splices along with associated control bars. These ultimate job control samples shall be prepared in the same manner as specified herein for ultimate prejob sample splices and control bars.

Each time 4 additional ultimate job control sample splices are prepared, 2 of these job control sample splice and associated control bar sets and 2 of the production sample splice and associated control bar sets, together, shall conform to the requirements for ultimate production sample splices in "Production Test Requirements for Ultimate Butt Splices" specified herein.

The 2 remaining job control sample splice and associated control bar sets, along with the 2 remaining production sample splice and associated control bar sets shall be shipped, unless otherwise directed in writing by the Engineer, to the Transportation Laboratory for quality assurance testing. The 4 sets shall be securely bundled together and identified by

location and contract number with weatherproof markings prior to shipment. Bundles containing fewer than 4 sets will not be tested.

Quality assurance testing will be performed in conformance with the requirements for ultimate production sample splices in "Production Test Requirements for Ultimate Butt Splices" specified herein.

Test results for each bundle of 4 sets will be reported in writing to the Contractor within 3 working days after receipt of the bundle by Transportation Laboratory. In the event that more than one bundle is received on the same day, 2 additional working days shall be allowed for providing test results for each additional bundle received. A test report will be made for each bundle received. Should the Contractor elect to encase any splices prior to receiving notification from the Engineer, it is expressly understood that the Contractor will not be relieved of the Contractor's responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Any material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase any splices pending notification by the Engineer, and should the Engineer fail to complete the review and provide notification within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in notification, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

### **SERVICE BUTT SPLICES**

Service butt splices shall be used at the locations shown on the plans, and shall conform to the provisions in Section 52, "Reinforcement," of the Standard Specifications and these special provisions. Service butt splices shall be either welded or mechanical splices. Unless otherwise specified, mechanical lap splices shall be treated as service butt splices as specified herein.

#### **General Requirements**

The Contractor shall designate in writing a service butt splicing Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for 1) the quality of all service butt splicing including the inspection of materials and workmanship performed by the Contractor and all subcontractors; and 2) submitting, receiving, and approving all correspondence, required submittals, and reports regarding service butt splicing to and from the Engineer.

The QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

All service prejob and production sample splices shall be 1) a minimum length of 1.5 meters for reinforcing bars No. 25 or smaller, and 2 meters for reinforcing bars No. 29 or larger, with the splice located at mid-point; and 2) suitably identified prior to shipment with weatherproof markings that do not interfere with the Engineer's tamper-proof markings or seals. Any splice that shows signs of tampering will be rejected.

Shorter length sample splice bars may be furnished if approved in writing by the Engineer.

Each set shall be identified as representing either a prejob or production test sample splice.

Section 52-1.08E, "Job Control Tests," of the Standard Specifications shall not apply.

When joining new reinforcing bars to existing reinforcement, the prejob sample splices shall be made using only the deformation pattern of the new reinforcement to be joined.

The provisions for total slip shall not apply to any service splices that are welded.

The independent qualified testing laboratory used to perform the testing of all service butt sample splices shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors who will provide other services or materials for the project, and shall have the following:

- A. Proper facilities, including a tensile testing machine capable of breaking the largest size of reinforcing bar to be tested.
- B. A device for measuring the total slip of the reinforcing bars across the splice to the nearest 25  $\mu$ m, that, when placed parallel to the longitudinal axis of the bar is able to simultaneously measure movement across the splice, at 2 locations, 180 degrees apart.
- C. Operators who have received formal training for performing the testing requirements of ASTM Designation: A 370/A 370M and California Test 670.
- D. A record of annual calibration of testing equipment performed by an independent third party that has 1) standards that are traceable to the National Institute of Standards and Technology, and 2) a formal reporting procedure, including published test forms.

### **Service Butt Splice Test Criteria**

Service prejob sample splices and production sample splices shall be tensile tested in conformance with the requirements described in ASTM Designation: A 370/A 370M and California Test 670.

Service prejob sample splices and production sample splices shall develop a minimum tensile strength of not less than 550 Mpa.

### **Prejob Test Requirements for Service Butt Splices**

Prior to use in the work, all service butt splices shall conform to the following prejob test requirements:

- A. Four prejob sample splices for each bar size of each splice type including service mechanical butt splices, service complete joint penetration butt welded splices, and service resistance butt welded splices, that will be used in the work, shall be fabricated by the Contractor. For deformation-dependent types of couplers, 4 sample prejob splices shall also be fabricated for each reinforcing bar size and deformation pattern that will be used in the work.
- B. The sample splices shall be fabricated using the same splice materials, position, operators, location, and equipment, and following the same procedures as will be used to make the splices in the work. In addition, for resistance butt welded splices, the sample splices shall have the weld flash removed and be epoxy-coated as specified elsewhere in these special provisions.
- C. At the option of the Contractor, operator qualification tests may be performed simultaneously with the preparation of prejob sample splices.
- D. Unless otherwise directed in writing by the Engineer, the 4 sample splices shall be tested by the Contractor's independent qualified testing laboratory.
- E. Each group of 4 samples from a prejob test shall be securely bundled together and identified by location and contract number with weatherproof markings prior to shipment. Bundles containing fewer than 4 samples shall not be tested by the independent laboratory.
- F. All 4 sample splices from each prejob test shall conform to the provisions in "Service Butt Splice Test Criteria" specified herein.
- G. Prior to performing any tensile tests on prejob test sample splices, one of the 4 samples shall be tested for, and shall conform to, the provisions for total slip. Should this sample not meet these requirements, one retest, in which the 3 remaining samples are tested for total slip, will be allowed. All 3 of these remaining samples tested shall conform to the aforementioned slip requirements.
- H. For each bundle of 4 samples, a Prejob Test Report shall be prepared by the independent testing laboratory performing the testing. The report shall 1) be signed by an engineer who represents the laboratory and is registered as a Civil Engineer in the State of California; 2) include, as a minimum, the following information for each sample: contract number, bridge number, bar size, type of splice, length of mechanical splice, physical condition of test sample splice, any notable defects, total measured slip, and ultimate strength of each splice; and 3) be submitted to the QCM for review and approval, and then to the Engineer.

### **Production Test Requirements for Service Butt Splices**

Production tests shall be performed by the Contractor's independent laboratory for all service butt splices used in the work. Unless otherwise specified, a production test shall consist of 4 sample splices prepared for each lot of completed splices. The samples shall be prepared by the Contractor in the same manner as specified herein for service prejob sample splices, and then tested by the independent laboratory in the presence of either the Engineer or the Engineer's authorized representative.

A lot of service butt splices is defined as 1) 150, or fraction thereof, of the same type of service mechanical butt splices used for each bar size and each bar deformation pattern that is used in the work or 2) 150, or fraction thereof, of service complete joint penetration butt welded splices, or service resistance butt welded splices for each bar size used in the work.

The Engineer or the Engineer's authorized representative will be at the independent qualified testing laboratory within a maximum of 5 working days after receiving written notification that the samples are at the laboratory and ready for testing. Should the Engineer or the Engineer's authorized representative fail to be at the laboratory within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of this action, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The 4 samples from each production test shall be securely bundled together and identified with a completed sample identification card prior to shipment to the independent laboratory. The card will be furnished by the Engineer. Bundles of samples containing fewer than 4 samples of splices shall not be tested.

A Production Test Report for all testing performed on each lot shall be prepared by the independent testing laboratory performing the testing and submitted to the QCM for review and approval. The report shall be signed by an engineer who

represents the laboratory and is registered as a Civil Engineer in the State of California. The report shall include, as a minimum, the following information for each sample: contract number, bridge number, lot number and location, bar size, type of splice, length of mechanical splice, physical condition of test sample splice, any notable defects, total measured slip, ultimate strength of each splice.

The QCM must review, approve, and forward each Production Test Report to the Engineer for review before any splices represented by the report are encased in concrete. The Engineer shall have 3 working days to review each Production Test Report and respond in writing after a complete report has been received. Should the Contractor elect to encase any splices prior to receiving notification from the Engineer, it is expressly understood that the Contractor will not be relieved of the Contractor's responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Any material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase any splices pending notification by the Engineer, and should the Engineer fail to complete the review and provide notification within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in notification, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Prior to performing any tensile tests on production test sample splices, one of the 4 samples shall be tested for, and shall conform to, the provisions for total slip. Should this sample not meet the slip requirements, one retest, in which the 3 remaining samples are tested for total slip, will be allowed. Should any of the 3 remaining samples not conform to the slip requirements, all splices in the lot represented by this production test will be rejected.

If 3 or more sample splices from any production test conform to the provisions in "Service Butt Splice Test Criteria" specified herein, all splices in the lot represented by this production test will be considered acceptable, provided all 4 samples develop a minimum tensile strength of not less than 420 Mpa.

Should only 2 sample splices from any production test conform to the provisions in "Service Butt Splice Test Criteria" specified herein, one additional production test shall be performed on the same lot of splices. This additional production test shall consist of testing 4 samples splices that have been randomly selected by the Engineer and removed by the Contractor from the actual completed lot of splices. Should any of the 4 splices from this additional test fail to conform to these provisions or to develop a minimum tensile strength of not less than 550 Mpa, all splices in the lot represented by these production tests will be rejected.

If only one sample splice from any production test conforms to the provisions in "Service Butt Splice Test Criteria" specified herein, all splices in the lot represented by this production test will be rejected.

If a production test for any lot fails, the Contractor will be required to repair or replace all reinforcing bars from which sample splices were removed, complete in place, before the Engineer selects any additional splices from this lot for further testing.

Whenever any lot of service butt splices is rejected, additional service butt splices shall not be used in the work until 1) the QCM performs a complete review of the Contractor's quality control process for these splices, 2) a written report is submitted to the Engineer describing the cause of failure for the splices in this lot and provisions for correcting these failures in future lots, and 3) the Engineer has provided the Contractor with written notification that the report is acceptable. The Engineer shall have 3 working days after receipt of the report to provide notification to the Contractor. Should the Engineer not provide notification within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of this action, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

## **EPOXY-COATED REINFORCEMENT**

Epoxy-coated reinforcement shall be used at locations shown on the plans, and shall conform to the provision in Section 52-1.02B, "Epoxy-coated Reinforcement," of the Standard Specifications and these special provisions.

## **MEASUREMENT AND PAYMENT**

Measurement and payment for reinforcement in structures shall conform to the provisions in Section 52-1.10, "Measurement," and Section 52-1.11, "Payment," of the Standard Specifications and these special provisions.

Full compensation for conforming to the provisions of "Ultimate Butt Splices," of these special provisions shall be considered as included in the contract prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

Full compensation for conforming to the provisions of "Service Butt Splices," of these special provisions shall be considered as included in the contract prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

**10-1.39 WATERPROOFING**

Waterproofing shall conform to the provisions in Section 54, "Waterproofing," of the Standard Specifications and these special provisions.

At the option of the Contractor, a preformed membrane waterproofing system may be furnished and applied in lieu of the asphalt membrane waterproofing specified above. Preformed membrane waterproofing shall conform to these special provisions.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be furnished for the preformed membrane sheet. The Certificate of Compliance shall include the following information: (1) type of preformed membrane sheet, and (2) the conditioner or primer application rates.

The preformed membrane waterproofing system shall consist of an adhesive, conditioner or primer applied to a prepared surface; a preformed membrane sheet of rubberized asphalt or polymer modified bitumen; mastic or tape for sealing the edges of the sheet; and a protective covering over the sheet held by an adhesive.

The preformed membrane sheet shall be either permanently applied to a polyethylene film or reinforced with a polypropylene mesh fabric, polyester/polypropylene fabric or a fiberglass mesh fabric. The membrane sheet shall conform to the following requirements:

Property	Test	Requirement	
		Polyethylene Film	Fabric Reinforced
Tensile Strength (Minimum)(1)	ASTM D 882 (2)	3.5N/mm (3)	3.5N/mm (3)
Percent Elongation at break (Minimum) (4)	ASTM D 882 (2)	150 percent (3)	25 percent (3)
Pliability	ASTM D 146 (5)	No cracks	No cracks
Thickness (Minimum) (6)	-----	1.5 mm	1.5 mm
Rubberized Asphalt Softening Point (Minimum)	AASHTO T 53	74°C	74°C
Polymer Modified Bitumen Softening Point (Minimum)	AASHTO T 53	99°C	99°C

Notes:

- (1) Breaking factor in machine direction.
- (2) Method A, average 5 samples.
- (3) At 23°C ± 2°C
- (4) Machine direction.
- (5) 180-degree bend over a 25-mm mandrel at -120°C
- (6) Total thickness of preformed membrane sheet and polyethylene film or fabric reinforcement.

Adhesives, conditioners, primers, mastics and sealing tapes shall be manufactured for use with the respective preformed membrane sheet materials and shall be applied according to the manufacturer's recommendations.

The protective covering shall be 3-mm minimum thickness hardboard or other material that furnishes equivalent protection. Backfill material and equipment shall not cut, scratch, depress or cause any other damage to the preformed membrane.

Surfaces designated to receive preformed membrane waterproofing shall be thoroughly cleaned of dirt, dust, loose or unsound concrete, and other extraneous material and shall be free from fins, sharp edges, and protrusions that would, in the opinion of the Engineer, puncture or otherwise damage the membrane. Sharp corners to be covered shall be rounded (outside) or chamfered (inside).

Surfaces shall be dry when components of the preformed membrane waterproofing system are applied.

Preformed membrane waterproofing shall not be applied to any surface until the Contractor is prepared to follow its application with the placing of the protective covering and backfill within a sufficiently short time that the membrane will not be damaged by workers or equipment, exposure to weathering, or from any other cause. Damaged membrane or protective covering shall be repaired or replaced by the Contractor at the Contractor's expense.

All projecting pipe, conduits, sleeves or other facilities passing through the preformed membrane waterproofing shall be flashed with prefabricated or field-fabricated boots, fitted coverings or other devices as necessary to provide watertight construction.

All conditioner or primers shall be thoroughly mixed and continuously agitated during application. Conditioner, primers or adhesive shall be allowed to dry to a tack free condition prior to placing membrane sheets.

The surfaces shall be recoated if membrane sheets are not placed over primer, conditioner or adhesive within the time recommended by the manufacturer.

The preformed membrane sheet shall not be applied in wet or foggy weather, nor when the ambient temperature is below 4°C.

Preformed membrane material shall be placed starting at the bottom and lapped by a minimum of 150 mm at splices and at repairs to holes or tears.

Exposed edges of membrane sheets shall have a trowelled bead of manufacturer's recommended mastic or sealing tape applied after the membrane is placed.

The surface of the preformed membrane shall be cleaned free of dirt and other deleterious material before the protective covering is placed.

The protective covering shall be placed on a coating of adhesive of a type recommended by the manufacturer. The adhesive shall be applied at a rate sufficient to hold the protective covering in position until the backfill is placed.

Preformed membrane waterproofing will be measured and paid for by the square meter as asphalt membrane waterproofing.

#### **10-1.40 TREAT BRIDGE DECKS**

Treating bridge decks shall consist of test sealing, and furnishing and applying a penetrating sealer as shown on the plans and as specified in these special provisions.

The following bridges shall be treated:

Soto Street Undercrossing (Br. No. 53-1390R)

Marietta Street Undercrossing (Br. No. 53-1392L)

The surfaces to be treated include the deck of the existing bridge and newly constructed overhang to the limits shown on the plans.

Prior to the start of deck treatment work, the Contractor shall submit for approval by the Engineer, a program for public safety associated with the use of methacrylate resin. The program shall identify materials, equipment, and methods to be used. The Contractor shall not perform deck treatment work, other than that specifically authorized in writing by the Engineer, until the program has been approved.

If the measures being taken by the Contractor are inadequate to provide for public safety associated with the use of methacrylate resin, the Engineer will direct the Contractor to revise the operations and the public safety program. Directions for revisions will be in writing and will specify the items in which the Contractor's program is inadequate. No further deck treatment shall be performed until public safety measures are adequate, and a revised program for public safety has been approved.

The Engineer will notify the Contractor of the approval or rejection of any submitted or revised program for public safety associated with the use of methacrylate resin within 10 working days of receipt of the program.

The State will not be liable to the Contractor for failure to approve all or any portion of an originally submitted or revised program for public safety associated with the use of methacrylate resin, nor for any delays to the work due to the Contractor's failure to submit an acceptable program for public safety associated with the use of methacrylate resin. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

#### **Materials**

The material used for treating the concrete shall be a low odor, high molecular weight methacrylate resin. Prior to adding initiator, the resin shall have a maximum volatile content of 30 percent, when tested in conformance with the requirements in ASTM Designation: D 2369, and shall conform to the following:

PROPERTY	TEST METHOD	REQUIREMENT
* Viscosity Pa·s, maximum, (Brookfield RVT with UL adaptor, 50 RPM at 25°C)	ASTM D 2196	0.025
* Specific Gravity minimum, at 25°C	ASTM D 1475	0.90
* Flash Point °C, minimum	ASTM D 3278	82
* Vapor Pressure mm Hg, maximum, at 25°C	ASTM D 323	1.0
Tack-free Time minutes, maximum at 25°C	California Test 551	400
PCC Saturated Surface-Dry Bond Strength MPa, minimum at 24 hours and 21±1°C	California Test 551	3.5
* Test shall be performed prior to adding initiator.		

A Material Safety Data Sheet shall be furnished prior to use for each shipment of high molecular weight methacrylate resin.

The promoter and initiator, if supplied separately from the resin, shall not be mixed directly with each other. Containers of promoters and initiators shall not be stored together in a manner that will allow leakage or spillage from one to contact the containers or material of the other.

### Testing

The Contractor shall allow 14 working days for sampling and testing by the Engineer of the high molecular weight methacrylate resin prior to proposed use.

The Contractor shall treat a test area within the project limits of approximately 50 m<sup>2</sup> at a location approved by the Engineer. Conditions during the test treatment shall be similar to those expected on the deck. Equipment used in the test shall be similar to those used for the deck treating operations. If the test area is on the traveled way, traffic shall not be allowed on the treated test area until (1) the treated surface is tack free (non-oily), (2) the sand cover adheres sufficiently to resist brushing by hand, and (3) the coefficient of friction of the deck is at least 0.35 when tested in conformance with the requirements in California Test 342.

Should the above requirements for traffic use not be met, the Contractor shall suspend treating of bridge decks until another test area is treated and complies with the requirements.

### Construction

Prior to treating bridge decks, the deck surface shall be cleaned as specified in "Clean Bridge Deck" of these special provisions.

Equipment shall be fitted with suitable traps, filters, drip pans, or other devices as necessary to prevent oil or other deleterious material from being deposited on the deck.

The relative humidity shall be less than 90 percent at time of treatment.

A compatible promoter/initiator system shall be capable of providing a resin gel time of not less than 40 minutes nor more than 1.5 hours at the temperature of application. Gel time shall be adjusted to compensate for the changes in temperature throughout treatment application.

The quantity of resin mixed with promoter and initiator shall be limited to 20 L at a time for manual application.

Machine application of the resin shall be performed by using a two-part resin system using a promoted resin for one part and an initiated resin for the other part. This two-part resin system shall be combined at equal volumes to the spray bars through separate positive displacement pumps. Combining of the 2 components shall be by either static in-line mixers or by external intersecting spray fans. The pump pressure at the spray bars shall not be great enough to cause appreciable

atomization of the resin. Compressed air shall not be used to produce the spray. A shroud shall be used to enclose the spray bar apparatus. Hand held spray apparatus shall not be used.

The Contractor shall apply methacrylate resin only to the specified area. Concrete barriers, joints, and drainage facilities shall be adequately protected to prevent contamination by the treatment material. Contaminated items shall be repaired at the Contractor's expense.

The prepared area shall be dry and the surface temperature shall not exceed 38°C when the resin is applied. The rate of application of promoted/initiated resin shall be approximately 2.5 square meter per liter; the exact rate shall be determined by the Engineer.

The deck surfaces to be treated shall be flooded with resin, allowing penetration into the concrete and filling of all cracks. The treatment shall be applied within 5 minutes after complete mixing. A significant increase in viscosity shall be cause for rejection. Excess material shall be redistributed by squeegees or brooms within 10 minutes after application.

After the resin has been applied, at least 20 minutes shall elapse before applying sand. The sand shall be commercial quality dry blast sand. Ninety-five percent of the sand shall pass the 2.36-mm sieve, and 95 percent shall be retained on the 850- $\mu$ m sieve. The sand shall be applied at a rate of approximately one kilogram per square meter.

Excess sand shall be removed from the deck surface by vacuuming or sweeping prior to opening to traffic.

Traffic shall not be allowed on the treated area until (1) the treated surface is tack free (non-oily), (2) the sand cover adheres sufficiently to resist brushing by hand, and (3) the coefficient of friction of the deck is at least 0.35 when tested in conformance with the requirements in California Test 342.

### **Measurement and Payment**

Treating bridge deck surfaces will be measured by the square meter based on plan dimensions and will be paid for as treat bridge deck. Furnishing the high molecular weight methacrylate resin will be measured by the liter of mixed material actually placed and will be paid for as furnish bridge deck treatment material. No payment will be made for material wasted or not used in the work.

The contract price paid per square meter for treat bridge deck shall include full compensation for furnishing all labor, materials, (including sand, but excluding treatment material), tools, equipment, and incidentals, and for doing all the work involved in test sealing, applying treatment material and removing excess sand, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The contract price paid per liter for furnish bridge deck treatment material (low odor) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals necessary to furnish the bridge deck treatment material to the site of the work, ready for application, as specified in the Standard Specifications and these special provisions and as directed by the Engineer.

Full compensation for compliance with the requirements for the program for public safety associated with use of methacrylate resin shall be considered as included in the contract prices paid for the items of work involving treating bridge decks, and no additional compensation will be allowed therefor.

### **10-1.41 ROADSIDE SIGNS**

Roadside signs shall be installed at the locations shown on the plans or where designated by the Engineer and in conformance with the provisions in Section 56-2, "Roadside Signs," of the Standard Specifications and these special provisions.

Wood posts shall be pressure treated after fabrication in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," of the Standard Specifications with creosote, creosote coal tar solution, creosote petroleum solution (50-50), pentachlorophenol in hydrocarbon solvent, copper naphthenate, ammoniacal copper arsenate, or ammoniacal copper zinc arsenate. In addition to the preservatives listed above, Southern yellow pine may also be pressure treated with chromated copper arsenate. When other than one of the creosote processes is used, blocks shall have a minimum retention of 6.4 kg/m<sup>3</sup>, and need not be incised.

Metal (wall mounted sign) will be measured by the unit from actual count.

The contract unit price paid for metal (wall mounted sign) shall include full compensation for furnishing all labor, materials (except State-furnished sign panels), tools, equipment, and incidentals, and for doing all the work involved in mounting the sign panels on sound wall, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **10-1.42 INSTALL SIGN OVERLAY**

Sign overlays shall be installed on existing signs as shown on the plans and in conformance with these special provisions.

Sign overlay panels will be furnished by the State as provided under "Materials" of these special provisions.

Self plugging blind rivets for installing sign overlays shall have a 4.8-mm x 15.9-mm shank. A No. 10 drill shall be used for drilling the rivet holes. If the overlay is not pre-punched, maximum rivet spacing shall be 400 mm.

Where the existing sign panel is porcelain enameled steel, a diamond bit shall be used for drilling rivet holes. Exposed metal around the hole shall be covered with a thin coat of silicone adhesive conforming to the provisions in "Adhesive for Bonding Reflex Reflectors to Porcelain Enamel Traffic Signs" of these special provisions.

Installing sign overlays will be measured by the unit from actual count.

The contract unit price paid for install sign overlay shall include full compensation for furnishing all labor, materials (except sign overlays), tools, equipment, and incidentals, and for doing all the work involved in installing sign overlay panels on existing signs (including fastening hardware), as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

#### **10-1.43 REINFORCED CONCRETE PIPE**

Reinforced concrete pipe shall conform to the provisions in Section 65, "Reinforced Concrete Pipe," of the Standard Specifications and these special provisions.

Where embankment will not be placed over the top of the pipe, a relative compaction of not less than 85 percent shall be required below the pipe spring line for pipe installed using Method 1 backfill in trench, as shown on Standard Plan A62D. Where the pipe is to be placed under the traveled way, a relative compaction of not less than 90 percent shall be required unless the minimum distance between the top of the pipe and the pavement surface is the greater of 1.2 m or one half of the outside diameter of the pipe.

Except as otherwise designated by classification on the plans or in the specifications, joints for culvert and drainage pipes shall conform to the plans or specifications for standard joints.

When reinforced concrete pipe is installed in conformance with the details shown on Revised Standard Plan A62DA, the fifth paragraph of Section 19-3.04, "Water Control and Foundation Treatment," of the Standard Specifications shall not apply.

When solid rock or other unyielding material is encountered at the planned elevation of the bottom of the bedding, the material below the bottom of the bedding shall be removed to a depth of 1/50 of the height of the embankment over the top of the culvert, but not less than 150 mm nor more than 300 mm. The resulting trench below the bottom of the bedding shall be backfilled with structure backfill material in conformance with the provisions in Section 19-3.06, "Structure Backfill," of the Standard Specifications.

The Outer Bedding shown on Revised Standard Plan A62DA shall not be compacted prior to placement of the pipe.

#### **10-1.44 SLOPE PROTECTION**

Slope protection shall be placed or constructed in conformance with the provisions in Section 72, "Slope Protection," of the Standard Specifications.

Rock slope protection fabric shall be woven or nonwoven type fabric, Type A or Type B, at the option of the Contractor.

#### **10-1.45 MISCELLANEOUS IRON AND STEEL**

Miscellaneous iron and steel shall conform to the provisions in Section 75, "Miscellaneous Metal," of the Standard Specifications.

#### **10-1.46 MISCELLANEOUS METAL (BRIDGE)**

Miscellaneous metal (bridge) shall conform to the provisions for miscellaneous bridge metal in Section 75, "Miscellaneous Metal," of the Standard Specifications and these special provisions.

Attention is directed to "Welding" of these special provisions.

Miscellaneous metal (bridge) shall consist of the miscellaneous bridge metal items listed in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications, and the following:

- A. Galvanized sheet metal conduit cover
- B. Galvanized double-extra strong steel pipe

Double extra strong steel pipe shall conform to the requirements of ASTM Designation: A53, Grade B.

#### **10-1.47 CHAIN LINK WALK GATE**

Chain link walk gates shall be Type CL-1.8 conforming to the provisions in Section 80, "Fences," of the Standard Specifications and these special provisions.

Gates shall be installed in existing fences at the locations shown on the plans. Gate installations shall be complete with gate post, latch post, concrete footings, braces, truss rods, and hardware. Gate and latch posts shall be braced to the next existing line post as shown on the plans.

At each gate location, an existing line post shall be removed and the new gate installed so that the gate is centered on the post hole of the removed post. Holes resulting from the removal of line posts shall be backfilled.

Gate mounting and latching hardware shall not contain open-end slots for the fastening bolts.

Chain link fabric for gates shall be of the same mesh size as the existing fence in which the gates are installed.

Openings made in existing fences for installation of gates shall be closed during the working day in which the openings are made and when work is not in progress. Temporary closures shall be made with the existing fence fabric or with additional 1.83-m chain link fabric as directed by the Engineer.

Full compensation for making the openings in existing fences, for temporary closing of the openings (including furnishing additional fence fabric if necessary), and for new posts, footings, hardware, braces, and truss rods shall be considered as included in the contract unit price paid for 1.5-m chain link gate (Type CL-1.8) and no additional compensation will be allowed therefor.

#### **10-1.48 METAL BEAM GUARD RAILING (WOOD POST)**

Metal beam guard railing (Wood Post) shall be constructed in conformance with the provisions in Section 83-1, "Railings," of the Standard Specifications and these special provisions.

Attention is directed to "Order of Work" of these special provisions.

Line posts and blocks shall be wood.

#### **TERMINAL SYSTEM (TYPE SRT)**

Terminal system (Type SRT) shall be furnished and installed as shown on the plans and in conformance with these special provisions.

Terminal system (Type SRT) shall be a SRT-350 Slotted Rail Terminal (8 post system) as manufactured by Trinity Industries, Inc., and shall include all the items detailed for terminal system (Type SRT) shown on the plans.

The 5 mm x 44 mm x 75 mm plate washer shown on the elevation view and in Section D-D at Wood Post No. 1 shall be omitted.

Arrangements have been made to insure that any successful bidder can obtain the SRT-350 Slotted Rail Terminal (8 post system) from the manufacturer, Trinity Industries, Inc., P.O. Box 99, 950 West 400S, Centerville, UT 84014, Telephone 1-800-772-7976. The price quoted by the manufacturer for the SRT-350 Slotted Rail Terminal (8 post system), FOB Centerville, Utah is \$845, not including sales tax.

The above price will be firm for orders placed on or before July 31, 2003, provided delivery is accepted within 90 days after the order is placed.

The Contractor shall provide the Engineer with a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall certify that terminal systems (Type SRT) conform to the contract plans and specifications, conform to the prequalified design and material requirements and were manufactured in conformance with the approved quality control program.

The terminal system (Type SRT) shall be installed in conformance with the manufacturer's installation instructions and these requirements. The steel foundation tubes with soil plates attached, shall be, at the Contractor's option, either driven, with or without pilot holes, or placed in drilled holes. Space around the steel foundation tubes shall be backfilled with selected earth, free of rock, placed in layers approximately 100 mm thick and each layer shall be moistened and thoroughly compacted. Wood terminal posts shall be inserted into the steel foundation tubes by hand. Before the wood terminal posts are inserted, the inside surfaces of the steel foundation tubes to receive the wood posts shall be coated with a grease which will not melt or run at a temperature of 65°C or less. The edges of the wood terminal posts may be slightly rounded to facilitate insertion of the post into the steel foundation tubes.

Surplus excavated material remaining after the terminal system (Type SRT) has been constructed shall be disposed of in a uniform manner along the adjacent roadway where designated by the Engineer.

#### **10-1.49 CONCRETE BARRIER**

Concrete barriers shall conform to the provisions in Section 83-2, "Barriers," of the Standard Specifications and these special provisions.

Concrete barrier (Type 736SV Mod) will be measured and paid for as concrete barrier (Type 736 Modified).

Full compensation for galvanized double-extra strong steel pipe conduit in barrier, including expansion fittings, shall be considered as included in the contract price paid per meter for concrete barrier of the type or types listed in the Engineer's Estimate and no separate payment will be made therefor.

### **10-1.50 THERMOPLASTIC TRAFFIC STRIPE**

Thermoplastic traffic stripes (traffic lines) shall be applied in conformance with the provisions in Section 84, "Traffic Stripes and Pavement Markings," of the Standard Specifications and these special provisions.

Where striping joins existing striping, as shown on the plans, the Contractor shall begin and end the transition from the existing striping pattern into or from the new striping pattern a sufficient distance to ensure continuity of the striping pattern.

Thermoplastic material shall conform to the requirements in State Specification 8010-19A.

Thermoplastic material for traffic stripes shall be applied at a minimum thickness of 2.0 mm.

At the option of the Contractor, permanent traffic striping and pavement marking tape conforming to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions may be placed instead of the thermoplastic traffic stripes and pavement markings specified herein. Permanent tape, if used, shall be installed in conformance with the manufacturer's specifications. If permanent tape is placed instead of thermoplastic traffic stripes, the tape will be measured and paid for by the meter as thermoplastic traffic stripe.

### **10-1.51 PAVEMENT MARKERS**

Pavement markers shall be placed in conformance with the provisions in Section 85, "Pavement Markers," of the Standard Specifications and these special provisions.

Attention is directed to "Traffic Control System For Lane Closure" of these special provisions regarding the use of moving lane closures during placement of pavement markers with bituminous adhesive.

Retroreflective pavement markers shall comply with the specific intensity provisions for reflectance after abrading the lens surface in conformance with the "Steel Wool Abrasion Procedure" specified for pavement markers placed in pavement recesses in Section 85-1.05, "Retroreflective Pavement Markers," of the Standard Specifications.

## **SECTION 10-2 HIGHWAY PLANTING AND IRRIGATION SYSTEMS**

### **10-2.01 GENERAL**

The work performed in connection with highway planting and irrigation systems shall conform to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications and these special provisions.

The Contractor shall notify the Engineer not less than 72 hours prior to requiring initial access to the existing irrigation controllers. When the Engineer determines that access to the controllers is required at other times, arrangements will be made to provide this access.

When fluctuations of water pressure and water supply are encountered during normal working hours, plants shall be watered at other times, as often, and in sufficient amounts as conditions may require to keep the soil and plant roots moist during the life of the contract.

Full compensation for watering plants outside normal working hours shall be considered as included in the contract lump sum prices paid for highway planting and plant establishment work and no additional compensation will be allowed therefor.

### **PROGRESS INSPECTIONS**

Progress inspections will be performed by the Engineer for completed highway planting and irrigation system work at designated stages during the life of the contract.

Progress inspections will not relieve the Contractor of responsibility for installation in conformance with the special provisions, plans and Standard Specifications. Work within an area shall not progress beyond each stage until the inspection has been completed, corrective work has been performed, and the work is approved, unless otherwise permitted by the Engineer.

The requirements for progress inspections will not preclude additional inspections of work by the Engineer at other times during the life of the contract.

The Contractor shall notify the Engineer, in writing, at least 4 working days prior to completion of the work for each stage of an area and shall allow a minimum of 3 working days for the inspection.

Progress inspections will be performed at the following stages of work:

- A. During pressure testing of the pipelines on the supply side of control valves.
- B. During testing of low voltage conductors.
- C. Irrigation functional tests.
- D. Before planting begins and after completion of the work specified for planting in Section 20-4.03, "Preparing Planting Areas," of the Standard Specifications.

- E. Before plant establishment work begins and after completion of the work specified for planting in Section 20-4.05, "Planting," of the Standard Specifications.
- F. At intervals of one month during the plant establishment period.

#### **COST BREAK-DOWN**

The Contractor shall furnish the Engineer a cost break-down for the contract lump sum items of highway planting and irrigation system. Cost break-down tables shall be submitted to the Engineer for approval within 15 working days after the contract has been approved. Cost break-down tables shall be approved, in writing, by the Engineer before any partial payment will be made for the applicable items of highway planting and irrigation system involved.

Cost break-downs shall be completed and furnished in the format shown in the samples of the cost break-downs included in this section. Line item descriptions of work shown in the samples are the minimum to be submitted. Additional line item descriptions of work may be designated by the Contractor. If the Contractor elects to designate additional line item descriptions of work, the quantity, value and amount for those line items shall be completed in the same manner as for the unit descriptions shown in the samples. The line items and quantities given in the samples are to show the manner of preparing the cost break-downs to be furnished by the Contractor.

The Contractor shall determine the quantities required to complete the work shown on the plans. The quantities and their values shall be included in the cost break-downs submitted to the Engineer for approval. The Contractor shall be responsible for the accuracy of the quantities and values used in the cost break-downs submitted for approval.

The sum of the amounts for the line items of work listed in each cost break-down table for highway planting and for irrigation system work shall be equal to the contract lump sum price bid for Highway Planting and Irrigation System, respectively. Overhead and profit, , shall be included in each individual line item of work listed in a cost break-down table.

No adjustment in compensation will be made in the contract lump sum prices paid for highway planting and irrigation system due to differences between the quantities shown in the cost break-downs furnished by the Contractor and the quantities required to complete the work as shown on the plans and as specified in these special provisions.

Individual line item values in the approved cost break-down tables will be used to determine partial payments during the progress of the work and as the basis for calculating an adjustment in compensation for the contract lump sum items of highway planting and irrigation system due to changes in line items of work ordered by the Engineer. When the total of ordered changes to line items of work increases or decreases the lump sum price bid for either Highway Planting or Irrigation System by more than 25 percent, the adjustment in compensation for the applicable lump sum item will be determined in the same manner specified for increases and decreases in the total pay quantity of an item of work in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications.

## HIGHWAY PLANTING COST BREAK-DOWN

Contract No. 07-053514

UNIT DESCRIPTION	UNIT	APPROXIMATE QUANTITY	VALUE	AMOUNT
COMMERCIAL FERTILIZER	KG	12		
MULCH (100 MM THICK)	M3	454		
PREPARE HOLES	EA	339		
PLANT (GROUP-A)	EA	321		
PLANT (GROUP-U)	EA	18		

**TOTAL** \_\_\_\_\_

**IRRIGATION SYSTEM COST BREAK-DOWN**

**Contract No. 07-053514**

UNIT DESCRIPTION	UNIT	APPROXIMATE QUANTITY	VALUE	AMOUNT
CHECK, TEST AND REMOVE EXISTING IRRIGATION FACILITIES	LS	LUMP SUM		
CONTROL AND NEUTRAL CONDUCTORS	LS	LUMP SUM		
MAINTAIN EXISTING IRRIGATION FACILITIES	LS	LUMP SUM		
REMOVE EXISTING IRRIGATION FACILITY	LS	LUMP SUM		
25-mm ELECTRIC REMOTE CONTROL VALVE	EA	23		
32-mm ELECTRIC REMOTE CONTROL VALVE	EA	13		
40-mm ELECTRIC REMOTE CONTROL VALVE	EA	8		
50-mm ELECTRIC REMOTE CONTROL VALVE	EA	1		
12 STATION IRRIGATION CONTROLLER (PEDESTAL MOUNTED)	EA	6		
20 mm PLASTIC PIPE (PR 200)	M	758		
25-mm PLASTIC PIPE (PR 200)	M	618		
32-mm PLASTIC PIPE (PR 200)	M	197		
40 mm PLASTIC PIPE (PR 200)	M	749		
50-mm PLASTIC PIPE (PR 200)	M	1030		
65-mm PLASTIC PIPE (PR 200)	M	245		
75-mm PLASTIC PIPE (PR 200)	M	160		
SPRINKLER (TYPE A-3)	EA	21		
SPRINKLER (TYPE C-3)	EA	165		
20 mm NOZZLE LINE	M	80		
25-mm BALL VALVE	EA	7		
32-mm BALL VALVE	EA	3		

40-mm BALL VALVE	EA	6		
65-mm GATE VALVE	EA	1		
75-mm GATE VALVE	EA	1		
200mm EXTEND CONDUIT	M	11		
25 mm WYE STRAINER	EA	4		

**TOTAL** \_\_\_\_\_

## **10-2.02 EXISTING HIGHWAY PLANTING**

In addition to the provisions in Section 20 of the Standard Specifications, work performed in connection with existing highway planting shall be in conformance with the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Replacement planting shall conform to the requirements specified under "Preservation of Property" of these special provisions.

### **MAINTAIN EXISTING PLANTS**

Existing plants shall be maintained as directed by the Engineer. Maintaining existing plants will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

### **REMOVE EXISTING PLANTS FOR TRENCHING**

Removing existing plants for trenching shall conform to the provisions in Section 20-5.026, "Remove Existing Plants for Trenching," of the Standard Specifications and these special provisions.

Removing existing plants for trenching work shall consist of removing ground cover, pruning trees and shrubs within trench locations, applying preemergents and disposing of removed ground cover and prunings.

Replacement of removed ground cover within the maximum 1.8-m width, as specified in Section 20-5.026, "Remove Existing Plants for Trenching," of the Standard Specifications, will not be required.

Trees and shrubs adjacent to soundwalls, dikes, walks, fences, guard railing, and pavement edges may be pruned back 3 m from these facilities to facilitate trenching work. When trenching is to be performed adjacent to other trees and shrubs that cannot be avoided, the trees and shrubs may be pruned upon receipt of prior written approval of the Engineer.

Pruning shall include removal of deadwood, suckers, and broken or bruised branches 25 mm or larger in diameter. Pruning shall conform to the provisions in Section 20-4.055, "Pruning," of the Standard Specifications.

Removed ground cover and pruned materials shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Shrubs adjacent to dikes, fences, guard railing, and the edge of pavement within the 3-m pruned area designated above, that in the opinion of the Engineer should be removed after pruning, shall be removed and disposed of. Removing and disposing of the shrubs not otherwise provided for will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

One application of a preemergent pesticide shall be applied to trenched areas in existing ground cover areas and to trenched areas adjacent to fences, curbs, dikes and shoulders. The Engineer will determine when the preemergent pesticide shall be applied.

### **PRUNE EXISTING PLANTS**

Existing plants, as determined by the Engineer, shall be pruned. Pruning of the existing plants, except as otherwise provided in these special provisions, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

## **10-2.03 EXISTING HIGHWAY IRRIGATION FACILITIES**

The work performed in connection with the various existing highway irrigation system facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Water shall be maintained in conformance with the provisions in Section 20-5.025, "Maintain Existing Water Supply," of the Standard Specifications.

### **LOCATE EXISTING CROSSOVERS AND CONDUITS**

Existing crossovers and conduits shown on the plans to be incorporated in the new work shall be located in conformance with the provisions for locating conduits in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

Unless otherwise directed by the Engineer, existing crossovers and conduits shown on the plans to be incorporated in the new work shall be located prior to performing work on irrigation systems.

If debris is encountered in the ends of conduits, the debris shall be removed prior to performing other work in the conduits. Removal of debris within the first one meter in these conduits shall be at the Contractor's expense. If debris is encountered in the conduits more than one meter from the ends of the conduits, the additional debris shall be removed as directed by the Engineer and the removal work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

## **CHECK AND TEST EXISTING IRRIGATION FACILITIES**

Existing irrigation facilities that are to remain, and that are within those areas of soundwall work, shall be checked by the Contractor in the presence of the Engineer for missing or damaged components and proper operation prior to performing clearing and grubbing or earthwork operations. Existing irrigation facilities outside of work areas that are affected by the construction work shall also be checked for proper operation.

A written list of existing irrigation system deficiencies and modifications necessary to facilitate soundwall construction shall be submitted to the Engineer within 5 working days after checking the existing facilities.

Deficiencies found during checking of the existing facilities shall be corrected as directed by the Engineer. Corrective and modification work, except as otherwise provided in these special provisions, ordered by the Engineer will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Length of watering cycles for use of potable water from water meters for checking or testing existing irrigation facilities shall be as determined by the Engineer.

Repairs to the existing irrigation facilities ordered by the Engineer after checking and testing the facilities, and further repairs or modifications required thereafter as ordered by the Engineer, except as otherwise provided for under "Maintain Existing Irrigation Facilities" of these special provisions, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

At the completion of all work at each location, the existing and modified irrigation facilities shall be inspected by the Contractor in the presence of the Engineer. Any damage to the existing and modified irrigation facilities caused by the Contractor's operations shall be repaired within 5 working days at the expense of the Contractor.

## **MAINTAIN EXISTING IRRIGATION FACILITIES**

Existing irrigation facilities shall be maintained throughout the life of the contract. Prior to the start of maintaining existing irrigation facilities work, the facilities shall be checked for proper operation, and repaired in conformance with the provisions in "Check and Test Existing Irrigation Facilities" of these special provisions.

After the existing facilities have been checked and repaired, the Contractor shall be responsible for the routine maintenance of existing irrigation systems. The work shall include, but not limited to, checking irrigation systems for proper operation and adjusting, repairing or replacing valves, valve boxes, sprinklers, risers, swing joints, wye strainers, and valve assembly units.

The Contractor will not be responsible for maintaining existing water meters, underground pipe supply lines, control and neutral conductors, and electrical conduits. Except as otherwise specified in section "Existing Highway Irrigation Facilities" of these special provisions, repair work to these facilities ordered by the Engineer will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Existing automatic irrigation systems shall be operated automatically during the life of the contract, except manual operation will be allowed for the work during plant replacement, fertilization, weed germination, and the repair of irrigation facilities.

Irrigation controllers shall be programmed by the Contractor for seasonal water requirements. During winter seasons irrigation systems shall be operated automatically a minimum of 2 minutes every 2 weeks.

Irrigation systems and facilities shall be checked for proper operation at least once every 30 days. When required, as determined by the Engineer, adjusting, repairing or replacing irrigation facilities shall be completed within 5 working days after checking the irrigation systems. Except as provided in these special provisions, repair and replacement of irrigation facilities shall conform to the provisions in "Existing Highway Irrigation Facilities" of these special provisions.

Except as provided in these special provisions, full compensation for maintaining existing irrigation facilities, including checking irrigation facilities, shall be considered as included in the contract lump sum price paid for irrigation system and no separate payment will be made therefor.

## **REMOVE EXISTING IRRIGATION FACILITIES**

Existing irrigation facilities that are within the clearing and grubbing zone, shall be removed. Facilities that are more than 150 mm below finished grade, excluding facilities to be salvaged, may be abandoned in place.

Immediately after disconnecting an existing irrigation facility to be removed or abandoned from an existing facility to remain, the remaining facility shall be capped or plugged, or shall be connected to a new or existing irrigation facility.

Facilities to be removed, shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

## **10-2.04 HIGHWAY PLANTING**

The work performed in connection with highway planting shall conform to the provisions in Section 20-4, "Highway Planting," of the Standard Specifications and these special provisions.

## HIGHWAY PLANTING MATERIALS

### Mulch (Green Material)

Mulch shall be woody material. Woody materials shall consist of chipped, shredded or ground green materials such as shrubs, tree trimmings or clean processed wood products.

Deleterious materials such as rocks, glass, plastics, metals, clods, weeds, weed seeds, coarse objects, sticks larger than the specified particle size, salts, paint, petroleum products, pesticides or other chemical residues that would be harmful to plant or animal life shall not exceed 0.1-percent of the mulch volume. Chipping shall include shredding, grinding or other methods used to reduce mulch materials to the specified size.

Green materials shall be processed and have reached an internal temperature of 56°C for a minimum of 15 consecutive days. During the processing period, the green material shall have been turned a minimum of 5 times.

Green material shall have a particle size conforming to the provisions for shredded bark in Section 20-2.08, "Mulch," of the Standard Specifications.

### Commercial Fertilizer (Slow Release)

Commercial fertilizer (slow release) shall be a pelleted or granular form, shall be slow or controlled release with a nutrient release over an 8- to 12-month period, and shall fall within the following guaranteed chemical analysis range:

Ingredient	Percentage
Nitrogen	16-21
Phosphoric Acid	6-8
Water Soluble Potash	4-10

## ROADSIDE CLEARING

Prior to preparing planting areas, mulch areas, or commencing irrigation trenching operations, trash and debris shall be removed from within 3 meters of soundwall construction, excluding paved areas, medians and existing planted areas where existing plants are to remain.

In addition to removing trash and debris, the project area shall be cleared as specified herein:

- A. Trees and shrubs adjacent to soundwalls, that in the opinion of the Engineer should be removed, shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Materials Outside of the Highway Right of Way," of the Standard Specifications. Removal of existing trees and shrubs regardless of size shall be at ground level and include treating the remaining stumps and roots with a herbicide (stump killer) approved by the Engineer.
- B. Weeds shall be killed and removed within 3 meters of soundwall construction, and including new and existing pavement, curb, sidewalk and other surfaced areas.

After the initial roadside clearing is complete, additional roadside clearing work shall be performed as necessary to maintain the areas, as specified above, in a neat appearance until the start of the plant establishment period. This work shall include the following:

- A. Trash and debris shall be removed.
- B. Rodents shall be controlled.
- C. Weed growth shall be killed before the weeds reach the seed stage of growth or exceed 150 mm in length.
- D. Weeds in plant basins, including basin walls, shall be removed by hand pulling, after the plants have been planted.

### Weed Control

Weed control shall also conform to the following:

- A. Stolon type weeds shall be killed with glyphosate.
- B. Removed weeds and ground cover shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Roadside clearing work shall not include work required to be performed as clearing and grubbing as specified in Section 16, "Clearing and Grubbing," of the Standard Specifications.

### **PESTICIDES**

Pesticides used to control weeds shall conform to the provisions in Section 20-4.026, "Pesticides," of the Standard Specifications. Except as otherwise provided in these special provisions, pesticide use shall be limited to the following materials:

- Cacodylic Acid
- Diquat
- Fluazifop-butyl
- Glyphosate
- Isoxaben (Preemergent)
- Sethoxydim
- Oxadiazon - 50 percent WP (Preemergent)
- Oryzalin (Preemergent)
- Pendimethalin (Preemergent)
- Proflaminate (Preemergent)
- Trifluralin (Preemergent)
- Ammonium Sulfate
- Magnesium Chloride
- Napropamide (Preemergent)

Granular preemergents may be used when applied to areas that will be covered with mulch, excluding plant basins. Granular preemergents shall be limited to the following materials:

- Dichlobenil (Preemergent)
- Oxadiazon (Preemergent)

Granular preemergents shall be applied prior to the application of mulch. Mulch applications shall be completed in these areas on the same working day. Photosensitive dye will not be required.

Glyphosate shall be used to kill stolon type weeds.

Oxadiazon shall be of the emulsifiable concentration or wettable powder type, except when Oxadiazon is used under mulch in conformance with these special provisions.

A minimum of 30 days shall elapse between applications of preemergents.

Preemergents shall not be applied within 450 mm of plants.

Ammonium sulfate and magnesium chloride shall be used only in areas planted to *Carpobrotus* or *Delosperma*. Ammonium sulfate and magnesium chloride shall not be applied in a manner that allows the pesticides to come in contact with trees or shrubs.

If the Contractor elects to request the use of other pesticides on this project, the request shall be submitted, in writing, to the Engineer not less than 15 days prior to the intended use of the other pesticides. Except for the pesticides listed in these special provisions, no pesticides shall be used or applied without prior written approval of the Engineer.

Pesticides shall not be applied within the limits of the plant basins. Pesticides shall not be applied in a manner that allows the pesticides to come in contact with the foliage and woody parts of the plants.

### **PREPARING PLANTING AREAS**

Plants adjacent to drainage ditches shall be located so that after construction of the basins, no portion of the basin walls shall be less than the minimum distance shown on the plans for each plant involved.

### **PREPARE HOLES**

Holes for plants shall be excavated to the minimum dimensions shown on the plans.

Backfill material for plant holes shall be a mixture of soil and other materials shown on the Plant List. Backfill material shall be thoroughly mixed and uniformly distributed throughout the entire depth of the plant hole without clods and lumps.

### **PLANTING**

Commercial fertilizer shall be applied or placed at the time of planting and at the rates shown on the plans.

A granular preemergent shall be applied to areas to be covered with mulch outside of plant basins in conformance with the provisions in "Pesticides" of these special provisions.

Mulch placed in areas outside of plant basins shall be spread to a uniform depth of 100 mm.

Mulch shall not be placed within one meter of the center line of earthen drainage ditches, within one meter of the edge of paved ditches, and within one meter of the center line of drainage flow lines.

Attention is directed to "Irrigation Systems Functional Test" of these special provisions regarding functional tests of the irrigation systems. Planting shall not be performed in an area until the functional test has been completed for the irrigation system serving that area.

#### **PLANT ESTABLISHMENT WORK**

The plant establishment period shall be Type 2 and shall not be less than 90 working days.

Attention is directed to "Relief From Maintenance and Responsibility" in these special provisions regarding relief from maintenance and protection.

Commercial fertilizer (slow release) shall be applied to trees, shrubs, and vines one time during the year. Commercial fertilizer shall be applied at the rates shown on the plans and shall be spread with a mechanical spreader wherever possible.

Weeds within plant basins, including basin walls shall be controlled by hand pulling.

Weeds within mulched outside of plant basins shall be controlled by killing.

Vines shall be trained onto walls.

At the option of the Contractor, plants of a larger container size than those originally specified may be used for replacement plants during the plant establishment period. The use of plants of a larger container size than those originally specified for replacement plants shall be at the Contractor's expense.

When ordered by the Engineer, one application of a preemergent pesticide conforming to the provisions in "Pesticides" of these special provisions, shall be applied between 20 and 30 working days prior to completion of the plant establishment period. This work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Wye strainers shall be cleaned at least 15 days prior to the completion of the plant establishment period.

The final inspection shall be performed in conformance with the provisions in Section 5-1.13, "Final Inspection," of the Standard Specifications and shall be completed a minimum of 20 working days before the estimated completion of the contract.

#### **10-2.05 IRRIGATION SYSTEMS**

Irrigation systems shall be furnished and installed in conformance with the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications, except materials containing asbestos fibers shall not be used.

Attention is directed to the provisions in "Obstructions" of these special provisions, regarding work over or adjacent to existing underground facilities. Excavation for proposed irrigation facilities shall not be started until the existing underground facilities have been located.

Pipe supply lines shall be pressure tested in conformance with the provisions in Section 20-5.03H, "Pressure Testing," of the Standard Specifications, except the pipe (supply line) on the discharge side of the control valve shall be tested by Method B as specified in Section 20-5.03H(2), "Method B," of the Standard Specifications.

Only pipeline trenches and excavation pits for supply lines being supplied from one water service point shall be open at one time. After pressure testing is complete, trenches and pits excavated for pipe supply lines, being supplied from one water service point, shall be backfilled prior to commencing excavations for pipe supply lines being supplied from another water service point.

Gate valves, 75 mm and larger in size, shall be furnished with a square lug and shall be operated by use of long shank keys. Prior to acceptance of the contract, 3 long shank keys shall be delivered to the Engineer.

#### **VALVE BOXES**

Valve boxes shall conform to the provisions in Section 20-2.24, "Valve Boxes," of the Standard Specifications, except as otherwise provided herein.

Valve boxes shall be precast portland cement concrete.

Covers for concrete valve boxes shall be cast iron or steel. Cast iron and steel covers shall be hinged with brass hinge pins for valve boxes containing valves smaller than 50 mm.

Valve boxes shall be identified on the top surface of the covers by labels containing the appropriate abbreviation for the irrigation facility contained in the valve box as shown on the plans. Valve boxes that contain remote control valves shall be identified by the appropriate letters and numbers (controller and station numbers). Labels for valve boxes shall conform to the provisions in Section 20-5.03F, "Valves and Valve Boxes," of the Standard Specifications.

Label material shall be polyurethane with contrasting colors for the base, letters, and numbers.

## **ELECTRIC AUTOMATIC IRRIGATION COMPONENTS**

### **Irrigation Controllers**

Irrigation controllers G, J, P, Q, T, and U shall be single, solid-state independent controllers conforming to the following:

- A. Irrigation controllers shall be fully automatic and shall operate a complete 14-day or longer irrigation program.
- B. A switch or switches shall be provided on the face of the control panel that will turn the irrigation controller "on" or "off" and provide for automatic or manual operation. Manual operation shall allow cycle start at the desired station and shall allow activation of a single station.
- C. The watering time of each station shall be displayed on the face of the control panel.
- D. The irrigation controller and the low voltage output source shall be protected by fuses or circuit breakers, located on the face of the controller.
- E. The irrigation controller mechanism, panel and circuit board shall be connected to the low voltage control and neutral conductors by means of plug and receptacle connectors located in the irrigation controller enclosure.
- F. Each station shall have a variable or incremental timing adjustment with a range of 12 hours to a minimum of one minute.
- G. Irrigation controllers shall be capable of a minimum of 4 program schedules.
- H. Irrigation controllers shall have an output that can energize a pump start circuit or a remote control valve (master).
- I. Irrigation controllers shall be manufactured by the same company.
- J. Where direct burial conductors are to be connected to the terminals strip, the conductors shall be connected with the proper size open-end crimp-on wire terminals. No exposed wire shall extend beyond the crimp of the terminal and the wires shall be parallel on the terminal strip.

### **Electric Remote Control Valves**

Electric remote control valves shall conform to the provisions in Section 20-2.23, "Control Valves," of the Standard Specifications and the following:

- A. Valves shall be brass, or bronze construction.
- B. Valves shall be straight pattern (side inlet) as shown on the plans.
- C. Valves for C-3 sprinkler systems shall be equipped with a pressure-regulating device. The device shall be capable of regulating pressure between 103 kPa and 689 kPa.

### **Pull Boxes**

Pull box installations shall conform to the provisions in Section 20-5.027I, "Conductors, Electrical Conduits and Pull Boxes," of the Standard Specifications.

### **Conductors**

Low voltage, as used in this section "Conductors," shall mean 36 V or less.

Low voltage control and neutral conductors in pull boxes and valve boxes, at irrigation controller terminals, and at splices shall be marked as follows:

- A. Conductor terminations and splices shall be marked with adhesive backed paper markers or adhesive cloth wrap-around markers, with clear, heat-shrinkable sleeves sealed over the markers.
- B. Non-spliced conductors in pull boxes and valve boxes shall be marked with clip-on, "C" shaped, white extruded polyvinyl chloride sleeves. Marker sleeves shall have black, indented legends of uniform depth with transparent overlays over the legends and "chevron" cuts for alignment of 2 or more sleeves.

Markers for the control conductors shall be identified with the appropriate number or letter designations of irrigation controllers and station numbers. Markers for neutral conductors shall be identified with the appropriate number or letter designations of the irrigation controllers.

New control and neutral conductors that are to replace existing control and neutral conductors shall be the same size and color as the existing control and neutral conductors being connected to.

The color of low voltage neutral and control conductor insulation, except for the striped portions, shall be homogeneous throughout the entire thickness of the insulation.

Insulation for conductors may be UL listed polyethylene conforming to UL44 test standards with a minimum insulation thickness of 1.05 mm for wire sizes 10AWG and smaller.

At the option of the Contractor, other types of splice sealing materials and methods may be used provided other materials and methods have been approved in writing by the Engineer prior to installation of the connectors.

### **IRRIGATION SYSTEMS FUNCTIONAL TEST**

Functional tests for the irrigation controllers and associated automatic irrigation systems shall conform to the provisions in Section 20-5.027J, "Testing," of the Standard Specifications and these special provisions.

Tests shall demonstrate to the Engineer, through one complete cycle of the irrigation controllers in the automatic mode, that the associated automatic components of the irrigation systems operate properly. If automatic components of the irrigation systems fail a functional test, these components shall be repaired at the Contractor's expense and the testing repeated until satisfactory operation is obtained.

Associated automatic components shall include, but not be limited to, remote control valve actuator systems and remote control valves.

Upon completion of work on an irrigation system, including correction of deficiencies and satisfactory functional tests for the systems involved, the plants to be planted in the area watered by the irrigation system may be planted provided the planting areas have been prepared as specified in these special provisions.

### **PIPE**

#### **Plastic Pipe**

Plastic pipe supply lines shall be polyvinyl chloride (PVC) 1120 or 1220 pressure rated pipe with the minimum pressure rating (PR) shown on the plans.

Plastic pipe supply lines shall have solvent cemented type joints. Primers shall be used on the solvent cemented type joints.

Plastic pipe supply lines (main) shall have a minimum cover of 0.45 m.

Plastic pipe supply lines downstream from the remote control valves for Type C sprinklers shall have a minimum cover of 150 mm.

Fittings for plastic pipe supply lines with a pressure rating (PR) of 315 shall be Schedule 80.

### **SPRINKLERS**

Sprinklers shall conform to the type, pattern, material, and operating characteristics listed in the "Sprinkler Schedule" shown on the plans.

Flexible risers shall be ultraviolet (UV) resistant, brown in color and shall conform to the details shown on the plans.

### **NOZZLE LINE INSTALLATION**

Nozzle line shall be 20 mm galvanized steel pipe anchored to the sound wall. Spray nozzles shall be brass body construction, 9 mm hex nut, self-tapping 7 mm thread, with a 2 mm orifice.

Nozzle line (20 mm) will be measured by the meter. The contract price paid per meter for nozzle line (20 mm) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in nozzle line (20 mm), complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **WYE STRAINERS**

Wye strainers shall be installed on the upstream side of the electric remote control valves as shown on the plans.

Removable stainless steel strainers for wye strainers shall be 25 µm size mesh.

When garden valves are opened, discharge shall be up and out of the valve box.

Full compensation for garden valves and pipe fittings for garden valves on wye strainers shall be considered as included in the contract lump sum price paid for irrigation system and no separate payment will be allowed therefor.

### **FINAL IRRIGATION SYSTEM CHECK**

A final check of existing and new irrigation facilities shall be performed not more than 20 working days prior to acceptance of the contract.

The length of watering cycles using potable water measured by water meters for the final check of irrigation facilities will be determined by the Engineer.

Remote control valves connected to existing and new irrigation controllers shall be checked for automatic performance when the controllers are in automatic mode.

Unsatisfactory performance of irrigation facilities installed or modified by the Contractor shall be repaired and rechecked at the Contractor's expense until satisfactory performance is obtained, as determined by the Engineer.

Repair or replacement of existing irrigation facilities due to unsatisfactory performance shall conform to the provisions in "Existing Highway Irrigation Facilities" of these special provisions.

Nothing in this section "Final Irrigation System Check" shall relieve the Contractor of full responsibility for making good or repairing defective work or materials found before the formal written acceptance of the entire contract by the Director.

Full compensation for checking the irrigation systems prior to the acceptance of the contract shall be considered as included in the contract lump sum price paid for plant establishment work and no additional compensation will be allowed therefor.

### **SECTION 10-3. SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS**

#### **10-3.01 DESCRIPTION**

Communication system routing (modify), modify lighting and sign illumination, and lighting and sign illumination (temporary) shall conform to the provisions in Section 86, "Signals, Lighting and Electrical Systems," of the Standard Specifications and these special provisions.

Lighting equipment is included in the following structures:

- A. Route 5 at Marietta Avenue Undercrossing (Bridge No. 53-1392L).
- B. Route 5 at Euclid Avenue Off-ramp Undercrossing (Bridge No. 53-1389L).
- C. Route 5 at Euclid Avenue Undercrossing (Bridge No. 53-0601).

Communication conduit is included in the following structures:

- A. Route 5 at Euclid Avenue Undercrossing (Bridge No. 53-1364).
- B. Route 5 at Euclid Avenue Undercrossing (Bridge No. 53-0601).

The Contractor shall confirm equipment placement with the Engineer before installing equipment.

### 10-3.02 ABBREVIATIONS AND GLOSSARY

The following abbreviations and glossary apply to these special provisions.

#### Abbreviations:

<b>&amp;</b>	And
<b>#</b>	number
<b>ADM:</b>	Add Drop Multiplexer.
<b>AFC:</b>	Automated Frequency Control.
<b>AGC:</b>	Automatic gain control.
<b>AIS:</b>	Alarm Indication Signal.
<b>AISI:</b>	American Iron and Steel Institute.
<b>AMI:</b>	Alternate Mark Inversion (a data transmission protocol.)
<b>APD:</b>	Avalanche Photo diode.
<b>APL:</b>	Average picture level.
<b>APS:</b>	Automatic Protection Switch.
<b>AVC</b>	Automatic vehicle classification system
<b>AWG</b>	American wire gauge
<b>AWM:</b>	Appliance Wiring Material.
<b>B8ZS:</b>	Bipolar 8 Zero Suppression(data transmission protocol)
<b>BER:</b>	Bit error rate.
<b>BERTS:</b>	Bit Error Rate Test Set.
<b>BITS:</b>	Building Integrated Timing Supply.
<b>BNC:</b>	Bayonet Navy Connector.
<b>bps:</b>	Bits per second.
<b>BPV:</b>	Bipolar Violation.
<b>CCD:</b>	Charge-Coupled Device.
<b>CCK:</b>	Camera Control Key pad.
<b>CCR:</b>	Camera Control Receiver
<b>CCT:</b>	Camera Control Transmitter.
<b>CCTV:</b>	Closed Circuit Television.
<b>NTR:</b>	Code of Federal Regulations.
<b>CIDH:</b>	Cast In Drilled Hole.
<b>CMIP:</b>	Configuration Management Information Protocol.
<b>CMISE:</b>	Common Management Information Service Entity.
<b>CMP:</b>	Configuration Management Plan.
<b>CMS:</b>	Changeable Message Sign.
<b>CODEC:</b>	Coder - Decoder.
<b>COMM</b>	Communication
<b>CPU:</b>	Central Processing Unit.
<b>CRT:</b>	Cathode Ray Tube.
<b>CTRL</b>	Controller
<b>DACCS</b>	Digital access and cross connection system
<b>D4:</b>	4th version of the D-signal format for time division multiplexers.
<b>dB:</b>	Decibel.
<b>dBm:</b>	Decibel referred to milliwatt.
<b>dBrn:</b>	Decibel above reference noise.
<b>DCD:</b>	Data carrier detect
<b>DCE:</b>	Data communication equipment.
<b>DTE:</b>	Data Circuit Terminating Equipment.
<b>DEMARC</b>	Demarcation
<b>DEMUX</b>	Demultiplexer
<b>DCS:</b>	Digital Cross-Connect System.
<b>DS-1:</b>	Digital Signal Level 1. Digital Transmission Rate - 1.544 megabits per second.
<b>DS-3:</b>	Digital Signal Level 3. Digital Transmission Rate - 44.876 megabits per second.
<b>DWP:</b>	LA Dept. of Water and Power
<b>EIA:</b>	Electronics Industries Association.

<b>ELA</b>	East Los Angeles
<b>EMT:</b>	Electrical Metallic Tubing.
<b>ESF:</b>	Extended Superframe or Extended Superframe Format (4).
<b>E/O</b>	east of
<b>FCC</b>	Federal Communications Commission
<b>F/O or FO:</b>	Fiber optic.
<b>FDf</b>	Fiber Distribution Frame
<b>FDU:</b>	Fiber Distribution Unit.
<b>FRP:</b>	Fiberglass Reinforced Plastic.
<b>FXS:</b>	Foreign Exchange Subscriber.
<b>GFCI:</b>	Ground Fault Circuit Interrupter.
<b>GUI</b>	Graphical User Interface.
<b>HAR:</b>	Highway Advisory Radio.
<b>HVAC:</b>	Heating Ventilation and Air Conditioning.
<b>Hz:</b>	Hertz.
<b>IRE:</b>	IRE is a SMPTE Standard video reference level.
<b>ITUR</b>	International Telecommunications Union Radio
<b>JKFD:</b>	Jackfield
<b>KP</b>	Kilometer Post
<b>LA</b>	Los Angeles
<b>M13:</b>	Multiplexer, 28 DS-1 circuits to 1 DS-3 circuit.
<b>MHz:</b>	Megahertz.
<b>MMFO:</b>	Multimode fiber optics
<b>MUX:</b>	Multiplexer
<b>NEMA:</b>	National Electrical Manufacturers Association.
<b>NHD</b>	North Hollywood
<b>nm:</b>	nanometer.
<b>NMS:</b>	Network Management System.
<b>NRZ:</b>	Non-return to Zero.
<b>NTSC:</b>	National Television Standards Committee.
<b>OC:</b>	Optical Channel.
<b>OD:</b>	Outside Diameter.
<b>OEM</b>	Original Equipment Manufacturer.
<b>OSHA:</b>	Occupational Safety and Health Administration.
<b>OW</b>	Order wire (Multiple voice circuit)
<b>P</b>	Pair
<b>P22</b>	Pair 22 American Wire Gauge
<b>PAC BELL</b>	Pacific Bell telephone Company
<b>p-p:</b>	Peak to Peak.
<b>PC:</b>	Personal Computer.
<b>PCMS:</b>	Pasadena City Municipal Services
<b>PDA</b>	Power distribution assembly
<b>PIN:</b>	P-type, intrinsic, N-type.
<b>PM:</b>	Post Mile
<b>PR</b>	Pair
<b>PRBS:</b>	Pseudo-Random Bit Sequence pattern.
<b>QRSS:</b>	Quasi-Random Signal Source.
<b>REA:</b>	United States Rural Electrification Administration.
<b>RETMA:</b>	Radio-Electronics-Television Manufacturers Association (Former name of EIA.)
<b>RF:</b>	Radio Frequency.
<b>RG:</b>	Regulatory Guide.
<b>RMS:</b>	Ramp Metering System.
<b>RMS:</b>	Root-mean-square.
<b>RTS:</b>	Request to send.
<b>SF:</b>	Superframe Format (D4).
<b>SM:</b>	Singlemode.
<b>SMFO:</b>	Singlemode Fiber Optic.

<b>SONET:</b>	Synchronous Optical Network.
<b>SSOVP:</b>	Solid State Over-voltage Protector.
<b>SSPC:</b>	Steel Structures Painting Council.
<b>ST:</b>	Type of Connector.
<b>TDM:</b>	Time Division Multiplexer.
<b>THHN:</b>	Heat Resistant thermoplastic with Nylon Jacket Conductor.
<b>THWN:</b>	Moisture and Heat Resistant Thermoplastic with Nylon Jacket Conductor.
<b>TIA:</b>	Telecommunications Industries Association.
<b>TL-1:</b>	Transaction Language 1.
<b>TLP:</b>	Transmission Level Point.
<b>TOSNET:</b>	Traffic Operational System Network
<b>TMC:</b>	Traffic Management Center.
<b>TSG:</b>	Test Signal Generator.
<b>TSI:</b>	Time Slot Interchange.
<b>UNC:</b>	Unified National Coarse.
<b>UNIX:</b>	Specific operating system found in real-time applications.
<b>UV:</b>	Ultraviolet.
<b>V:</b>	Volt.
<b>V(ac)</b>	V, Alternating Current.
<b>VID:</b>	Video Identification and Date/Time Display.
<b>VSK:</b>	Video switch keypad.
<b>VSM:</b>	Video switch matrix.
<b>VT-1.5:</b>	Virtual Tributary-Level 1.5 (1.728 Mb/s.).
<b>VT:</b>	Virtual Tributary.
<b>W:</b>	Watt.
<b>WFM:</b>	Waveform Monitor.
<b>WTO:</b>	Wire Transit Only.
<b>X.11, X.25:</b>	specific protocol standards generated by the International Telecommunications Union (formerly CCITT.)
<b>XHHW:</b>	Moisture and Heat Resistant Cross Linked Synthetic Polymer Conductor.

## Glossary:

**Breakout.**--The cable "breakout" is produced by (1) removing the jacket just beyond the last tie-wrap point, (2) exposing 0.9 m to 1.8 m of the cable buffers, aramid strength yarn and central fiberglass strength member, and (3) cutting the aramid yarn, central strength member and the buffer tubes to expose the individual glass fibers for splicing or connection to the appropriate device.

**Cable Storage Cabinet.**--A cabinet for holding excess cable slack for protection. The cable storage cabinet allows the user flexibility in equipment location and the ability to pull cable back for re-splicing.

**Channel.**--(1) An information path between a discrete input and a discrete output. (2) One single input to a multiplexer or output from a demultiplexer.

**Closed Circuit Television Assembly.**--Camera, lens, environmental enclosure, and necessary connectors and cables.

**Connector.**--A mechanical device used to provide a means for attaching to and decoupling from a transmitter, receiver, or another fiber (such as on a patch panel).

**Connectorized.**--A term that describes a fiber to which a connector has been affixed.

**Connector Module Housing (CMH).**--A patch panel used in the FDF to terminate singlemode fibers with most common connector types. It may include a jumper storage shelf and a hinged door.

**Couplers.**--Couplers are devices which mate two fiber optic connectors to facilitate the transition of optical light signals from one connector into another. Couplers may also be referred to as: adapters, feed-throughs, and barrels.

They are normally located within FDF's mounted in panels. They may also be used unmounted, to join two simplex fiber runs.

**Fiber Distribution Frame (FDF).**--A rack mounted system that is usually installed in the TMC that consists of a standard equipment rack, fiber routing guides, horizontal jumper troughs, fiber distribution units (FDU), connector module housings (CMH), and splice module housings (SMH).

The FDF serves as the "home" for the passive fiber optic components from cable breakout, for connection by jumpers, to the electronics.

**Fiber Distribution Unit (FDU).**--An enclosure containing both a Connector Module Housing (CMH) and a Splice Module Housing enclosure.

**Field Cabinet.**--A roadside cabinet used for housing controllers or communications equipment.

**Jumper.**--A short fiber optic cable that has connectors installed on both ends, and is typically used for connection within a FDF.

**Light Source.**--A portable piece of fiber optic test equipment that, in conjunction with a power meter, is used to perform end-to-end attenuation testing. It contains a stabilized light source operating at the designed wavelength of the system under test.

**Link.**--A passive section of the system, the ends of which are to be connected to active components. A link may include splices and couplers. For example, a video link may be from a F/O transmitter to a video Multiplexer (MUX).

**Mux/Demux.**--Multiplexer/Demultiplexer.

**Optical Time Domain Reflectometer (OTDR).**--Fiber optic test equipment (similar in appearance to an oscilloscope) that is used to measure the total amount of power loss between two points and the corresponding distance. It provides a visual and printed display of the relative location of system components such as fiber sections, splices and connectors and as the losses that are attributed to each component or defect in the fiber.

**Patchcord.**--A short jumper.

**Pigtail.**--Relatively short length of fiber optic cable that has a connector installed on only one end.

**Power Meter.**--A portable piece of fiber optic test equipment that, in conjunction with a light source, is used to perform end-to-end attenuation testing. It contains a detector that is sensitive to light at the designed wavelength of the system under test. Its display indicates the amount of power injected by the light source that arrives at the receiving end of the link.

**Segment.**--A section of F/O cable that is not connected to any active device and may or may not have splices per the design.

**Splice Closure.**--Normally installed in a splice vault, a splice closure is an environmentally sealed container used to organize and protect splice trays. The container allows splitting or routing of fiber cables from multiple locations.

**Splice Module Housing (SMH).**--The SMH stores splice trays as well as pigtails and short cable lengths.

**Splice Tray.**--A container used to organize and protect spliced fibers.

**Splice Vault.**--A splice vault is used to house splice closures.

### 10-3.03 COST BREAK-DOWN

Cost break-downs shall conform to the provisions in Section 86-1.03, "Cost Break-Down," of the Standard Specifications and these special provisions.

The Engineer shall be furnished a cost break-down for each contract lump sum item of work described in this Section 10-3.

The cost break-down shall be submitted to the Engineer for approval within 15 days after the contract has been approved. The cost break-down shall be approved, in writing, by the Engineer before any partial payment for the items of electrical work will be made.

The cost breakdown shall include the following items in addition to those listed in the Standard Specifications:

- A. Communication pull boxes.
- B. Fiber optic cables – each size.
- C. Twisted pair cables – each size.
- D. Fiber optic splice closures.
- E. Twisted pair cables splice closures.
- F. Conduits-each size and installation method.
- G. System testing.

#### **10-3.04 MAINTAINING EXISTING AND TEMPORARY ELECTRICAL SYSTEMS**

Existing and/or temporary lighting systems shall be maintained on, during normal hours of operation.

Attention is directed to Section 7-1.11, "Preservation of Property", of the Standard Specifications and these special provisions.

The Contractor shall obtain written approval from the Engineer, not less than 72 hours prior to any system cutover, disconnection of service from existing individual electrical systems for existing lighting and sign illumination, and communication system routing, including, but not limited to, ramp metering system (RMS) and traffic (count) monitoring system (TMS).

#### **MAINTAINING EXISTING COMMUNICATION SYSTEM ROUTING FACILITIES**

Existing communication system routing facilities are located within the project limits and may conflict with construction operations. In areas where excavation operations are performed, the Contractor shall notify the Engineer a minimum of 72 hours, prior to starting work and obtain as-built plans for the area. The Engineer will advise the District Office of Intelligent Transportation System (ITS) of the Contractor's scheduled work.

An individual electrical system for communication system routing shall be considered to be "offline" for the duration of time that it is disconnected from AC power and disrupted from active communications with the District Transportation Management Center (TMC), such that the equipment cannot be controlled through the exercise of remote control commands from the TMC.

The Contractor and the Engineer shall jointly conduct a pre-construction check of the existing communication system routing elements. The Engineer will determine the exact location of existing communication system routing elements including, but not limited to, closed circuit television camera (CCTV), fiber optic cables, conduits, communication pull boxes of various types and splice vaults, prior to the Contractor beginning excavation operations. The Engineer will maintain the records of the pre-construction check of the existing communication system routing elements.

Existing communication system routing elements shall remain in place and shall be protected from damage.

The Contractor shall use hand tools to perform work involved in excavating, relocating, repairing, replacing and removing existing communication system routing field elements, and devices. If part of the existing communication system routing elements is damaged or failed by the Contractor's operations, the Engineer shall be notified immediately and the damaged communication system routing elements shall be repaired or replaced, at the Contractor's expense, within 5 working days. Replaced communication system routing elements shall be new, of equal or better quality than the damaged communication system routing elements.

The Engineer shall approve replacement methods and replaced facilities, including communication conduit types, bend radius and fusion splicing of all fiber optic cables, in advance and in writing.

In the event the fiber optic cables are damaged due to the Contractor's operations, the Contractor shall install new fiber optic cables from an original splice point to an original splice point, unless otherwise authorized in writing by the Engineer, but in no case shall the fiber optic cable be spliced other than at an existing splice vault.

The amount of new fiber optic cable slack in the splice vault and the number of new fiber optic cable splices shall be the same as the original. Fusion splicing is required for all fiber optic cables.

After repair or replacement of such facilities is complete, the Contractor shall demonstrate to the Engineer that the repaired or replaced facilities operate in the manner identical to that prior to the damage. Should the Contractor fail to perform the required repair or replacement work, as determined by the Engineer, the State will perform the repair or replacement work, and the cost of performing such repairs or replacement work shall be deducted from any money due or to become due to the Contractor. Electrically related construction on this project may be suspended, as determined by the Engineer, until all repairs and replacement works have been completed.

Works of maintaining existing communication system routing, including removing, relocating, repairing and replacing the existing communication system routing elements, including post-construction testing, ordered only by the Engineer, and further repairs required thereafter as ordered only by the Engineer, except as otherwise provided under "Existing Highway Facilities" of these special provisions, will be paid for as extra work in "Maintain Existing Communication System Routing Facilities" and as provided in Section 4-1.03D of the Standard Specifications.

Full compensation for pre-construction check of the existing communication system routing facilities shall be considered as included in the contract lump sum price paid for communication system routing (modify) and no additional compensation will be allowed therefor.

### **10-3.05 LIGHTING (TEMPORARY)**

The temporary lighting system (TLS) shall consist of installing and maintaining temporary lighting in conformance with the details shown on the plan entitled "Lighting and Sign Illumination (Temporary)" and in "Maintaining Traffic" of these special provisions.

The provisions in this section shall not relieve the Contractor from the responsibility to provide the additional devices or take the measures as may be necessary to conform to the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications.

Materials and equipment for a temporary lighting system including, but not limited to, mast arms, luminaires, wood poles, conductors, and hardware shall be furnished by the Contractor.

Materials and equipment to be used in the temporary lighting system shall either be new, or used, suitable for the intended use.

**Operations.**--Temporary lighting system shall operate at 120 / 240 V.

**Maintaining temporary lighting system.**--Maintaining a temporary lighting system shall be the sole responsibility of the Contractor. If components in the temporary lighting system are damaged, displaced, or cease to operate, or function as specified, from any cause during the progress of the work, the Contractor shall immediately repair the components to the original condition or replace the components and shall restore the components to the original location.

**Conduit.**--Attention is directed to "Conduit" of these special provisions.

**Conductors and Wiring.**--Conductors and wires shall be the types specified in Section 86-2.08, "Conductors," of the Standard Specifications or shall be Type UF cable of the size and number of conductors shown on the plans. Where conductors are to be placed across paved areas, the conductors shall be placed in conduit.

Conductors to be placed outside of paved areas shall be suspended from wood poles with a minimum clearance as conductors shown on the plans.

**Bonding and grounding.**--Temporary lighting system shall be mechanically and electrically secured to form a continuous system that is effectively grounded by the grounding conductor.

**Service.**--Existing commercial electrical power is available at the work site.

**Luminaire.** Luminaire shall have integral ballast.

**Removing temporary lighting system.**--Upon completion of the work requiring temporary lighting system, as determined by the Engineer, components of the temporary lighting system shall become the property of the Contractor and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Materials Outside the Highway Right of Way," of the Standard Specifications. Pole holes shall be back-filled.

### **10-3.06 COMMUNICATION SYSTEM ROUTING**

Communication system routing consists of, but not limited to, communication conduits, fiber optic cables, and twisted pair cables, of various types and sizes, communication pull boxes, various field element sites such as closed circuit television camera, fiber optic video node, data node, cable node, ramp metering system, and traffic monitoring/count station, at various locations, and the existing East Los Angeles (ELA) Hub building.

Modifying works on the existing communication system routing shall conform to all rules and regulations of the Federal Communications Commission (FCC) and these special provisions.

Prototype equipment is not acceptable. All new equipment shall be current standard production units and shall have been in production for a minimum of six months. Rebuilt or reconditioned equipment will not be allowed.

Before working on the existing communication system routing, the Contractor shall perform the jointly conducted pre-construction check with the Engineer according to "Maintaining Existing and Temporary Electrical Systems," elsewhere in these special provisions, and shall submit a test plan, in accordance with manufacturer's specifications, for approval in advance by the Engineer, also as described elsewhere in these special provisions.

The test plan is also to verify that all existing equipment is functional before construction and to record the working condition of that equipment.

The Contractor may arrange, at the Contractor's own expenses, to have a technician, qualified to work on existing communication system routing equipment or employed by the communication system routing equipment manufacturer, or manufacturer's representative, present at the time the communication system routing equipment is installed or modified.

Except for testing and verification of the condition of the existing communication system routing before and after the work on the existing communication system routing, the scope of the Contractor's work shall be as shown on the plans.

### **COMMUNICATION SYSTEM ROUTING (MODIFY)**

Communication system routing (modify) works shall consist of, but not limited to, removal and disposal of existing fiber optic and twisted pair cables, fiber optic and twisted pair splice closures, innerducts, pull boxes, of various sizes and types, furnishing and installing a new and permanent communication conduit routing, including conduits, innerducts, pull boxes, fiber optic and twisted pair cables, fiber optic and twisted pair splice closures, of various sizes, types, and installation methods, re-splicing new fiber optic and twisted pair cable installation to current wiring configuration, and reconnecting existing East Los Angeles (ELA) Hub Building, CCTV camera PO 001, and ramp metering systems 0148 and 0598, system testing, and system cut-over, to restore the full functionality of the existing communication system routing that is impacted by the soundwall construction, within the contract limits, complete in place, as shown on plans and as directed by the Engineer.

The existing CCTV camera PO 001 consists of Type 334-TV cabinet and control equipment, CCTV camera assembly which includes pan and tilt unit, color video camera, camera lens and camera housing, camera control receiver (CCR), video transmitter and camera control circuits and accessories, CCTV wiring which includes enclosed, or outdoor, cables for video and camera control, connectors and coaxial cables, camera pole, camera junction box, and other equipment, as shown on plans.

The existing ramp metering systems 0148 and 0598 consist of Type 334 cabinets and control equipment, detector loop lead-in cables, inductive loop detectors and connectors as shown on plans.

The Contractor shall modify the system elements as part of the communication system routing in accordance with manufacturer's specifications, as shown on the plans and as directed by the Engineer, to provide a fully functional communication system routing.

The Contractor shall arrange to have a technician, qualified to work on the communication system routing equipment, or employed by the communication system routing equipment manufacturer or his representative, present at the time the communication system routing equipment is modified or reconnected.

CFIn order to minimize the down time of the existing communication system routing, the Contractor shall perform the "communication system routing (modify)" work prior to the commencement of any road works, as provided under "Order of Works", described elsewhere in these special provisions, as shown on the plans, as directed by the Engineer, and in the following order:

1. The Contractor shall perform the jointly conducted pre-construction check with the Engineer, as provided under "Maintaining Existing Communication System Routing Facilities," described elsewhere in these special provisions.
2. The Contractor shall install the new communication conduits in trench, attach 2 size 103 communication conduits (bridge), and install 4 size 78 communication conduits in structure, as shown on the plans, as provided under "communication conduits (bridge)," described elsewhere in these special provisions, and as directed by the Engineer.
3. The Contractor shall install new 100P22, 12 SMFO and 18 MMFO cables, in the existing spare communication conduit, and in the new communication conduit, from the existing East Los Angeles (ELA) Hub building to the existing splice vault located east of Euclid Avenue Undercrossing, as shown on the plans, and as directed by the Engineer.  
The Contractor shall maintain the existing communication system routing active until the aforementioned 100P22, 12 SMFO, and 18 MMFO cables are installed.
4. The Contractor shall disconnect the existing 100P22, 12 SMFO, and 18 MMFO cables at the East Los Angeles Hub building. The Contractor shall disconnect all other existing break-out cables that are spliced to the existing communication system routing trunk line cables at the respective existing cable splice closures as shown on the plans, and as directed by the Engineer.

5. The Contractor shall splice new 100P22, 12 SMFO, and 18 MMFO cables with the existing 100P22, 12 SMFO, and 18 MMFO cables at the existing splice vault located east of Euclid Avenue Undercrossing, as shown on plans, and as directed by the Engineer. All cable splices shall be matched in current wiring configuration to prevent cross connection. All other disconnected break-out cables shall be connected (spliced) to the new communication system routing trunk line cables and shall be restored to its pre-construction state as shown on plans, and as directed by the Engineer.
6. The Contractor shall terminate new 100P22, 12 SMFO, and 18 MMFO cables at the East Los Angeles Hub building, as shown on the plans, and as directed by the Engineer.
7. The Contractor shall perform system testing work as provided under "System Testing," described elsewhere in these special provisions
8. The Contractor shall remove and dispose the existing 100P22, 12 SMFO, and 18 MMFO cables from the existing East Los Angeles Hub building to the existing splice vault located west of Euclid Avenue Undercrossing, as shown on the plans, and as directed by the Engineer.

Except for verification and testing of the condition of the existing communication system routing before and after the communication system routing (modify) work, the scope of the Contractor's work shall be as shown on the plans.

Attention is directed to "System Testing," elsewhere in these special provisions, regarding testing the modified communication system routing.

### 10-3.07 CONDUIT

Conduit to be installed underground shall be Type 1 unless otherwise specified. The Contractor shall install tapes in all various empty innerducts and conduits. Type 3 conduit shall be used for communication trunk line.

Communication conduit shall be installed by the methods shown on the plans, as specified in these special provisions, and as directed by the Engineer. A flat, woven, lubricated, polyester tape with a minimum tensile strength of 80 kN minimum shall be placed in conduits. At least 1.2 m of tape shall be extended beyond termination.

The conduit in a foundation and between a foundation and the nearest pull box shall be Type 1.

Conduit sizes shown on the plans and specified in the Standard Specifications and these special provisions are referenced to metallic type conduit. When rigid non-metallic conduit is required or allowed, the nominal equivalent industry size shall be used as shown in the following table:

Size Designation for Metallic Type Conduit	Equivalent Size for Rigid Non-metallic Conduit
21	20
27	25
41	40
53	50
63	65
78	75
103	100

When a standard coupling cannot be used for joining Type 1 conduit, a UL listed threaded union coupling conforming to the provisions in Section 86-2.05C, "Installation," of the Standard Specifications.

When Type 3 communication conduit is placed in a trench, after the bedding material is placed and the conduit is installed, the trench shall be back-filled with slurry cement backfill conforming to the requirements in Section 19-3.062 of the Standard Specification, except the maximum size of aggregate shall be 10 mm (pea gravel), and containing not less than 250 kg of portland cement per cubic meter, and commercial quality cement sand to not less than 100 mm above the conduit before additional backfill material is placed.

In those areas where a jacking pit in a concrete shoulder is necessary to jack conduit across a roadway and the work has not been completed in a work shift the Contractor shall cover the jacking pit with steel plates after each completed work day. When the work has been completed in a particular jacking area the surface must be restored to its original condition. When conduit is placed in a trench under paved shoulder, after the bedding material is placed and conduit installed, the trench shall be back-filled with cement slurry backfill as specified above to a minimum of 25 mm of existing shoulder surface.

Conduits located within the same trench shall have not less than 50 mm separation.

Trenches shall be less than or equal to 200 mm width.

The Contractor's attention is directed to "Aerially Deposited Lead" of these special provisions.

Immediately prior to installing conductors, cables and innerducts, all conduits shall be blown out with compressed air until all foreign material is removed.

After conductors have been installed, the ends of conduits terminating in various pull boxes and service equipment enclosures shall be sealed with an approved type of sealing compound.

Conduit shall not be installed by trenching along the pavement of freeway lanes except in sections of the highway where there is insufficient clearance to locate a longitudinal trench off the traveled way, or where obstructions off the traveled way would necessitate bends in the conduits in excess of those allowed.

Where conduits are shown on the plans to be installed parallel and adjacent to each other, the conduits shall be installed together in a common trench as shown on the conduit installation details. Trenching in pavement method is not allowed across freeway lanes, connectors, and ramps.

### **COMMUNICATION CONDUIT**

Communication conduit shall conform to the provisions specified above under "Conduit" and the following.

Communication conduit shall include excavation, installation of the communication conduit, and placing sand and slurry cement backfill.

Excavation and slurry cement backfill shall conform to Section 19-3, "Structure Excavation and Backfill," of the Standard Specifications. The slurry cement backfill shall reach initial set prior to placing of reinforced concrete for the approach slab.

Conduit shall enter splice vault and communication pull boxes through knockouts. Conduits entering the ends of these communication boxes shall be vertically and horizontally aligned with the conduits at the opposite end of the communication box. Conduit ends shall not extend beyond the interior wall face of splice vault and communication pull boxes. The space around conduits through end walls of splice vault and communication pull boxes shall be filled with Portland cement mortar conforming to the provisions in Section 51-1.135, "Mortar," of the Standard Specifications. In no case shall a conduit body or communication pull box be used in lieu of a specified bend to change the direction of the communication conduit run, except where specified.

No bends shall be placed in a section of conduit in excess of those indicated in the plans without the approval of the Engineer. The total degrees of bending in a section of conduit between splice vaults and communication pull boxes shall not exceed a total of 180 degrees, except where specified otherwise.

Changes in indicated conduit bends may be made in order to suit field conditions, as long as the change reduces the degree of the bend or increases the radius of the bend. In no case shall the angle of the bend be increased without the approval of the Engineer.

Minimum bending radius for Size 53 communication conduit shall be 610 mm and minimum bending radius for Size 103 communication conduit shall be 1220 mm. Bends of greater than 22 degrees shall be factory bends and bends greater than 45 degrees shall galvanized rigid steel with any necessary adapters.

Deflections from the indicated communication conduit routing to avoid obstructions shall not exceed 83.3 mm/m. Conduit from the typical trench sections shall not deflect by more than 83.3 mm/m from the alignment preceding or following communication pull boxes and splice vault.

Where edge drains are in the path of conduit routing the Contractor must first locate the edge drains and install the conduit maintaining a minimum depth. In the event an edge drain is damaged by the Contractor's work, the repair shall be at the Contractor's expense.

Adjacent to over crossings or bridge foundations, the Contractor shall trench and install conduit in the shoulder as close as possible to the edge of traveled way so that a minimum of 1.5 m from the outside face of footing or pile cap is maintained.

Full compensation for conduits shall be considered as included in the contract lump sum price paid for communication system routing (modify) and no additional compensation will be allowed therefor.

### **10-3.08 WARNING TAPE**

Warning tape shall be furnished and installed in the trench, over new conduits to receive reinstalled or new fiber optic cables, as shown on the plans. The warning tape shall consist of 100 mm wide bright orange pigmented polyolefin film with a bold printed message of approximately 19 mm black characters on one side. The message shall be: "CAUTION: BURIED FIBER OPTIC CABLE - CALTRANS (213) 897-0340," repeated at approximately 910 mm intervals.

The warning tape shall not delaminate nor shall the message smear when wet. The tape and the printed message shall be resistant to insects and shall not degrade when exposed to alkalis, acids and other corrosive elements commonly found in soil. It shall have a minimum of 356 N tensile strength and a minimum of 700 percent elongation before breakage.

Warning tape shall be Condux International, Inc.; Allen System, Inc.; Reef Industries, Inc. or equal.

Full compensation for warning tape shall be considered as included in the contract lump sum price paid for communication system routing (modify) and no additional compensation will be allowed therefor.

### 10-3.09 COLORED CEMENT BACKFILL

The slurry cement backfill for the installation of communication conduits that will contain fiber optic cable shall be a medium to dark, red or orange color to clearly distinguish the concrete backfill from other concrete and soil. The concrete shall be pigmented by the addition of commercial quality cement pigment to the concrete mix. The red or orange concrete pigment shall be LM Scofield Company; Orange Chromix Colorant; Davis Colors; or equal.

For trenches in pavement areas, only the top 100 mm of slurry cement backfill will be required to be pigmented concrete. At the option of the Contractor, the full depth may have the pigment.

Full compensation for furnishing and incorporating the cement pigment to achieve the color required shall be considered as included in the contract lump sum price paid for communication system routing (modify) and no additional compensation will be allowed therefor.

### 10-3.10 0.5 MM PLASTIC SHEET

The 0.5 mm plastic sheet shall be furnished and installed in the trench within roadway pavement, approximately 3 cm over new communication conduits, as shown on the plans, and as directed by the Engineer. The plastic sheet will serve as a breaking plane within the slurry cement backfill. The plastic sheet shall be manufactured from high-density polyethylene (HDPE) virgin compounds or polyvinyl chloride (PVC) virgin compounds.

Full compensation for 0.5 mm plastic sheet shall be considered as included in the contract lump sum price paid for communication system routing (modify), and no separate payment will be made therefor.

### SIZE 103 COMMUNICATION CONDUIT (BRIDGE)

At the location shown on the plans, where communication conduits are to be installed on bridge, fiberglass conduit shall be used and shall conform to the details shown on the plans, and to these special provisions. Communication conduit (bridge) shall include excavation, installation of the fiberglass conduit, and placing sand and slurry cement backfill.

Excavation and slurry cement shall conform to Section 19-3, "Structure Excavation and Backfill," of the Standard Specifications. The slurry cement backfill shall reach initial set prior to placing of reinforced concrete for the approach slab.

#### Fiberglass Conduit

**General.**--Fiberglass conduit and components shall comply with the specifications in ANSI/NEMA Standards Publication TC-14A or TC-14B. All fiberglass conduit components shall be free of defects including delaminating, foreign inclusions, etc. All fiberglass conduit components shall be nominally uniform (as commercially practical) in color, density, and physical properties. Fiberglass conduit shall be straight and the ends shall be cut square and true.

The Contractor shall purchase all fiberglass conduits and other fiberglass conduit system components from the same manufacturer to insure component compatibility.

**Conduit Sizes.**--Fiberglass conduit shall be supplied in 6 m minimum lengths.

**System Components.**--Fiberglass conduit components shall include compatible fittings, adapters, expansion joints, and factory bends at nominal radii of 0.6 m, and 1.3 m for Size 53, and 103 conduits, respectively.

**Material.**--All fiberglass conduit system components shall be produced from heat cured, corrosion resistant epoxy resin and continuous fiberglass roving. All materials shall be manufactured for use at temperatures from -40°C to 110°C. All fiberglass conduit components shall be manufactured using a homogeneously dispersed UV inhibitor. When exposed to direct diurnal sunlight, the UV inhibitor shall prevent the degradation of all physical material properties, except for surface cosmetic appearance. Materials shall contain no halogens above trace levels and shall be fire resistant.

**Joining Method.**--Joints shall be watertight and withstand a minimum 4450 N of pullout tension.

**Stiffness.**--For all sizes of fiberglass conduit, under a load of 1.3 kN/m of conduit, the deflection of the inside diameter shall not exceed 5 percent.

**Impact Resistance.**--The minimum impact resistance values for the fiberglass conduit shall be as follows when measured as described in ASTM Designation: D2444-70, using a 9 kg.tup "B" with a 50 mm radius nose:

Size 53 conduit	40 N/m.
Size 103 conduit	108 N/m.

## **BRIDGE METAL SUPPORTS**

Wrapping tape for pipe in contact with the earth shall be a pressure sensitive polyvinyl chloride or polyethylene tape with a minimum thickness of 1.27 mm.

Pipe hanger assemblies shall consist of a concrete clevis plate or embedded steel welded linked eye rods, an adjustable steel yoke, a cast iron pipe roller rod and hex nuts. Parts shall be galvanized. The pipe hanger assembly shall be suitable for the type and size of pipe installed and shall be as shown on the plans.

Anchor bolts, pipe clamps, nuts and bolts, and other fittings shall be suitable for the type and size of the supply lines or casing and shall conform to the provisions in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

Bridge metal supports shall consist of galvanized steel pipe clamp, 2 anchor bolts and, where shown on the plans, a stainless steel pipe protection shield.

Epoxy adhesive shall conform to the provisions in Section 95-1, "General," of the Standard Specifications and at the option of the Contractor, shall conform to the provisions in Section 95-2.03, "Epoxy Resin Adhesive for Bonding New Concrete to Old Concrete," or in Section 95-2.04, "Rapid Set Epoxy Adhesive for Pavement Markers," or in Section 95-2.05, "Standard Set Epoxy Adhesive for Pavement Markers," of the Standard Specifications.

Full compensation for mechanical expansion bolt anchors, steel brackets and other fittings, pipe wrapping tape, epoxy adhesives, and conduit expansion fittings and incidentals shall be considered as included in the contract unit price paid per meter for communication conduit (bridge) and no additional compensation will be allowed therefor.

### **10-3.11 SIZE 53 INNERDUCT**

Wherever fiber optic cable is used, innerduct shall be installed to provide protection for the fiber optic cable. A separate innerduct shall be installed for each fiber optic cable along the communication mainline as shown on the plans.

All innerduct shall be 53 mm, smooth, ribbed or corrugated high tensile polyethylene duct. Innerduct shall have the following characteristics:

Inner diameter greater than or equal to 53 mm, nominal.

Environmental stress crack resistance in excess of 2000 hours at - 100°C, no failures.

Cold impact resistance to -76°C not brittle until -100°C.

Minimum tensile strength of 2670 N for finished product.

Minimum crush strength of 2900 N.

Coefficient of friction shall be less than 0.4 un-lubricated on nonmetallic conduit and with common polyethylene cable jackets.

Different innerducts within the same conduit shall be different colors, and shall be consistent throughout the project. The colors shall be yellow for the 18 MMFO fiber optic cables used for video/data and contrasting color approved by the Engineer for the 12 SMFO for video distribution. The exterior of the innerduct shall be marked with sequential measurement markings each meter.

Innerduct shall be installed using the manufacturer's recommended practices. A manufacturer recommended lubricant shall be applied between the innerduct and the conduit during installation to reduce friction. Innerduct shall be installed using a cable pulling lubricant recommended by the innerduct manufacture and a non-abrasive pull tape conforming to the provisions described under "Conduit" elsewhere in these special provisions. If innerduct is to be installed with adjacent cables in the same conduit, the innerduct and the cable shall be installed together in one operation. Innerduct shall be installed in continuous runs between communication pull boxes and splice vaults without splices or joints.

All ends shall be smoothed to prevent scraping of the cable. A dynamometer shall be used to record installation tension and a tension-limiting device shall be used to prevent exceeding the maximum pulling tension during installation. A breakaway device shall be used to limit the pulling tension. One device shall be placed in series with every element rated for less than the maximum pulling tension of that element. The innerduct shall not be stressed beyond the minimum-bending radius allowed by either the innerduct or fiber optic cable manufacturer.

The tension shall be set to the manufacturer's maximum limit. The maximum pulling tension shall be recorded for each innerduct run.

Immediately prior to installing cables, innerduct shall be blown out with compressed air until all foreign material is removed. After cables have been installed, the ends of innerducts shall be sealed with an approved type of sealing compound.

Full compensation for innerduct shall be considered as included in the contract lump sum price paid for communication system routing (modify) and no additional compensation will be allowed therefor.

### 10-3.12 PULL BOXES

Grout shall not be placed in the bottom of pull boxes.  
All Type 9A pull boxes shall come equipped with 78C knockout.

#### COMMUNICATION PULL BOXES

Communication pull boxes and covers shall have a vertical proof-load strength of 111 kN. The 111 kN load shall be distributed through a 229 mm x 229 mm x 51 mm steel plate according to Federal Specification RR-F-621e. This load shall be placed anywhere on the box and cover for a period of one minute without causing any cracks or permanent deformations.

The communication pull boxes shall be reinforced with a galvanized Z-bar welded frame and cover similar to that shown on the plans for No. 6(T) boxes. Frames shall be anchored to the boxes by means of 6 mm x 57 mm long concrete anchors. Six concrete anchors shall be provided for each communication pull box, one placed in each corner and one placed near the middle of each of the longer sides.

Hold down screws shall be 9 mm hex flange cap screws of Type 316 stainless steel. The nut shall be zinc plated carbon steel and shall be made vibration resistant with a wedge ramp at the root of the thread. The nut shall be spot welded to the underside of, or fabricated with, the galvanized Z-bar pull box frame.

Steel covers shall be countersunk approximately 6 mm to accommodate the bolt head. The bolt head shall not extend more than 3 mm above the top of the cover when tightened down. A 6 mm tapped hole and brass-bonding screw shall be provided.

Communication pull boxes shall have "CALTRANS COMMUNICATION" marking on the steel cover.

The opening of communication pull boxes shall have the following dimensions.

Pull Box Type	Width (±25 mm)	Length (±25 mm)
Communication	432 mm	762 mm

Concrete placed around and under communication pull boxes as shown on the plans shall contain a minimum of 325 kg of cement per cubic meter.

After the installation of communication pull boxes, the steel covers shall be installed and kept bolted down during periods when work is not actively in progress at the pull box. When placing the steel cover for the final time, the cover and the Z-bar frame shall be cleaned of all debris and securely tightened down.

Communication pull boxes shown on the plans in the shoulder are shown for general location only. The exact location shall be outside the paved shoulder and shall be determined by the Engineer.

Additional pull boxes for communication shall not be installed without the Engineer's written approval. All communication pull boxes outside of the structures shall be installed in the unpaved area immediately adjacent to the paved shoulder, or behind guardrail, or to be determined by the Engineer. Communication conduit shall be directed from the shoulder to the boxes with 15-degree (maximum) sweeps. Dikes shall be replaced in kind, as necessary.

Full compensation for replacing the dikes shall be considered as included in the contract lump sum price paid for communication system routing (modify) and no additional compensation will be allowed therefor.

Full compensation for pull boxes of various sizes and types shall be considered as included in the contract lump sum price paid for communication system routing (modify) and no additional compensation will be allowed therefor.

### 10-3.13 CONDUCTORS AND WIRING

Splices shall be insulated by "Method B".

The minimum insulation thickness, at any point, for Type USE, RHH or RHW wire shall be 1.0 mm for conductor sizes No. 14 to No. 10, inclusive, and 1.3 mm for No. 8 to No. 2, inclusive. The minimum insulation thickness, at any point, for Type THW and TW wires shall be 0.69 mm for conductor sizes No. 14 to No. 10, inclusive, 1.02 mm for No. 8, and 1.37 mm for No. 6 to No. 2, inclusive.

Twisted pair cables and fiber optic cables are provided in the following sections of these special provisions.

#### TWISTED PAIR CABLE

Twisted pair cable shall be supplied in the configurations shown on the plans and specified in these special provisions. The twisted pair cable shall meet the requirements of REA Specification PE-39 and the following:

Conductors shall consist of a solid wire of plain annealed high conductivity copper, smoothly drawn, circular in section, uniform in quality, free from defects and having a conductor size of number 22 AWG. Each conductor shall be insulated with a colored, high-density polyethylene jacket.

Insulated conductors shall be uniformly twisted to form pairs. The twisted length of the pairs shall vary to minimize cross talk. A non-hygroscopic dielectric tape shall be wrapped around the insulated pairs. A laid up core shall be wrapped with aluminum tape and bonded with an overlap to provide 100 percent shielding. A black, high molecular weight, medium or low density, polyethylene jacket shall be extruded over the shield. Filling compound materials used in the cable shall not support galvanic action.

The cables shall be color-coded using the REA standard color code.

**Packing.**--The cable shall be supplied on reels. Each reel shall be transported to the site using cable reel trailers and shall have the following information clearly labeled on it:

Customer  
Customer order number  
Reel number  
Destination  
Ship date  
Manufactured date  
Manufacturer's name  
Cable code  
Length of cable  
Manufacturers Test Data

Cable shall be transported to the project site using cable reel trailers. Care shall be taken at all times to avoid scraping, denting, or otherwise damaging the cable before, during, or after installation. The Contractor without additional compensation shall replace damaged cable.

**Installation.**--Cable shall be installed in duct in the field in accordance with the plans. Duct ends shall have all rough ends smoothed to prevent scraping the cable. A manufacturer recommended lubricant should be applied to the cable to reduce friction between the cable and the duct. Mechanical aids and pulling cable or ropes shall be used as required. Personnel shall be stationed at each cabinet, splice vault and communication pull box through which the cable is to be pulled to observe and lubricate the cable. All exposed cable ends shall be protected from moisture ingress.

The cable shall not be stressed beyond the manufacturer's minimum bending radius at any time. A dynamometer shall be used to measure installation tension and a tension-limiting device shall be used to prevent exceeding the manufacturer's maximum pulling tension specification during installation. The tension limit shall be set at or below the manufacturer's maximum limit. The maximum measured pulling tension shall be recorded for each run of cable.

A single loop of cable, with a minimum length of 3.0 m, shall be provided at each communication pull box in accordance with the plans. Cable shall be trained to the splice vault wall, tied with nylon ties and labeled with vinyl marking bands.

A minimum of 12 m of slack shall be provided for each unspliced cable at each splice vault.

Following installation of the cable in the duct, all duct entrances at pull boxes, vaults and cabinets shall be sealed with duct sealing compound to prevent the ingress of moisture, foreign materials, and rodents. The cables shall be spliced, maintaining the pair count and REA color code. Cable markers shall be used to identify the cable and pair-count. All field splices shall be made in twisted pair splice closures located in the splice vaults. The cable shall be securely fastened in place within communication pull boxes, splice vaults, and field cabinets.

**Testing.**--The Contractor is responsible for all testing and documentation required establishing approval and acceptance of the cable, its installation and in operation during the system integration testing. The following identifies the specific quality control requirements for this specification.

Cables shall be tested at the factory to ensure the cable complies with the manufacturer's specifications. The Contractor shall record the reel number from which the cable came, the identification of the pairs measured, and the results of continuity and insulation tests. Half of the twisted wire pairs in each reel of cable shall be tested for insulation breakdown and continuity prior to installation in ducts.

As a post-installation check, the Contractor shall measure the continuity and insulation resistance of the cable pairs in each length of cable after installation. The Contractor shall measure these parameters on each pair and record and submit the results to the Engineer.

The twisted-pair cable testing consists of testing the trunk cable and drop cable. After all cable pairs are terminated, the Contractor shall test the continuity of the cable, looking for grounds, opens, shorts, and splits. Any anomalies shall be corrected.

The Contractor shall measure and record the loop resistance and insulation integrity of all twisted-pair between terminations. The measured value shall not deviate from the calculated loop resistance of the cable by more than 10 percent.

The Contractor shall carry out system integration testing to ensure that the twisted-pair cables perform as specified when used in operation with equipment installed under these special provisions and plans.

Full compensation for furnishing, installing, connecting, terminating and testing new twisted pair cables, of various sizes and types, and disconnecting, removing, and disposing existing twisted pair cables, of various sizes and types, shall be considered as included in the contract lump sum price paid for communication system routing (modify) and no additional compensation will be allowed therefor.

#### **10-3.14 TWISTED PAIR SPLICE CLOSURE**

Twisted-pair splice closures shall come in two sizes: 305 mm and 610 mm. The closures shall be installed inside communication pull boxes or splice vaults for every drop from the twisted-pair cable to an equipment location and at mid-span splices as shown on the plans and shall conform to the following.

The twisted-pair splice closure shall consist of a neoprene sleeve, and shall be secured with hose clamps.

The twisted-pair splice closure shall have external dimensions not exceeding 610 mm in length by 76 mm in diameter. In the communication pull boxes, the length shall be limited to 305 mm. The twisted-pair splice closure shall consist of a neoprene sleeve, and shall be secured with hose clamps. The closure shall protect the cable splices from water and mechanical damage and shall be resistant to salt corrosion. All material of the twisted-pair splice closure and associated mounting accessories shall be non-reactive and the completed assembly shall not support galvanic cell action. The twisted-pair splice closure shall be waterproof, encapsulated with re-enterable material, and shall be sealed with a gasket. Wire connections shall be of the insulation displacement type with water blocking gel, (3-M Scotchlocks, AMP Pica-bonds, or equivalent). The manufacturer's instructions shall be explicitly followed during installation of the twisted-pair splice closure.

The closure shall be mounted securely inside the communication pull box or vault as shown on the plans. The closure shall be properly grounded and the cable sheaths bonded using bonding clamps. The cables shall be identified as "IN" or "OUT" depending upon their location relative to the splice (toward the communications node or away from the communications node). A tape collar shall be placed around the two cables and the drop cable at the location required by the splice closure. The splice closure shall be fitted to the splice and the hose clamps tightened over the cables.

Each pair of the drop cable shall be properly spliced to the designated pair in the cable as indicated in the twisted-pair splice tables. The splice conductors shall be securely crimped onto the wires, using manufacturer approved installation tools.

The closures shall be provided along with a splice kit, which shall contain all hardware items. Hardware shall include, but not be limited to, vinyl tape, bonding clamps, splice connectors, No. 14 AWG, insulated wire, spacer tapes, and terminal lugs.

Continuity shall be tested and confirmed prior to final assembly of the splice closure. After installing, splicing, and terminating the twisted-pair communication cables the Contractor shall test the cables for grounds, shorts, splits, and opens. The Contractor shall measure and record the loop resistance from the adjacent data node for all pairs at each terminal location. This resistance shall not exceed 34  $\Omega$  per 305 m; the Contractor shall record all data and shall correct any problems per manufacturer's instruction. The Contractor shall record all data for review by the Engineer.

Full compensation for furnishing, installing, connecting, and testing new twisted pair cable splice closures, of various sizes and types, and disconnecting, removing, and disposing existing twisted pair cable splice closures, of various sizes and types, shall be considered as included in the contract lump sum price paid for communication system routing (modify) and no additional compensation will be allowed therefor.

### 10-3.15 FIBER OPTIC CABLE

Fiber optic cable shall conform to the details shown on the plans and these special provisions.

#### DEFINITIONS

The following definitions shall apply to these special provisions:

- A. Active Component Link Loss Budget.—The active component link loss budget is the difference between the average transmitter launch power (in dBm) and the receiver maximum sensitivity (in dBm).
- B. Backbone.—Fiber cable that provides connections between the TMC and hubs, as well as between equipment rooms or buildings, and between hubs. The term is used interchangeably with "trunk" cable.
- C. Connector.—A mechanical device used to align and join two fibers together to provide a means for attaching to and decoupling from a transmitter, receiver, or another fiber (patch panel).
- D. Connectorized.--The termination point of a fiber after connectors have been affixed.
- E. Connector Module Housing (CMH).--A patch panel used to terminate singlemode fibers with most common connector types. It may include a jumper storage shelf and a hinged door.
- F. Couplers.--Devices which mate fiber optic connectors to facilitate the transition of optical light signals from one connector into another. They are normally located within FDUs, mounted in panels. They may also be used unmounted, to join two simplex fiber runs.
- G. Distribution Cable.--Fiber cable that provides connections between hubs. Drop cables are typically spliced into a distribution cable.
- H. Drop Cable.--Fiber cable that provides connections between a distribution cable to a field element. Typically these run from a splice vault to a splice tray within a field cabinet. Drop cables are usually short in length (less than 20 m) and are of the same construction as outside plant cable. The term "breakout cable" is used interchangeably with drop cable.
- I. End-to-End Loss.--The maximum permissible end-to-end system attenuation is the total loss in a given link. This loss could be the actual measured loss, or calculated using typical (or specified) values. A designer should use typical values to calculate the end-to-end loss for a proposed link. This number will determine the amount of optical power (in dB) needed to meet the System Performance Margin.
- J. Fan Out Termination.--Permits the branching of fibers contained in an optical cable into individual cables and can be done at field locations; thus, allowing the cables to be connectorized or terminated per system requirements. A kit provides pull-out protection for individual bare fibers to support termination. It provides three layers of protection consisting of a Teflon inner tube, a dielectric strength member, and an outer protective PVC jacket. Fan out terminations shall not be used for more than 6 fibers. Using a patch panel would be appropriate.
- K. Fiber Distribution Frame (FDF).--A rack mounted system that is usually installed in hubs or the Transportation Management Center (TMC), that may consist of a standard equipment rack, fiber routing guides, horizontal jumper troughs and Fiber Distribution Units (FDU). The FDF serves as the termination and interconnection of passive fiber optic components from cable breakout, for connection by jumpers, to the equipment.
- L. Fiber Distribution Unit (FDU).--An enclosure or rack mountable unit containing both a patch panel with couplers and splice tray(s). The unit's patch panel and splice trays may be integrated or separated by a partition.
- M. F/O.--Fiber optic.
- N. FOIP.--Fiber optic inside plant cable.
- O. FOOP.--Fiber optic outside plant cable.
- P. FOTP.--Fiber optic test procedure(s) as defined by TIA/EIA standards.
- Q. Jumper.--A short cable, typically one meter or less, with connectors on each end, used to join two CMH couplers or a CMH to active electronic components.
- R. Light Source.--Portable fiber optic test equipment that, when coupled with a power meter, is used to perform end-to-end attenuation testing. It contains a stabilized light source operating at the wavelength of the system under test.
- S. Link.--A passive section of the system, the ends of which are connectorized. A link may include splices and couplers. For example, a video link may be from a F/O transmitter to a video multiplexer (MUX).
- T. Loose Tube Cable.--Type of cable construction in which fibers are placed in buffer tubes to isolate them from outside forces (stress). A flooding compound or material is applied to the interstitial cable core to prevent water migration and penetration. This type of cable is primarily for outdoor applications.
- U. Mid-span Access Method.--Description of a procedure in which fibers from a single buffer tube are accessed and spliced to an adjoining cable without cutting the unused fibers in the buffer tube, or disturbing the remaining buffer tubes in the cable.
- V. MMFO.--Multimode Fiber Optic Cable.

- W. Optical Time Domain Reflectometer (OTDR).--Fiber optic test equipment similar in appearance to an oscilloscope that is used to measure the total amount of power loss in a F/O cable between two points. It provides a visual and printed display of the losses associated with system components such as fiber, splices and connectors.
- X. Optical Attenuator.--An optical element that reduces the intensity of a signal passing through it.
- Y. Patchcord.--A term used interchangeably with "jumper".
- Z. Patch Panel.--A precision drilled metal frame containing couplers used to mate two fiber optic connectors.
- AA. Pigtail.--A short optical fiber permanently attached to a source, detector, or other fiber optic device.
- AB. Power Meter.--Portable fiber optic test equipment that, when coupled with a light source, is used to perform end-to-end attenuation testing. It contains a detector that is sensitive to light at the designed wavelength of the system under test. Its display indicates the amount of optical power being received at the end of the link.
- AC. Riser Cable.--NEC approved cable installed in a riser (a vertical shaft in a building connecting floors).
- AD. Segment.--A section of F/O cable that is not connected to any active device and may or may not have splices per the design.
- AE. SMFO.--Singlemode Fiber Optic Cable.
- AF. Splice.--The permanent joining of two fiber ends using a fusion splicer.
- AG. Splice Closure.--A environmentally sealed container used to organize and protect splice trays. The container allows splitting or routing of fiber cables from multiple locations. Normally installed in a splice vault.
- AH. Splice Module Housing (SMH).--A unit that stores splice trays as well as pigtails and short cable lengths. The unit allows splitting or routing of fiber cables to or from multiple locations.
- AI. Splice Tray.--A container used to organize and protect spliced fibers.
- AJ. Splice Vault.--An underground container used to house excess cable and/or splice closures.
- AK. System Performance Margin.--A calculation of the overall "End to End" permissible attenuation from the fiber optic transmitter (source) to the fiber optic receiver (detector). The system performance margin should be at least 6 dB. This includes the difference between the active component link loss budget, the passive cable attenuation (total fiber loss) and the total connector/splice loss.
- AL. Tight Buffered, Non-Breakout Cable (Tight Buffer Cable).--Type of cable construction where each glass fiber is tightly buffered (directly coated) with a protective thermoplastic coating to 900  $\mu\text{m}$  (compared to 250  $\mu\text{m}$  for loose tube fibers).

## FIBER OPTIC OUTSIDE PLANT CABLE

### General

Each fiber optic outside plant cable (FOOP) for this project shall be all dielectric, non gel filled or water-blocking material, duct type, with loose buffer tubes and shall conform to these special provisions. Cables with singlemode fibers shall contain singlemode (SM) dual-window (1310 nm and 1550 nm) fibers. The optical fibers shall be contained within loose buffer tubes. The loose buffer tubes shall be stranded around an all dielectric central member. Aramid yarn or fiberglass shall be used as a primary strength member, and a polyethylene outside jacket shall provide for overall protection.

All fiber optic (F/O) cable on this project shall be from the same manufacturer, who is regularly engaged in the production of this material.

The cable shall be qualified as compliant with RUS Federal Rule 7NTR1755.900.

CABLE TYPE	DESCRIPTION
A	18MMFO
B	2MMFO
C	12SMFO

### Fiber Characteristics

Each optical fiber shall be glass and consist of a doped silica core surrounded by concentric silica cladding. All fibers in the buffer tube shall be usable fibers, and shall be sufficiently free of surface imperfections and occlusions to meet the optical, mechanical, and environmental requirements of these specifications. The required fiber grade shall reflect the maximum individual fiber attenuation, to guarantee the required performance of each and every fiber in the cable.

The coating shall be a dual layered, UV cured acrylate. The coating shall be mechanically or chemically strippable without damaging the fiber.

The cable shall comply with the optical and mechanical requirements over an operating temperature range of -40°C to +70°C. The cable shall be tested in accordance with EIA-455-3A (FOTP-3), "Procedure to Measure Temperature Cycling Effects on Optical Fiber, Optical Cable, and Other Passive Fiber Optic Components." The change in attenuation at extreme

operational temperatures (-40°C to +70°C) for singlemode fiber shall not be greater than 0.20 dB/km, with 80 percent of the measured values no greater than 0.10 dB/km. The singlemode fiber measurement is made at 1550 nm.

For all fibers the attenuation specification shall be a maximum attenuation for each fiber over the entire operating temperature range of the cable.

Singlemode fibers within the finished cable shall meet the requirements in the following table:

Fiber Characteristics Table	
Parameters	Singlemode
Type	Step Index
Core diameter	8.3 μm (nominal)
Cladding diameter	125 μm ±1.0 μm
Core to Cladding Offset	≤0.8 μm
Coating Diameter	250 μm ±15 μm
Cladding Non-circularity defined as: [1-(min. cladding dia ÷max. cladding dia.)] x 100	≤1.0%
Proof/Tensile Test	345 Mpa, min.
Attenuation: (-40(C) to +70(C)) @1310 nm @1550 nm	≤0.4 dB/km ≤0.3 dB/km
Attenuation at the Water Peak	≤2.1 dB/km @ 1383 ±3 nm
Chromatic Dispersion: Zero Dispersion Wavelength Zero Dispersion Slope	1301.5 to 1321.5 nm ≤0.092 ps/(nm <sup>2</sup> *km)
Maximum Dispersion:	≤3.3 ps/(nm*km) for 1285 – 1330 nm ≤18 ps/(nm*km) for 1550 nm
Cut-Off Wavelength	<1260 nm
Mode Field Diameter (Petermann II)	9.3 ±0.5 μm at 1310 nm 10.5 ±1.0 μm at 1550 nm

### Color Coding

In buffer tubes containing multiple fibers, each fiber shall be distinguishable from others in the same tube by means of color-coding according to the following:

- |                |                 |
|----------------|-----------------|
| 1. Blue (BL)   | 7. Red (RD)     |
| 2. Orange (OR) | 8. Black (BK)   |
| 3. Green (GR)  | 9. Yellow (YL)  |
| 4. Brown (BR)  | 10. Violet (VL) |
| 5. Slate (SL)  | 11. Rose (RS)   |
| 6. White (WT)  | 12. Aqua (AQ)   |

Buffer tubes containing fibers shall also be color-coded with distinct and recognizable colors according to the same table listed above for fibers.

These colors shall be targeted in accordance with the Munsell color shades and shall meet EIA/TIA-598 "Color Coding of Fiber Optic Cables."

The color formulation shall be compatible with the fiber coating and the buffer tube filling compound, and be heat stable. It shall not fade or smear or be susceptible to migration and it shall not affect the transmission characteristics of the optical fibers and shall not cause fibers to stick together.

### Cable Construction

The fiber optic cable shall consist of, but not be limited to, the following components:

1. Buffer tubes
2. Central member
3. Filler rods
4. Stranding

5. Core and cable flooding
6. Tensile strength member
7. Ripcord
8. Outer jacket

#### 1. Buffer Tubes

Clearance shall be provided in the loose buffer tubes between the fibers and the inside of the tube to allow for expansion without constraining the fiber. The fibers shall be loose or suspended within the tubes. The fibers shall not adhere to the inside of the buffer tube. Each buffer tube shall contain a maximum of 12 fibers. SM and MM fibers shall not be mixed within the same buffer tube.

The loose buffer tubes shall be extruded from a material having a coefficient of friction sufficiently low to allow free movement of the fibers. The material shall be tough and abrasion resistant to provide mechanical and environmental protection of the fibers, yet designed to permit safe intentional "scoring" and breakout, without damaging or degrading the internal fibers.

Buffer tube filling compound shall be a homogeneous hydrocarbon-based gel with anti-oxidant additives and used to prevent water intrusion and migration. The filling compound shall be non-toxic and dermatologically safe to exposed skin. It shall be chemically and mechanically compatible with all cable components, non-nutritive to fungus, non-hygroscopic and electrically non-conductive. The filling compound shall be free from dirt and foreign matter and shall be readily removable with conventional nontoxic solvents.

Buffer tubes shall be stranded around a central member by a method, such as the reverse oscillation stranding process, that will prevent stress on the fibers when the cable jacket is placed under strain.

#### 2. Central Member

The central member which functions as an anti-buckling element shall be a glass reinforced plastic rod with similar expansion and contraction characteristics as the optical fibers and buffer tubes. To ensure the proper spacing between buffer tubes during stranding, a symmetrical linear overcoat of polyethylene may be applied to the central member to achieve the optimum diameter.

#### 3. Filler Rods

Fillers may be included in the cable to maintain the symmetry of the cable cross-section. Filler rods shall be solid medium or high-density polyethylene. The diameter of filler rods shall be the same as the outer diameter of the buffer tubes.

#### 4. Stranding

Completed buffer tubes shall be stranded around the overcoated central member using stranding methods, lay lengths and positioning such that the cable shall meet mechanical, environmental and performance specifications. A polyester binding shall be applied over the stranded buffer tubes to hold them in place. Binders shall be applied with sufficient tension to secure the buffer tubes to the central member without crushing the buffer tubes. The binders shall be non-hygroscopic, non-wicking (or rendered so by the flooding compound), and dielectric with low shrinkage.

#### 5. Core and Cable Flooding

The cable core interstices shall contain a water blocking material, to prevent water ingress and migration. The water blocking material shall be either a polyolefin based compound which fills the cable core interstices, or an absorbent polymer, which fills voids and swells to block the ingress of water. The flooding compound or material shall be homogeneous, non-hygroscopic, electrically non-conductive, and non-nutritive to fungus. The compound or material shall also be nontoxic, dermatologically safe, and compatible with all other cable components.

#### 6. Tensile Strength Member

Tensile strength shall be provided by high tensile strength aramid yarns and/or fiberglass which shall be helically stranded evenly around the cable core and shall not adhere to other cable components.

#### 7. Ripcord

The cable shall contain at least one ripcord under the jacket for easy sheath removal.

#### 8. Outer Jacket

The jacket shall be free of holes, splits, and blisters and shall be medium or high density polyethylene (PE), or medium density cross-linked polyethylene with minimum nominal jacket thickness of 1 mm  $\pm$  0.076 mm. Jacketing material shall be applied directly over the tensile strength members and water blocking material and shall not adhere to the aramid strength

material. The polyethylene shall contain carbon black to provide ultraviolet light protection and shall not promote the growth of fungus.

The jacket or sheath shall be marked with the manufacturer's name, the words "Optical Cable", the number of fibers, "SM" or "MM" as applicable, year of manufacture, and sequential measurement markings every meter. The actual length of the cable shall be within -0/+1 percent of the length marking. The marking shall be in a contrasting color to the cable jacket. The height of the marking shall be 2.5 mm  $\pm$ 0.2 mm.

### **General Cable Performance Specifications**

The F/O cable shall withstand water penetration when tested with a one meter static head or equivalent continuous pressure applied at one end of a one meter length of filled cable for one hour. No water shall leak through the open cable end. Testing shall be done in accordance with EIA-455-82 (FOTP-82), "Fluid Penetration Test for Fluid-Blocked Fiber Optic Cable."

A representative sample of cable shall be tested in accordance with EIA/TIA-455-81 (FOTP-81), "Compound Flow (Drip) Test for Filled Fiber Optic Cable". No preconditioning period shall be conducted. The cable shall exhibit no flow (drip or leak) at 80°C as defined in the test method.

Crush resistance of the finished F/O cables shall be 220 N/mm applied uniformly over the length of the cable without showing evidence of cracking or splitting when tested in accordance with EIA-455-41 (FOTP-41), "Compressive Loading Resistance of Fiber Optic Cables". The average increase in attenuation for the fibers shall be  $\leq$ 0.10 dB at 1550 nm (singlemode) and  $\leq$ 0.20 dB at 1300 nm (multimode) for a cable subjected to this load. The cable shall not exhibit any measurable increase in attenuation after removal of load. Testing shall be in accordance with EIA-455-41 (FOTP-41), except that the load shall be applied at the rate of 3 mm to 20 mm per minute and maintained for 10 minutes.

The cable shall withstand 25 cycles of mechanical flexing at a rate of 30  $\pm$ 1 cycles/minute. The average increase in attenuation for the fibers shall be  $\leq$ 0.20 dB at 1550 nm (singlemode) at the completion of the test. Outer cable jacket cracking or splitting observed under 10x magnification shall constitute failure. The test shall be conducted in accordance with EIA-455-104 (FOTP-104), "Fiber Optic Cable Cyclic Flexing Test," with the sheave diameter a maximum of 20 times the outside diameter of the cable. The cable shall be tested in accordance with Test Conditions I and II of (FOTP-104).

The cable shall withstand 20 impact cycles, with a total impact energy of 5.9 N•m. Impact testing shall be conducted in accordance with TIA/EIA-455-25B (FOTP-25) "Impact Testing of Fiber Optic Cables and Cable Assemblies." The average increase in attenuation for the fibers shall be  $<$ 0.20 dB at 1550 nm for singlemode fiber. The cable shall not exhibit evidence of cracking or splitting.

The finished cable shall withstand a tensile load of 2700 N without exhibiting an average increase in attenuation of greater than 0.20 dB (singlemode) and 0.40 dB (multimode). The test shall be conducted in accordance with EIA-455-33 (FOTP-33), "Fiber Optic Cable Tensile Loading and Bending Test." The load shall be applied for one-half hour in Test Condition II of the EIA-455-33 (FOTP-33) procedure.

### **Packaging and Shipping Requirements**

Documentation of compliance to the required specifications shall be provided to the Engineer prior to ordering the material.

Attention is directed to "Fiber Optic Testing," elsewhere in these special provisions.

The completed cable shall be packaged for shipment on reels. The cable shall be wrapped in a weather and temperature resistant covering. Both ends of the cable shall be sealed to prevent the ingress of moisture.

Each end of the cable shall be securely fastened to the reel to prevent the cable from coming loose during transit. Four meters of cable length on each end of the cable shall be accessible for testing.

Each cable reel shall have a durable weatherproof label or tag showing the manufacturer's name, the cable type, the actual length of cable on the reel, the Contractor's name, the contract number, and the reel number. A shipping record shall also be included in a weatherproof envelope showing the above information and also include the date of manufacture, cable characteristics (size, attenuation, bandwidth, etc.), factory test results, cable identification number and any other pertinent information.

The minimum hub diameter of the reel shall be at least thirty times the diameter of the cable. The F/O cable shall be in one continuous length per reel with no factory splices in the fiber. Each reel shall be marked to indicate the direction the reel should be rolled to prevent loosening of the cable.

Installation procedures and technical support information shall be furnished at the time of delivery.

### **LABELING**

**General**

The Contractor shall label all fiber optic cabling in a permanent consistent manner. All tags shall be of a material designed for long term permanent labeling of fiber optic cables and shall be marked with permanent ink on non-metal types, or embossed lettering on metal tags. Metal tags shall be constructed of stainless steel. Non-metal label materials shall be approved by the Engineer. Labels shall be affixed to the cable per the manufacturer’s recommendations and shall not be affixed in a manner which will cause damage to the fiber. Handwritten labels shall not be allowed.

**Label Identification**

1. Labeling of Cables

Labeling of the backbone, distribution and drop fiber optic cables shall conform to the following unique identification code elements:

UNIQUE IDENTIFICATION CODE ELEMENTS for Backbone, Distribution or Drop Cables		
DESCRIPTION	CODE	NUMBER OF CHARACTERS
District	District number	2
Cable Type	Fiber: S: Singlemode M: MultimodeCopper: T: 18 AWG, U: 19 AWG, V: 20AWG, W: 22AWG X: 24 AWG	1
Cable fiber (or copper pairs) Count	Number of fibers or conductor pairs (Examples: 144 fibers; or 100 TWP)	3
Route Number	Hwy. Rte (Example: 005)	3
Begin Function	T: TMC; H: HUB; V: Video Node; D: Data Node; C: Cable Node; M: CCTV Camera; N: CMS; P: Traffic Signal; Z: Ramp Meter; U: Traffic Monitoring/Count Station/Vehicle Count Station (VDS, TOS); S: Splice Vault	1
Begin Function Number	Unique ID number corresponds to Begin Function (Example: H02 [Hub 02])	2
End Function	T: TMC; H: HUB; V: Video Node; D: Data Node; C: Cable Node; M: CCTV Camera; N: CMS; P: Traffic Signal; Z: Ramp Meter; U: Traffic Monitoring/Count Station; S: Splice Vault	1
End Function Number	Unique ID number corresponds to Begin Function (Example: H03 [Hub 03])	2
Unique Identifier	XX: If two or more cables of the same count are in the same run	2
TOTAL		17

Each cable shall display one unique identification, regardless of where the cable is viewed. The begin function and end function correspond to the end points of each cable. The order of the begin and end function follow a hierarchy as listed below, where the lowest number corresponding to the begin/end function is listed first.

List of Hierarchy										
1	2	3	4	5	6	7	8	9	10	11
TMC	HUB	Video Node (VN)	Data Node (DN)	Cable Node	CCTV Camera	CMS	Traffic Signal	Ramp Meter	Traffic Monitoring/ Count Station	Splice Vault

This scheme will work as follows: A cable between the TMC and a HUB will always have the TMC listed as the start function and the HUB as the end function. Between a CMS and a Splice Vault, the start function will always be listed as the CMS, and so on. If a cable is connected between HUBs, for example HUB-01 and HUB-03, the lowest number, in this case HUB-01, will be listed as the start function and HUB-03 as the end function.

A. Example 1: 08S060010H02H0302

This cable is located in District 8, identified as a singlemode fiber optic cable containing 60 fibers, installed along highway Route 10, beginning in Hub 2, and ending in Hub 3, with unique ID of number 2. The implication for the unique ID is that there may be another 60 fiber optic cable between those hubs. This is an example for a backbone cable.

B. Example 2: 11S048008H01S04

This cable is located in District 11, identified as a singlemode fiber optic cable containing 48 fibers, installed along highway Route 8, beginning in Hub 1, and ending in Splice Vault 04. In this case, no additional digits are necessary for a unique ID. This is an example for a distribution cable.

C. Example 3: 11S006163N03S04

This cable is located in District 11, identified as a singlemode fiber optic cable containing 6 fibers, installed along highway Route 163, beginning at CMS-03, and ending in Splice Vault 04. In this case, no additional digits are necessary for a unique ID. This is an example for a drop cable.

2. Labeling of Jumpers and Pigtails

Labeling of the jumpers and pigtails shall conform to the following unique identification code elements:

UNIQUE IDENTIFICATION CODE ELEMENTS for JUMPERS (active component to FDU) and PIGTAILS (to connector # on patch panel)		
DESCRIPTION	CODE	NUMBER OF CHARACTERS
Hub Identifier	Hub, TMC , VN or DN ID Numbers or Alphanumeric or both	2
From (Source) Device	MU: Multiplexer FD: FDU (Fiber Distribution Unit) RP: Repeater	2
From (Source) Device Identifier	Numbers or Alphanumeric or both	2
Transmitter or Receiver	T or R	1
To (Destination) Device	MU: Multiplexer FD: FDU (Fiber Distribution Unit) RP: Repeater	2
To (Destination) Device Identifier	Numbers or Alphanumeric or both	2
Connector Identifier	Connector ID	2
TOTAL		13

A. Example 1: 01MU01TFD0203.

This pigtail is located in Hub 1, from multiplexer 01, transmitting to FDU 02 to patch panel position (connector) 03.

B. Example 2: 02MUA1TFD0B08.

This jumper is located in Hub 2, from multiplexer A1, transmitting to FDU B, to patch panel position (connector) 08.

## **Label Placement**

### **1. Cables**

All cables shall be clearly labeled with the unique identification code element method described elsewhere in these special provisions, at all terminations, even if no connections or splices are made, and at all splice vault entrance and exit points.

### **2. Cable to Cable Splices**

All cable jackets entering the splice closure shall be labeled in accordance with the identification method described elsewhere in these special provisions.

### **3. Cable to Fiber Distribution Units**

The cable jackets shall be clearly labeled at entry to the FDU in accordance with the unique identification code element method described elsewhere in these special provisions. In addition, each fiber shall be labeled with the Fiber ID and pigtails shall be labeled at the connector with the Fiber ID. The FDU shall be clearly labeled with the Cable ID on the face of the FDU. If multiple cables are connected to the FDU, each block of connectors relating to each individual cable shall be clearly identified by a single label with the Cable ID. Individual connections shall be clearly marked on the face of the FDU in the designated area with the Fiber ID.

### **4. Fiber**

Fiber labels shall be placed next to the connectors of the individual fibers.

### **5. Patch Panels**

The cable jackets shall be clearly labeled at entry to the Patch Panel in accordance with the unique identification code element method described elsewhere in these special provisions. In addition, each fiber shall be labeled with the Fiber ID and pigtails shall be labeled at the connector with the Fiber ID. The Patch panel shall be clearly labeled with the Cable ID on the face of the Panel. If multiple cables are connected to the Patch Panel, each block of connectors relating to each individual cable shall be clearly identified by a single label with the Cable ID. Individual connections shall be clearly marked on the face of the Panel in the designated area with the Fiber ID.

### **6. Jumpers**

Equipment to FDU jumpers shall be labeled as to the equipment type connected and shall be labeled at both ends. FDU to FDU jumpers shall be labeled at each end in accordance with the unique identification code element method described elsewhere in these special provisions.

### **7. Pigtails**

Pigtails shall be labeled at the connector in accordance with the unique identification code element method described elsewhere in these special provisions.

### **8. Copper Cable Labels**

All twisted-pair communications cables shall be clearly labeled in a in accordance with the unique identification code element method described elsewhere in these special provisions.

## **CABLE INSTALLATION**

Installation procedures shall be in conformance with the procedures specified by the cable manufacturer for the specific cable being installed. The contractor shall submit the manufacturer's recommended procedures for pulling fiber optic cable at least 20 working days prior to installing cable. Mechanical aids may be used provided that a tension measuring device, and a break-away swivel are placed in tension to the end of the cable. The tension in the cable shall not exceed 2225 N, or the manufacturer's recommended pulling tension, whichever is less.

During cable installation, the bend radius shall be maintained at a minimum of twenty times the outside diameter. The cable grips for installing the fiber optic cable shall have a ball bearing swivel to prevent the cable from twisting during installation.

The F/O cable shall be installed using a cable pulling lubricant recommended by the F/O cable or the innerduct manufacturer, and a pull tape conforming to the provisions described under "conduit" elsewhere in these special provisions. Contractor's personnel shall be stationed at each splice vault and pull box through which the cable is to be pulled to lubricate and prevent kinking or other damage.

The F/O cable shall be installed without splices except where specifically allowed on the plans. If splice locations are not shown on the plans, splicing shall be limited to one cable splice every 6 km. Any midspan access splice or FDU

termination shall involve only those fibers being spliced as shown on the plans. Cable splices shall be located in splice closures, installed in splice vaults shown on the plans. A minimum of 20 m of slack shall be provided for each F/O cable at each splice vault. Slack shall be divided equally on each side of the F/O splice closure.

Unless shown or provided otherwise, only F/O cable shall be installed in each innerduct. Pulling a separate F/O cable into a spare duct to replace damaged fiber will not be allowed.

At the Contractor's option, the fiber may be installed using the air blown method. If integral innerduct is used, the duct splice points or any temporary splices of innerduct used for installation must withstand a static air pressure of 758 kPa.

The fiber installation equipment must incorporate a mechanical drive unit or pusher, which feeds cable into the pressurized innerduct to provide a sufficient push force on the cable, which is coupled with the drag force created by the high-speed airflow. The unit must be equipped with controls to regulate the flow rate of compressed air entering the duct and any hydraulic or pneumatic pressure applied to the cable. It must accommodate longitudinally ribbed, or smooth wall ducts from nominal 16 mm to 51 mm inner diameter. Mid assist or cascading of equipment must be for the installation of long cable runs. The equipment must incorporate safety shutoff valves to disable the system in the event of sudden changes in pneumatic or hydraulic pressure.

The equipment must not require the use of a piston or any other air capturing device to impose a pulling force at the front end of the cable, which also significantly restricts the free flow of air through the inner duct. It must incorporate the use of a counting device to determine the speed of the cable during installation and the length of the cable installed.

## **SPLICING**

Field splices shall be done either in splice vaults or cabinets as shown on the plans. All splices in splice vaults shall be done in splice trays, housed in splice closures. All splices in cabinets shall be done in splice trays housed in FDU's.

Unless otherwise specified, fiber splices shall be the fusion type. The mean splice loss shall not exceed 0.07 dB per splice. The mean splice loss shall be obtained by measuring the loss through the splice in both directions and then averaging the resultant values.

All splices shall be protected with a metal reinforced thermal shrink sleeve.

The mid-span access method shall be used to access the individual fibers in a cable for splicing to another cable as shown on the plans. Cable manufacturers recommended procedures and approved tools shall be used when performing a mid-span access. Only the fibers to be spliced may be cut. All measures shall be taken to avoid damaging buffer tubes and individual fibers not being used in the mid-span access.

The individual fibers shall be looped one full turn within the splice tray to avoid micro bending. A 45 mm minimum bend radius shall be maintained during installation and after final assembly in the optical fiber splice tray. Each bare fiber shall be individually restrained in a splice tray. The optical fibers in buffer tubes and the placement of the bare optical fibers in the splice tray shall be such that there is no discernable tensile force on the optical fiber.

The Contractor will be allowed to splice a total of 12 percent of all fibers to repair any damage done during mid-span access splicing without penalty. The Contractor shall be assessed a fine of \$300.00 for each additional and unplanned splice. Any single fiber may not have more than 3 unplanned splices. If any fiber requires more than 3 unplanned splices, the entire length of F/O cable must be replaced at the Contractor's expense.

## **SPLICE CLOSURES**

The F/O field splices shall be enclosed in splice closures which shall be complete with splice organizer trays, brackets, clips, cable ties, seals and sealant, as needed. The splice closure shall be suitable for a direct burial or pull box application. Manufacturer's installation instructions shall be supplied to the Engineer prior to the installation of any splice closures. Location of the splice closures shall be where a splice is required as shown on the plans, designated by the Engineer, or described in these special provisions.

The splice closure shall conform to the following specifications:

- A. Non-filled thermoplastic case
- B. Rodent proof, water proof, re-enterable and moisture proof
- C. Expandable from 2 cables per end to 8 cables per end by using adapter plates
- D. Cable entry ports shall accommodate 10 mm to 25 mm diameter cables
- E. Multiple grounding straps
- F. Accommodate up to 8 splice trays
- G. Suitable for "butt" or "through" cable entry configurations
- H. Place no stress on finished splices within the splice trays

The splice closure shall be bolted to the side wall of the splice vault and communication pull boxes.

The Contractor shall verify the quality of each splice prior to sealing the splice closure. The splice closure shall not be sealed until link testing is performed and is approved by the Engineer.

### **SPLICE TRAYS**

Splice trays must accommodate a minimum of 12 fusion splices and must allow for a minimum bend radius of 45 mm. Individual fibers must be looped one full turn within the splice tray to allow for future splicing. No stress is to be applied on the fiber when it is located in its final position. Buffer tubes must be secured near the entrance of the splice tray to reduce the chance that an inadvertent tug on the pigtail will damage the fiber. The splice tray cover may be transparent.

Splice trays in the splice closure shall conform to the following:

- A. Accommodate up to 24 fusion splices
- B. Place no stress on completed within the tray
- C. Stackable with a snap-on hinge cover
- D. Buffer tubes securable with channel straps
- E. Must be able to accommodate a fusion splice with the addition of an alternative splice holder
- F. Must be labeled after splicing is completed.

Only one single splice tray may be secured by a bolt through the center of the tray in the fiber termination unit. Multiple trays must be securely held in place as per the manufacturer's recommendation.

### **PASSIVE CABLE ASSEMBLIES AND COMPONENTS**

The F/O cable assemblies and components shall be compatible components, designed for the purpose intended, and manufactured by a company regularly engaged in the production of material for the fiber optic industry. All components or assemblies shall be best quality, non-corroding, with a design life of at least 20 years.

The cable assemblies and components manufacturer shall be ISO9001 registered.

### **FIBER OPTIC CABLE TERMINATIONS**

#### **General**

Fiber optic outside plant (FOOP) cable entering a building shall be routed as described in these special provisions and as shown on the plans. The cable shall continue within the conduit to the designated termination point for cable termination. All components shall be the size and type required for the specified fiber. Fiber optic cable terminations may take place in several locations such as hub, data node, TOS cabinets, camera site, etc.

#### **Cable Termination**

Once the fiber optic cable arrives within the hub, it shall be routed within conduit to a wall mounted fiber splice closure as shown on the plans.

Fiber Optic Inside Plant (FOIP) cable shall then be spliced to the incoming cable.

At the FDU, the cable jacket of the FOIP, or outside plant cable, shall be removed exposing the aramid yarn, filler rods, and buffer tubes. The exposed length of the buffer tubes shall be at least the length recommended by the FDU manufacturer which allows the tubes to be secured to the splice trays. Each buffer tube shall be secured to the splice tray in which it is to be spliced. The remainder of the tubes shall be removed to expose sufficient length of the fibers in order to properly install on the splice tray, as described in "Splicing," elsewhere in these special provisions

The cable shall then be spliced and secured with tie wraps and routed to its appropriate fiber distribution frame/unit (FDF/U) as shown on the plans.

When applicable, moisture-blocking gel shall be removed from the exposed buffer tubes and fibers. The transition from the buffer tube to the bundle of jacketed fibers shall be treated by an accepted procedure for sleeve tubing, shrink tube and silicone blocking of the transition to prevent future gel leak. Manufacturer directions shall be followed to ensure that throughout the specified temperature range gel will not flow from the end of the buffer tube. The individual fibers shall be stripped and prepared for splicing.

Factory terminated pigtails shall then be spliced and placed in the splice tray.

All fibers inside a fiber optic cable entering an Fiber Distribution Unit (FDU), such as at a hub, shall be terminated and labeled. Attention is directed to "Fiber Distribution Unit" elsewhere in these special provisions.

A transition shall then be made, with flexible tubing, to isolate each fiber to protect the individual coated fibers. The final transition from bundle to individual fiber tube shall be secured with an adhesive heat shrink sleeve. Refer to Fan-Out Termination, elsewhere in these special provisions.

## **Distribution Interconnect Package**

Distribution involves connecting the fibers to locations shown on the plans. The distribution interconnect package consists of FDFs and FDU with connector panels, couplers, splice trays, fiber optic pigtails and cable assemblies with connectors. The distribution interconnect package shall be assembled and tested by a company that is regularly engaged in the assembly of these packages. Attention is directed to "Fiber Optic Testing" elsewhere in these special provisions. All distribution components shall be products of the same manufacturers, who are regularly engaged in the production of these components, and the respective manufacturers shall have quality assurance programs.

## **Fiber Optic Cable Assemblies and Pigtails**

### **1. General**

Cable assemblies (jumpers and pigtails) shall be products of the same manufacturer. The cable used for cable assemblies shall be made of fiber meeting the performance requirements of these special provisions for the F/O cable being connected.

### **2. Pigtails**

Pigtails shall be of simplex (one fiber) construction, in 900- $\mu$ m tight buffer form, surrounded by aramid for strength, with a PVC jacket with manufacturer identification information, and a nominal outer jacket diameter of 3 mm. Singlemode simplex cable jackets shall be yellow in color and multimode jackets shall be orange. All pigtails shall be factory terminated and tested and at least one meter in length.

### **3. Jumpers**

Jumpers may be of simplex or duplex design. Duplex jumpers shall be of duplex round cable construction, and shall not have zipcord (siamese) construction. All jumpers shall be at least 2 m in length, sufficient to avoid stress and allow orderly routing.

The outer jacket of duplex jumpers shall be colored according to the singlemode color (yellow) and multimode color (orange) specified above. The two inner simplex jackets shall be contrasting colors to provide easy visual identification for polarity.

### **4. Connectors**

Connectors shall be of the ceramic ferrule ST type for both SM and MM. Indoor ST connector body housings shall be either nickel-plated zinc or glass reinforced polymer construction. Outdoor ST connector body housing shall be glass reinforced polymer.

The associated coupler shall be of the same material as the connector housing.

All F/O connectors shall be the 2.5 mm connector ferrule type with Zirconia Ceramic material with a PC (Physical Contact) pre-radiused tip.

The ST connector operating temperature range shall be  $-40^{\circ}\text{C}$  to  $+70^{\circ}\text{C}$ . Insertion loss shall not exceed 0.4 dB for either singlemode or multimode, and the return reflection loss on singlemode connectors shall be at least -35 dB. Connection durability shall be less than a 0.2 dB change per 500 mating cycles per EIA-455-21A (FOTP-21). All terminations shall provide a minimum 222 N pull out strength. Factory test results shall be documented and submitted to the Engineer prior to installing any of the connectors. Singlemode connectors shall have a yellow color on the body and/or boot that renders them easily identifiable from multimode connectors.

Field terminations shall be limited to splicing of adjoining cable ends and/or cables to ST pigtails.

All connectors shall be factory-installed and tested. There shall be no installation of connectors in the field.

All unmated connectors shall have protective caps installed.

## **Fan-Out Termination**

A fan out termination shall be required as shown on the plans designated by the Engineer or described in these special provisions.

For fiber counts of less than 6 fibers, a fan out termination may be used to terminate the incoming fiber optic cable. The connector return loss shall be no greater than -40 dB.

The fan out termination shall consist of a splice connector and the appropriate number of fiber optic pigtails, which will be fusion spliced to the incoming fibers.

The pigtail shall be contained in a housing that will provide strain relief between the incoming fiber optic cable plant jacket, buffer tubes, fibers and pigtail jacket material.

Each fiber shall be spliced to a pigtail with a factory installed and polished ST connector, as specified elsewhere in these special provisions. The splices shall then be encapsulated in a weather-proof housing. Each connector shall have a weatherproof cap to protect it from the elements. The pigtail shall be of simplex (one fiber) construction, in a 900 µm tight buffer form, surrounded by Aramid yarn for strength. The buffer shall have a PVC jacket with manufacturer identification information, and a nominal outer jacket diameter of 3 mm. Singlemode simplex cable jackets shall be yellow in color. All pigtails shall be at least two meter in length.

Each pigtail shall be labeled, as specified elsewhere in these special provisions, and secured onto the cable using clear heat shrink tubing.

## **FIBER OPTIC TESTING**

### **General**

Testing shall include the tests on elements of the passive fiber optic components: (1) at the factory, (2) after delivery to the project site but prior to installation, (3) after installation but prior to connection to any other portion of the system. The Contractor shall provide all personnel, equipment, instrumentation, and materials necessary to perform all testing. The Engineer shall be notified two working days prior to all field tests. The notification shall include the exact location or portion of the system to be tested.

Documentation of all test results shall be provided to the Engineer within 2 working days after the test involved.

A minimum of 15 working days prior to arrival of the cable at the site, the Contractor shall provide detailed test procedures for all field testing for the Engineer's review and approval. The procedures shall include the tests involved and how the tests are to be conducted. Included in the test procedures shall be the model, manufacturer, configuration, calibration, and alignment procedures for all proposed test equipment.

### **Factory Testing**

Documentation of compliance with the fiber specifications as listed in the Fiber Characteristics Table shall be supplied by the original equipment manufacturer. Before shipment, but while on the shipping reel, 100 percent of all fibers shall be tested for attenuation. Copies of the results shall be (1) maintained on file by the manufacturer with a file identification number for a minimum of seven years, (2) attached to the cable reel in a waterproof pouch, and (3) submitted to the Contractor and to the Engineer.

### **Arrival On Site**

The cable and reel shall be physically inspected on delivery and 100 percent of the fibers shall be attenuation tested to confirm that the cable meets requirements. The failure of any single fiber in the cable to comply with these special provisions, is cause for rejection of the entire reel. Test results shall be recorded, dated, compared, and filed with the copy accompanying the shipping reel in a weatherproof envelope. Attenuation deviations from the shipping records of greater than five percent shall be brought to the attention of the Engineer. The cable shall not be installed until completion of this test sequence and the Engineer provides written approval. Copies of traces and test results shall be submitted to the Engineer. If the test results are unsatisfactory, the reel of F/O cable shall be considered unacceptable and all records corresponding to that reel of cable shall be marked accordingly. The unsatisfactory reels of cable shall be replaced with new reels of cable at the Contractor's expense. The new reels of cable shall then be tested to demonstrate acceptability. Copies of the test results shall be submitted to the Engineer.

### **After Cable Installation**

Index matching gel shall not be allowed in connectors during testing. After the fiber optic cable has been pulled but before breakout and termination, 100 percent of all the fibers shall be tested with an OUTDOORS for attenuation. Test results shall be recorded, dated, compared, and filed with the previous copies of these tests. Copies of traces and test results shall be submitted to the Engineer. If the OTDR test results are unsatisfactory, the F/O cable segment of cable shall be unacceptable. The unsatisfactory segment of cable shall be replaced with a new segment, without additional splices, at the Contractor's expense. The new segment of cable then shall be tested to demonstrate acceptability. Copies of the test results shall be submitted to the Engineer.

### **System Cable Verification At Completion**

#### **1. Power Meter and Light Source**

At the conclusion of the OTDR testing, 100 percent of the fiber links shall be tested end to end with a power meter and light source, in accordance with EIA Optical Test Procedure 171 and in the same wavelengths specified for the OTDR tests. These tests shall be conducted in one direction. As shown in Appendix A, the Insertion Loss (IC) shall be calculated. Test

results shall be recorded, compared, and filed with the other recordings of the same links. Test results shall be submitted to the Engineer. These values shall be recorded in the Cable Verification Worksheet in Appendix A.

## 2. OTDR Testing

Once the passive cabling system has been installed and is ready for activation, 100 percent of the fibers shall be tested with the OTDR for attenuation at wavelengths of both 1310 nm and 1550 nm. OTDR testing shall be performed in both directions (bi-directional), on all fibers. Test results shall be generated from software of the test equipment, recorded, dated, compared, and filed with previous copies. A hard copy printout and an electronic copy on a DOS based 89 mm diskette of traces and test results shall be submitted to the Engineer. The average of the two losses shall be calculated, and recorded in the Cable Verification Worksheet in Appendix A. The OTDR shall be capable of recording and displaying anomalies of at least 0.02 dB. All connector losses must be displayed on the OTDR traces.

## 3. Cable Verification Worksheet

The Cable Verification Worksheet shown in Appendix A shall be completed for all links in the fiber optic system, using the data gathered during cable verification. The completed worksheets shall be included as part of the system documentation.

## 4. Test Failures

If the link loss, measured from the power meter and light source, exceeds the calculated link loss, or the actual location of the fiber ends does not agree with the expected location of the fiber ends (as would occur with a broken fiber), the fiber optic link will not be accepted. The unsatisfactory segments of cable, or splices shall be replaced with a new segment of cable or splice at the Contractor's expense. The OTDR testing, power meter and light source testing and Cable Verification Worksheet shall be completed for the repaired link to determine acceptability. Copies of the test results shall be submitted to the Engineer. The removal and replacement of a segment of cable shall be interpreted as the removal and replacement of a single contiguous length of cable connecting two splices and two connectors. The removal of a small section containing the failure, and therefore introducing new unplanned splices, will not be allowed.

### **Passive Component Package Testing and Documentation**

All components in the passive component package (FDUs, pigtails, jumpers, couplers, and splice trays) shall be from a manufacturer who is ISO9001 registered.

In developing the passive component package, each connector termination (pigtail, or jumper) shall be tested for insertion attenuation loss using an optical power meter and source. In addition, all singlemode terminations shall be tested for return reflection loss. These values shall meet the loss requirements specified earlier and shall be recorded on a tag attached to the pigtail or jumper.

Once an assembly is complete, the manufacturer shall visually verify all tagging of loss values is complete. As a final quality control measure, the manufacturer shall do an "end to end" optical power meter/light source test from pigtail end to end to the terminating point assure continuity and overall attenuation loss valued.

The final test results shall be recorded, along with previous individual component values, on a special form assigned to each FDU. The completed form shall be dated and signed by the Manufacturer's Quality Control supervisor. One copy of this form will be attached in a plastic envelope to the assembled FDU unit. Copies will be provided separately to the Contractor and to the Engineer, and shall also be maintained on file by the manufacturer or supplier.

The assembled and completed FDU unit shall then be protectively packaged for shipment to the Contractor for installation.

### **Fiber Optic System Performance Margin Design Criteria**

The installed system performance margin shall be at least 6 dB for every link. If the design system performance margin is less than 6 dB, the Engineer shall be notified and informed of the Contractor's plan to meet that requirement.

### **Active Component Testing**

The transmitters and receivers shall be tested with a power meter and light source, to record the transmitter average output power (dBm) and receiver sensitivity (dBm). These values shall be recorded in the Fiber System Performance Margin Calculations Worksheet in Appendix B, section C, number 6.

**APPENDIX A**

**Cable Verification Worksheet**

*End-to-End Attenuation (Power Meter and Light Source) Testing  
and OTDR Testing*

Contract No. \_\_\_\_\_ Contractor: \_\_\_\_\_

Operator: \_\_\_\_\_ Date: \_\_\_\_\_

Link Number: \_\_\_\_\_ Fiber Number: \_\_\_\_\_

Test Wavelength (Circle one): 1310 nm      1550 nm

Expected Location of fiber ends: End 1: \_\_\_\_\_ End 2: \_\_\_\_\_

**Power Meter and Light Source Test Results:**

Power In:	_____ dBm	1A
Output Power:	_____ dBm	1B
Insertion Loss [1A - 1B]:	_____ dB	1C

**OTDR Test Results:**

Forward Loss:	_____ dB	2A
Reverse Loss:	_____ dB	2B
Average Loss [(2A + 2B)/2]:	_____ dB	2C

-----  
To Be Completed by Caltrans:

Resident Engineer's Signature: \_\_\_\_\_

Cable Link Accepted: \_\_\_\_\_

**APPENDIX B**  
**Fiber System Performance Margin Calculations Worksheet**

**A. Calculate the Passive Cable Attenuation**

1. Calculate Fiber Loss at Operating Wavelength: _____ nm	Cable Distance (times) Individual Fiber Loss (equal) @ 1310 nm (0.4 dB/km) @ 1550 nm (0.3 dB/km)	_____ km x ____ dB/km =
<b>Total Fiber Loss:</b>		_____ dB

**B. Calculate the Total Connector/Splice Loss**

2. Calculate Connectors/couplers Loss: (exclude Tx and Rx connectors)	Individual Connector Loss (times) Number of Connector Pairs (equal) <b>Total Connector Loss:</b>	0.4 dB x _____ = _____ dB
3. Calculate Splice Loss:	Individual Splice Loss (times) Number of Splices (equal) <b>Total Splice Loss:</b>	0.1 dB x _____ = _____ dB
4. Calculate Other Components Loss:	<b>Total Components:</b>	_____ dB
5. Calculate Total Losses:	Total Connector Loss (plus) Total Splice Loss (plus) Total Components (equal)	+ _____ dB + _____ dB + _____ dB =
<b>Total Connector/Splice Loss:</b>		_____ dB

**C. Calculate Active Component Link Loss Budget**

System Wavelength: Fiber Type: Average Transmitter Output (Launch Power):	_____ nm singlemode _____ dBm
Receiver MAX Sensitivity (10 <sup>9</sup> BER) (minus) Receiver MIN Sensitivity (equal)	_____ dBm - _____ dBm = <b>Receiver Dynamic Range:</b> _____ dB
6. Calculate Active Component Link Loss Budget:	Average Transmitter Output (Launch Power) (minus) Receiver MAX Sensitivity (equal)
<b>Active Component Link Loss Budget:</b>	

**D. Verify Performance**

7. Calculate System Performance Margin to Verify Adequate Power:	Active Component Link Loss Budget [C] (minus) Passive Cable Attenuation [A] (minus) Total Connector/Splice Lost [B] (equal)	_____ dB - _____ dB - _____ dB =
<b>System Performance Margin:</b>		_____ dB

Full compensation for furnishing, installing, connecting, terminating and testing new fiber optic cables, and fiber optic splice closures, of various sizes and types, and disconnecting, removing, and disposing existing fiber optic cables, and fiber

optic splice closures, of various sizes and types, shall be considered as included in the contract lump sum price paid for communication system routing (modify) and no additional compensation will be allowed therefor.

### **10-3.16 SERVICE**

Continuous welding of exterior seams in service equipment enclosures is not required.

Type III service equipment enclosures shall be the aluminum type.

Each service shall be provided with up to 2 main circuit breakers, which shall disconnect ungrounded service entrance conductors. Where the "Main" circuit breaker consists of 2 circuit breakers as shown on the plans or required in the special provisions, each of the circuit breakers shall have a minimum interrupting capacity of 10 000 A, rms.

An engraved phenolic nameplate shall be installed with stainless steel rivets on the exterior of the front panel indicating the identification number and the service address of the service cabinet enclosure. Character size shall be a minimum of 5 mm in height.

Service conduit between the serving utility owned power pole and service equipment enclosure shall not be installed until service location has been verified by the serving utility.

Where a new service is to be installed, the Contractor shall notify the Engineer in writing at least 5 working days prior to the date service is required.

Full compensation for Type III-BF service equipment enclosure shall be considered as included in the contract lump sum price paid for the items involved and no additional compensation will be allowed therefor.

### **10-3.17 NUMBERING ELECTRICAL EQUIPMENT**

Reflective numbers and edge sealer will be State-furnished in conformance with the provisions in "Materials" of these special provisions.

The numbers and edge sealer shall be placed on the equipment where designated by the Engineer.

Where new numbers are to be placed on existing or relocated equipment, the existing numbers shall be removed.

Reflective numbers shall be applied to a clean surface. Only the edges of the numbers shall be treated with edge sealer.

Five-digit, equipment numbers shall be placed for all electroliers, and service equipment enclosure. On service equipment enclosure, the numbers shall be placed on the front door.

### **10-3.18 LUMINAIRES**

Ballasts shall be the lag regulator type.

### **10-3.19 PHOTOELECTRIC CONTROLS**

Contactors shall be the mechanical armature type.

Photoelectric units for illuminated signs shall have a "turn-on" level of between 215 lux and 323 lux (corresponds to a switching level of approximately 430 lux to 646 lux measured in the horizontal plane). "Turn-off" level shall not exceed 3 times the "turn-on" level.

### **10-3.20 WORKS AT EXISTING EAST LOS ANGELES (ELA) HUB BUILDING**

The existing East Los Angeles (ELA) Hub building is located at Route 5/Route 10 Separation.

Works at the existing East Los Angeles (ELA) Hub building shall consist of video link and data link testing to and from the various field elements, including the existing data node 1 at the existing East Los Angeles (ELA) Hub building, as described elsewhere in these special provisions, before and after the various fiber optic and twisted pair cables are installed, as required to make the communication system routing fully operational.

The Contractor's attention is directed to "Video link testing" and "Data link testing" under "System Testing" as described elsewhere in these special provisions.

### **ACCESS TO EXISTING EAST LOS ANGELES (ELA) HUB BUILDING**

Except as otherwise provided in these special provisions or as directed by the Engineer, any work that requires access to the existing East Los Angeles (ELA) Hub building shall be subjected to the following restrictions:

Works at the existing East Los Angeles (ELA) Hub building shall be limited to the hours between 4:00 p.m. Friday through 6:00 a.m. Monday. The Contractor shall obtain approval from the Engineer a minimum of 48 hours before scheduling any work in the East Los Angeles (ELA) Hub building. In addition, the Engineer and the Caltrans Electrical Maintenance Supervisor, shall be notified a minimum of 48 hours in advance before access is required to the East Los Angeles (ELA) Hub building. Access to the equipment room in the East Los Angeles (ELA) Hub building shall be strictly limited to the hours needed to complete that portion of work being performed within these rooms. The work

performed in the equipment room shall take place only in the presence of the Engineer and the TMC Systems Engineer, telephone (213) 897-0329, and / or the Caltrans Maintenance Supervisor or any designee as directed by the Engineer.

The works performed in the East Los Angeles (ELA) Hub building shall be done in such a manner so as to maintain the integrity of the equipment room as neatly as possible. At all times, the Contractor shall provide a clear walking path to all equipment in the East Los Angeles (ELA) Hub building for the building staff's use.

The Contractor shall protect all existing equipment within the equipment room from damage from the Contractor's operations. Access to hardware, electronics and peripheral equipment shall be limited strictly to those items necessary for the Contractor to perform the work required as stated elsewhere in these special provisions.

The Contractor shall cooperate with other contractors, vendors, and support personnel for ongoing systems work that may be in progress at the East Los Angeles (ELA) Hub building during the term of this contract.

Full compensation for works at the existing East Los Angeles (ELA) Hub building, shall be considered as included in the contract lump sum price paid for communication system routing (modify) and no additional compensation will be allowed therefor.

### **10-3.21 SYSTEM TESTING, SYSTEM DOCUMENTATION AND FINAL ACCEPTANCE**

The following existing system testing, system documentation and final acceptance special provisions are mostly the same as from those used on the contract for the existing communication system routing installation. The Contractor shall provide system testing and system documentation, as required, to meet these specifications, as part of the communication system routing, as shown on the plans. The existing communication system routing is described in these special provisions to assist the Contractor in understanding the scope of work involved. Except for verification and testing of the condition of the existing system before and after the new system, the scope of the Contractor's work shall be as defined on plans.

As built plans for the existing communication system routing are available for inspection at the Department of Transportation, Construction Office, 120 South Spring Street, Room 244, Los Angeles California 90012, telephone (213) 897-0054.

#### **SYSTEM TESTING**

The system testing shall cover pre-construction testing, fiber optic cable and twisted pair cable testing, video link testing, data link testing, physical inspection, functional testing, performance testing, final acceptance and recording test results, that are required to validate the operational performance of the installed fiber optic and twisted pair cables as described elsewhere in these special provisions.

**Test Plan.**--The Contractor shall develop and submit within 30 working days, after the approval of the Contract, to the Engineer an installation and test plan for approval, which details the method of installation and all testing for all new material and cables and the associated schedule of activities, based on these special provisions, plans, the manufacturer's recommended test procedures, and industry standard practices. Three copies of the test plan shall be submitted to the Engineer for approval. The Engineer will review then approves, or disapproves, the plan within two weeks. If the Engineer rejects the test plan the Contractor shall submit a revised test plan within 20 working days for review and approval by the Engineer. No testing shall be performed until the Engineer has approved the Contractor's test plan. The tests shall demonstrate that the design and production of new material and cables meet the requirements of these special provisions and plans.

All test results, including results of failed test or re-tests, shall be submitted, and delivered to the Engineer and a copy placed with the equipment at the site.

The Contractor shall supply all test equipment.

The Contractor shall notify the Engineer of his intent to proceed with functional and sub-system testing 48 hours prior to commencement of each test. Sub-system testing and inspections shall include visual inspection for damaged in correct installation, adjustments and alignment, and measurement of parameters and operating conditions.

**Pre-Installation Testing.**--Pre-inspection testing shall include testing of all material, and cables in a laboratory environment prior to delivery to the site. The Contractor shall arrange use of laboratory facilities, including an environmental simulation chamber. The tests shall either be conducted at the manufacturer's premises or at a laboratory arranged by the Contractor.

All material, except test equipment and special tools, shall be bench tested in accordance with the following paragraphs, which include those items, described elsewhere requiring pre-installation testing for each individual item where applicable.

All active equipment shall be connected to normal operating power, energized and subjected to normal operating conditions for a continuous period of time in the laboratory of not less than 48 hours.

Functional testing shall be performed by the manufacturer on all material prior to delivery to the site. The functional tests shall be performed in accordance with an approved test plan. Any material, which fails to meet the requirements of the

contract, shall be repaired or replaced and the test shall be repeated until satisfactory. All functional test results, including results of failed tests or re-tests, shall be submitted and delivered with all material delivered to the site.

The manufacturer in accordance with a test plan developed by the Contractor and approved by the Engineer shall perform full performance test.

**Sub-system Testing.**--Sub-system testing shall encompass the testing of all new and existing material, and cables after installation of new material and cables at the site, but prior to acceptance tests. These tests shall be done in accordance with the performance testing called under each individual item in these special provisions.

New material and cables shall be installed in accordance with the plans and special provisions. Sub-system testing and inspections shall include visual inspection for damaged or incorrect installation, adjustments and alignment, and measurement of parameters and operating conditions. The Contractor shall notify the Engineer of his intent to proceed with sub-system testing 48 hours prior to commencement of each test.

Installation documentation and test results shall be provided for all new material, and cables prior to commencement of acceptance tests. Installation documentation shall be in accordance with these special provisions and shall include the following as appropriate:

- Model, part number and serial number for all material.
- Test equipment model number, serial number, settings, and date of last calibration.
- All strap and switch settings.
- Record of all adjustments and levels.
- Alignment measurements.
- Identification of interconnections.
- All factory, laboratory, and site test results.

**Fiber Optic Cable Testing.**--Attention is directed to "Fiber Optic Testing" elsewhere in these special provisions.

**Video Link Testing.**--The video link testing shall be conducted after the Contractor submits a test plan and receives approval from the Engineer, based on these special provisions, plans and the manufacture's recommended test procedures for the equipment and cable involved.

Video link testing shall be conducted between various existing CCTV camera locations, and the existing East Los Angeles (ELA) Hub building, as shown on the plans and as directed by the Engineer.

A video communications link shall include an existing video transmitter in an existing CCTV camera controller cabinet, an existing video demultiplexer's video receiver the existing East Los Angeles (ELA) Hub building, interconnecting fiber optic cables, connectors and power supplies. The video link is to provide point-to-point transmission and reception of a full motion NTSC baseband video signal using an optical fiber as the transmission medium. Video system performance tests for any particular video link shall be performed after the interconnecting fiber optic cables have been installed and tested.

The video link in the communications system shall be tested with a video test signal at the video transmitter input. The Contractor shall perform all level adjustments and alignments required on the video link in order for it to operate in accordance with these special provisions. If any video link fails to meet the performance requirements, the Contractor shall take all steps necessary to restore the failed link to the required performance.

Each video link in the communication system routing shall be tested for qualitative performance with its associated camera turned on and connected to the BNC connector of the video transmitter. The Contractor shall measure, record and tabulate a video receiver's dynamic range at the optical connector of the existing video demultiplexer's video receiver at the East Los Angeles (ELA) Hub building under test using a 90 percent APL (average picture level) flat field input to the existing video transmitter. Measurements shall be made from the baseband-in to baseband-out connections.

To do this the measured optical attenuation of the fiber being used shall be increased to the point at which the video test set just begins to show a 3 dB degradation of the video signal to noise ratio in accordance with EIA 250 video test procedures. The optical receive power into the existing video demultiplexer's video receiver shall be measured and recorded. Then the optical attenuation shall be decreased until the video test set once again shows degradation of the video and registers errors. At no time shall the optical power into the existing video demultiplexer's video receiver exceed the manufacturer's specified saturation level. The optical receive level shall once again be measured and recorded. These minimum and maximum receive levels define the existing video demultiplexer's video receiver dynamic range and shall meet or exceed the specifications as specified elsewhere under these special provisions. The Contractor shall measure and record the baseband video output level from the existing video demultiplexer's video receiver under test. This measurement shall be repeated for each video link affected by the Contractor's work.

The output video signal shall be connected to a video display monitor. The observed picture on the video display monitor shall be assessed for qualitative performance. All qualitative comments shall be recorded for each camera.

The Engineer shall approve the video test set. All video links affected by the Contractor's work shall be tested for the following performance characteristics. The Contractor shall measure, record and demonstrate that the performance meets or exceeds the specified EIA RS-250 requirements listed below:

- Differential gain.
- Differential phase.
- Chrominance to luminance delay inequality.
- Amplitude vs. frequency characteristics.
- Frequency response characteristic.
- Signal to noise ratio.
- Signal to low frequency noise.
- Signal to periodic noise.
- Output signal level.

**Data Link Testing.**--The data link testing shall be conducted after the Contractor submits a test plan and receives approval from the Engineer, based on these special provisions, plans for the equipment involved.

Data link testing is for the alignment and testing of the data system. The activities shall include verification of all data circuits in the low speed data links, and in the integrated data system. The Contractor shall adjust levels required for the data system to operate. Data link tests shall be conducted in one phase:

**Data link performance.**--Data link performance tests shall consist of functional tests conducted between the existing D4 channel bank multiplex at the existing data node 1 in the existing East Los Angeles (ELA) Hub building, and each field cabinet as shown in the plans. The audio channel shall be verified in both directions using telephone instruments. The signaling system shall be verified in both directions. In addition for circuits using 4 WTO channel cards for modems, bit error rate (BER) tests shall be conducted using appropriate model 400, 1200 BPS modem or ITU compatible high speed modem, and a bit error rate test set (BERTS) shall be used to verify error free transmission for five minutes at the bit rate to be employed in the system.

Records of all tests shall be delivered to the Engineer. Circuits shall be fully tested to the channel card manufacturer's specifications. Modem manufacturer required channel specifications shall be measured. In addition, end-to-end bit error rate tests (BERTS) shall be conducted using the type modem to be employed on the link at the bit rate to be employed. The BERTS shall be with the modem at the equipment site(s) configured in a loop back and with the test setup at the node. The BERTS shall be a minimum of 3 hours for each circuit exactly and fully configured for operation in accordance with these Special Provisions and the Plans including required bridges.

All circuits affected by the Contractor's work shall provide an error rate less than  $1 \times 10^{-6}$ .

**Acceptance Testing.**--The acceptance testing shall be conducted in accordance with the approved test plan. The acceptance testing shall include conducting acceptance tests and subsequent retest, and documentation of the test results.

Final acceptance tests shall be conducted after the site and sub-system test results have been reviewed and accepted by the Engineer. These tests include the complete system in normal operations. The test plan shall address the full testing requirements of the specifications. The test plan shall detail all tests to be performed, the expected test results, and the test schedule. The acceptance test plan shall include the following major test and acceptance categories:

- Physical inspection.
- Functional tests.
- Performance tests.

The Contractor shall test the communications system according to the approved acceptance test plan and shall provide all test equipment, labor, and ancillary items required to perform the testing. The test equipment shall be certified to be calibrated to the manufacturer's specifications. The model and part numbers and date of last calibration of all test equipment shall be included with the test results.

Acceptance testing shall not commence until all material required by these special provisions and plans are delivered, installed, and aligned and all production test and site test documentation and results have been approved by the Engineer.

All acceptance test results shall be fully documented and such documentation provided as a condition of acceptance.

**Physical Inspection.**--The Contractor shall provide documentation to prove delivery of all material, equipment, cable, and documentation. If any material or documentation is outstanding or have been replaced under pre-acceptance warranty a

physical inspection and documentation shall be provided for this material. The physical inspection shall consist of inspecting all installed material to ensure workmanship satisfies the specified requirements.

**Functional Tests.**--The Contractor shall test all system functions to demonstrate that all circuits (video, data, and voice), cameras, camera control and all equipment satisfies the functional requirements of the specifications.

This testing shall include subjective testing of each camera image and verification of camera control from the camera control receiver. The connectivity of each data channel shall be demonstrated. The Contractor shall document all functional test results. In the event that any aspect of the functional tests are determined by the Engineer to have failed, the Contractor all cease all acceptance testing and determine the cause of the failure and make repairs to the satisfaction of the Engineer. Acceptance testing shall, at the discretion of the Engineer, be repeated beginning from the start of functional tests.

**Performance Tests.**--The Contractor shall conduct operational performance tests on the following:

Affected video links between the various existing CCTV camera locations, and the existing East Los Angeles (ELA) Hub building.

Affected data links from the existing data node 1 at the existing East Los Angeles (ELA) Hub building, and the system elements located in the field equipment.

Video tests shall satisfy the end-to-end performance requirements under normal operating conditions. Video tests shall be measured with the camera video output transmitting a video signal at the input of the video display monitors. The Contractor shall test the video sub-system and record the results.

The video signal to noise shall be measured according to EIA-250. The video signal to noise ratio shall be measured and recorded with both the camera providing the video-input reference and with suitable video test equipment providing the video reference signal. When the source is the test equipment, the video signals to noise ratio shall be greater than 47 dB.

Adjustments shall be calculated to account for any deviation in output level of the camera resulting from the variable light conditions, the automatic iris, and associated automatic gain control. The resulting video signal to noise ratio shall be recorded.

The video signal to low frequency noise ratio shall be measured according to EIA-250. The resulting video signal to low frequency noise ratio shall be greater than 39 dB. If an AGC circuit does not allow measurement as per EIA-250, the Contractor shall submit an alternative test plan for approval.

The video signal to periodic noise ratio shall be measured according to EIA-250. The resulting video signal to periodic noise ratio shall be greater than 52 dB.

Data tests shall be performed on all operational and voice data circuits affected by the Contractor's work using appropriate test equipment for the measurement of the following parameters:

End-to-end bit error rate tests shall be run from the data node 1 in the East Los Angeles (ELA) hub building to each remote drop of each data circuit. A data test set shall be used at both the data node 1 in the East Los Angeles (ELA) hub building and the remote modems to insert an asynchronous pseudo-random pattern using 8 data bits, 1 start bit, 1 stop bit and even parity. The data test set at the remote modem must hold RTS high for the duration of the data test. The data rate of the test sets shall be set to rate as employed in the system.

A 15 minute test on each drop of each multipoint circuit shall be error free in both directions. One drop of each circuit as chosen by the Engineer shall be tested for 72 hours. The average bit error rate in both directions shall be less than  $1 \times 10^{-6}$  at 9600 bps.

## **SYSTEM DOCUMENTATION**

The Engineer will provide the Contractor a complete copy of the existing documentation for the existing communication system routing to be updated and revised. The scope of system documentation performed by the Contractor shall reflect the Contractor's work, as specified by these special provisions, and as directed by the Engineer.

The Contractor shall submit a draft copy of all test results and changes made by the Contractor to the existing communication system routing for review and approval prior to production of this documentation. The Engineer will review and approve or reject the draft documentation within two weeks of receipt.

The Contractor shall revise the documentation if required and submit the revised documentation. The Engineer will approve or reject the revised documentation within three weeks of receipt. The Contractor shall arrange for re-submission in a timely manner to meet the schedule in the case that the documents be rejected.

Upon approval, the draft documentation shall be supplied three weeks prior to the start of site testing. The draft documentation shall be of the same format as the final manuals but with temporary insertion for items, which cannot be finalized until the system is completed tested and accepted. Final documentation shall be submitted no later than four weeks

after completion of the acceptance tests and shall incorporate all comments made during the approval stages. The Contractor shall be responsible for all delay caused by non-compliance to the specified requirements.

Final documentation shall be approved prior to its production. Ten copies of all final documents shall be delivered. The copies shall be made on 216 mm x 279 mm paper and bound in three-ring hard-covered binders complete with dividers. System documentation shall be arranged in an operation and maintenance (O & M) manual format providing all the information necessary to reflect the changes made to the existing system by the Contractor. The revised documentation shall as a minimum, reflect changes made by the Contractor to the existing communication system routing, consisting of the following sub-section as described below:

Master Items Index. This shall be the first section of the revised communication system routing manual and shall be revised as needed. The section shall describe the purpose of each manual and brief description to the directory of the manual.

System Description and Technical Data. This revised section shall reflect changes made by the Contractor to the existing communication system routing with illustrative block diagrams. Technical data specification for cable shall be provided. Any modification that has been done on the existing communication system routing equipment shall be clearly described.

Corrective Maintenance. The revised section shall include procedures to permit the location and correction of faults to the level of each replaceable module.

Preventative Maintenance. The revised section shall include procedures for preventative maintenance in order to maintain the performance parameters of the communication system routing within the requirements of the specifications.

Parts List. The revised section shall include an update list of all replaceable parts with exact parts description and number and a directory of recommended suppliers with correspondence address, telephone and fax numbers.

Test Results. This revised section shall include a final copy of the test results for all the testing that have been conducted during the contract.

Revised Manuals. Ten complete sets of revised manuals shall be provided. The manuals shall, as a minimum, include any updates and revisions of the following, caused by the Contractor's work:

- A. Complete and accurate Block Diagrams.
- B. Complete installation and turn-on procedures.
- C. Complete performance specifications (functional, electrical, mechanical and environmental) identified by a universal part number such as JEDEC, RETMA, or EIA.
- D. Complete maintenance and trouble-shooting procedures.
- E. Complete stage-by-stage explanation of operation.

A comprehensive list of cabling and wiring updates shall be provided to clearly identify the interconnection and labeling of all existing equipment both in the field and at the East Los Angeles (ELA) Hub building.

Full compensation for system documentation shall be considered as included in the contract lump sum price paid for communication system routing (modify) and no separate payment will be made therefor.

## **FINAL ACCEPTANCE**

The final acceptance of the system will not occur until all of the following conditions have been met as follows:

Physical, functional, and full performance acceptance tests have been completed and the Engineer approves the results.

All documentation has been completed and submitted to the Engineer.

All connections that were changed to perform acceptance tests are restored and tested.

Full compensation for final acceptance shall be considered as included in the contract lump sum price paid for communication system routing (modify) and no separate payment will be made therefor.

## **10-3.22 COMMUNICATION SYSTEM ROUTING CUTOVER**

Communication system routing cutover is the orderly disconnection of existing communication system routing elements and the connection, activation, testing the modified communication system routing elements. The integration and testing shall begin at the affected field sites of the existing communication system routing with direction from the East Los Angeles (ELA) Hub building. The existing communication system routing is described in these special provisions to assist the Contractor in understanding the scope of work involved. Except for verification and testing of the condition of the existing communication system routing before and after the modification, the scope of the Contractor work shall be as defined on the plans between the East Los Angeles (ELA) Hub building and the existing splice vault east of Euclid Avenue on Route 5.

Communication system routing cutover of individual field elements shall consist of:

1. Installation of the new fiber optics and twisted pair cables, as shown on the plans.
2. Integration and testing at the site over the fiber optic communication system routing with local control from CCTV camera and remote control from the East Los Angeles (ELA) Hub building.

The communication system routing cutover of the modified system shall be between the existing East Los Angeles (ELA) Hub building, the existing data node 1 in the existing East Los Angeles (ELA) Hub building, and the various field elements.

To minimize downtime of the system, communication system routing cutover shall begin after the following tasks have been performed:

- 1) Perform manufacturer recommended pre-installation tests on all new cables.
- 2) Perform pre-installation tests on all new communication system routing elements.
- 3) Install and test the entire project cable plant.
- 4) Test fiber optic cable links between the existing East Los Angeles (ELA) Hub building and the various field elements.
- 5) Perform subsystem testing on all affected channel cards, data links, and video links.

All testing listed above shall be performed as described in "System Testing and Documentation," elsewhere in these special provisions.

The Contractor shall provide a detailed communication system routing cutover plan to the Engineer for approval, at least 20 working days prior to the beginning of communication system routing cutover. The cutover plan shall be designed to minimize the downtime of each field site. The Contractor shall coordinate all communication system routing cutover activity with the Engineer.

Except as otherwise provided in these special provisions, communication with ramp metering and traffic monitoring station system controllers shall be interrupted only during the hours specified and under the restrictions listed elsewhere in these special provisions.

Full compensation for communication system routing cutover shall be considered as included in the contract lump sum price paid for communication system routing (modify) and no separate payment will be made therefor.

### **10-3.23 REMOVING, DISPOSING OR SALVAGING ELECTRICAL EQUIPMENT**

Salvaged electrical materials shall be hauled to Department of Transportation, Electrical Maintenance Yard, at 9123 Lower Azusa Avenue, Rosemead, CA, 91770, or to a location within 50 miles, as directed by the Engineer, and by appointment only, prior to delivery.

The Contractor shall provide the equipment and materials, as necessary, to clean, to safely unload, and stockpile the salvaged electrical material. A minimum of 5 working days' notice shall be given to the Engineer prior to delivery.

Full compensation for removing, disposing or salvaging electrical equipment shall be considered as included in the contract lump sum price paid for lighting and sign illumination and no separate payment will be made.

### **10-3.24 DISPOSING OF ELECTRICAL EQUIPMENT**

Ballasts and transformers that contain polychlorinated biphenyl (PCB) are designated as extremely hazardous wastes and mercury lamps are designated as hazardous wastes under Title 22, Chapter 30, Article 9, Section 66680, of the California Code of Regulations.

The following electrical materials on the project are known to contain polychlorinated biphenyl (PCB):

- A. Mercury lamps
- B. Ballasts and transformers.

When 25 or more mercury lamps, are to be disposed of, the lamps shall be treated as recyclable hazardous waste and shall be recycled within the State of California in conformance with Title 22, Chapter 30, Article 12, of the California Code of Regulations by a currently certified recycler such as, but not limited to, the following:

- A. Exceltrans Inc., P.O. Box 866, Benicia, CA 94510, Telephone (707) 745-8907.
- B. Roberts Enterprises, 2021 South Myrtle Avenue, Monrovia, CA 91016, Telephone (818) 303-2053.

The recyclable hazardous waste shall be packaged and then shipped via a currently certified hauler in conformance with Title 22, Chapter 30, Article 12, of the California Code of Regulations and other applicable local, State, and Federal regulations.

The Engineer shall be furnished with a statement noting which certified hauler and which certified recycler is proposed for utilization, together with a copy of the recycler's interim status document or a copy of the variance letter from the Department of Health Services. The statement shall be furnished within 15 calendar days after the contract has been approved by the Attorney General.

The State assumes generator responsibility for these wastes. The Engineer will prepare the Hazardous Waste Manifest for Shipment.

Full compensation for hauling, stockpiling, and disposing of mercury lamps shall be considered as included in the contract price paid for the electrical item involved and no additional compensation will be allowed therefor

After removal, handling and disposing of electrical material containing polychlorinated biphenyl (PCB) will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

### **10-3.25 PAYMENT**

Other roadway lighting on the project shall be considered as included in the contract lump sum price paid for lighting and sign illumination

The contract lump sum price paid for lighting and sign illumination (temporary) shall include full compensation for furnishing all labor, tools, equipment, and incidentals, and for doing all work involved in temporary lighting and sign illumination, complete in place, including furnishing and installing service equipment enclosures, conduits, conductors, span wires, temporary wood poles, luminaires and mast arms, and pull boxes, as shown on the plans, as specified in Standard Specifications and these special provisions, and as directed by the Engineer.

The contract unit price paid for communication conduit (bridge) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in communication conduit (bridge), complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The contract lump sum price paid for communication system routing (modify) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in communication system routing (modify), including system testing and documentation, communication system routing cutover, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The contract lump sum price paid for modify lighting and sign illumination shall include full compensation for furnishing all labor, tools, equipment, and incidentals, and for doing all work involved in modifying lighting and sign illumination, complete in place, including hauling, stockpiling, and disposing of mercury lamps, as shown on the plans, as specified in Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for arranging for a qualified technician employed by the various cable and communication equipment manufacturers, or their representatives, shall be considered as included in the contract price paid for the items involved and no additional compensation will be allowed therefor.

Full compensation for system testing shall be considered as included in the contract lump sum price paid for communication system routing (modify) and no additional compensation will be allowed therefor.

**SECTION 11. (BLANK)**

**SECTION 12. (BLANK)**

**SECTION 13. (BLANK)**

**SECTION 14 FEDERAL REQUIREMENTS FOR FEDERAL-AID CONSTRUCTION PROJECTS**

**GENERAL.**—The work herein proposed will be financed in whole or in part with Federal funds, and therefore all of the statutes, rules and regulations promulgated by the Federal Government and applicable to work financed in whole or in part with Federal funds will apply to such work. The "Required Contract Provisions, Federal-Aid Construction Contracts, Form FHWA 1273, are included in this Section 14. Whenever in said required contract provisions references are made to "SHA contracting officer", "SHA resident engineer", or "authorized representative of the SHA", such references shall be construed to mean "Engineer" as defined in Section 1-1.18 of the Standard Specifications.

**PERFORMANCE OF PREVIOUS CONTRACT.**—In addition to the provisions in Section II, "Nondiscrimination," and Section VII, "Subletting or Assigning the Contract," of the required contract provisions, the Contractor shall comply with the following:

The bidder shall execute the CERTIFICATION WITH REGARD TO THE PERFORMANCE OF PREVIOUS CONTRACTS OR SUBCONTRACTS SUBJECT TO THE EQUAL OPPORTUNITY CLAUSE AND THE FILING OF REQUIRED REPORTS located in the proposal. No request for subletting or assigning any portion of the contract in excess of \$10,000 will be considered under the provisions of Section VII of the required contract provisions unless such request is accompanied by the CERTIFICATION referred to above, executed by the proposed subcontractor.

**NON-COLLUSION PROVISION.**—The provisions in this section are applicable to all contracts except contracts for Federal Aid Secondary projects.

Title 23, United States Code, Section 112, requires as a condition precedent to approval by the Federal Highway Administrator of the contract for this work that each bidder file a sworn statement executed by, or on behalf of, the person, firm, association, or corporation to whom such contract is to be awarded, certifying that such person, firm, association, or corporation has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with the submitted bid. A form to make the non-collusion affidavit statement required by Section 112 as a certification under penalty of perjury rather than as a sworn statement as permitted by 28, USC, Sec. 1746, is included in the proposal.

**PARTICIPATION BY MINORITY BUSINESS ENTERPRISES IN SUBCONTRACTING.**—Part 23, Title 49, Code of Federal Regulations applies to this Federal-aid project. Pertinent sections of said Code are incorporated in part or in its entirety within other sections of these special provisions.

Schedule B—Information for Determining Joint Venture Eligibility

(This form need not be filled in if all joint venture firms are minority owned.)

1. Name of joint venture \_\_\_\_\_
2. Address of joint venture \_\_\_\_\_
3. Phone number of joint venture \_\_\_\_\_
4. Identify the firms which comprise the joint venture. (The MBE partner must complete Schedule A.) \_\_\_\_\_  
\_\_\_\_\_  
  - a. Describe the role of the MBE firm in the joint venture. \_\_\_\_\_
  - b. Describe very briefly the experience and business qualifications of each non-MBE joint venturer: \_\_\_\_\_  
\_\_\_\_\_
5. Nature of the joint venture's business \_\_\_\_\_
6. Provide a copy of the joint venture agreement.
7. What is the claimed percentage of MBE ownership? \_\_\_\_\_
8. Ownership of joint venture: (This need not be filled in if described in the joint venture agreement, provided by question 6.).
  - a. Profit and loss sharing.
  - b. Capital contributions, including equipment.

- c. Other applicable ownership interests.
9. Control of and participation in this contract. Identify by name, race, sex, and "firm" those individuals (and their titles) who are responsible for day-to-day management and policy decision making, including, but not limited to, those with prime responsibility for:
- a. Financial decisions \_\_\_\_\_
  - b. Management decisions, such as:
    - (1) Estimating \_\_\_\_\_
    - (2) Marketing and sales \_\_\_\_\_
    - (3) Hiring and firing of management personnel \_\_\_\_\_
    - (4) Purchasing of major items or supplies \_\_\_\_\_
  - c. Supervision of field operations \_\_\_\_\_

Note.—If, after filing this Schedule B and before the completion of the joint venture's work on the contract covered by this regulation, there is any significant change in the information submitted, the joint venture must inform the grantee, either directly or through the prime contractor if the joint venture is a subcontractor.

**Affidavit**

"The undersigned swear that the foregoing statements are correct and include all material information necessary to identify and explain the terms and operation of our joint venture and the intended participation by each joint venturer in the undertaking. Further, the undersigned covenant and agree to provide to grantee current, complete and accurate information regarding actual joint venture work and the payment therefor and any proposed changes in any of the joint venture arrangements and to permit the audit and examination of the books, records and files of the joint venture, or those of each joint venturer relevant to the joint venture, by authorized representatives of the grantee or the Federal funding agency. Any material misrepresentation will be grounds for terminating any contract which may be awarded and for initiating action under Federal or State laws concerning false statements."

Name of Firm	Name of Firm
Signature	Signature
Name	Name
Title	Title
Date	Date

Date \_\_\_\_\_

State of \_\_\_\_\_

County of \_\_\_\_\_

On this \_\_\_\_ day of \_\_\_\_\_, 19 \_\_, before me appeared (Name) \_\_\_\_\_, to me personally known, who, being duly sworn, did execute the foregoing affidavit, and did state that he or she was properly authorized by (Name of firm) \_\_\_\_\_ to execute the affidavit and did so as his or her free act and deed.

Notary Public \_\_\_\_\_

Commission expires \_\_\_\_\_

[Seal]

Date \_\_\_\_\_

State of \_\_\_\_\_

County of \_\_\_\_\_

On this \_\_\_\_ day of \_\_\_\_\_, 19 \_\_, before me appeared (Name) \_\_\_\_\_ to me personally known, who, being duly sworn, did execute the foregoing affidavit, and did state that he or she was properly authorized by (Name of firm) \_\_\_\_\_ to execute the affidavit and did so as his or her free act and deed.

Notary Public \_\_\_\_\_

Commission expires \_\_\_\_\_

[Seal]

**REQUIRED CONTRACT PROVISIONS  
FEDERAL-AID CONSTRUCTION CONTRACTS**

**I. GENERAL**

1. These contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.
2. Except as otherwise provided for in each section, the contractor shall insert in each subcontract all of the stipulations contained in these Required Contract Provisions, and further require their inclusion in any lower tier subcontract or purchase order that may in turn be made. The Required Contract Provisions shall not be incorporated by reference in any case. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with these Required Contract Provisions.
3. A breach of any of the stipulations contained in these Required Contract Provisions shall be sufficient grounds for termination of the contract.
4. A breach of the following clauses of the Required Contract Provisions may also be grounds for debarment as provided in 29 CFR 5.12:

Section I, paragraph 2;  
Section IV, paragraphs 1, 2, 3, 4, and 7;  
Section V, paragraphs 1 and 2a through 2g.

5. Disputes arising out of the labor standards provisions of Section IV (except paragraph 5) and Section V of these Required Contract Provisions shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the U.S. Department of Labor (DOL) as set forth in 29 CFR 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the DOL, or the contractor's employees or their representatives.
6. **Selection of Labor:** During the performance of this contract, the contractor shall not:
  - a. discriminate against labor from any other State, possession, or territory of the United States (except for employment preference for Appalachian contracts, when applicable, as specified in Attachment A), or
  - b. employ convict labor for any purpose within the limits of the project unless it is labor performed by convicts who are on parole, supervised release, or probation.

**II. NONDISCRIMINATION**

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

1. **Equal Employment Opportunity:** Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630, and 41 CFR 60) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The Equal Opportunity Construction Contract Specifications set forth under 41 CFR 60-4.3 and the provisions of the American Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:
  - a. The contractor will work with the State highway agency (SHA) and the Federal Government in carrying out EEO obligations and in their review of his/her activities under the contract.
  - b. The contractor will accept as his operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, preapprenticeship, and/or on-the-job training."

2. **EEO Officer:** The contractor will designate and make known to the SHA contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active contractor program of EEO and who must be assigned adequate authority and responsibility to do so.
3. **Dissemination of Policy:** All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:
  - a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.
  - b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.
  - c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minority group employees.
  - d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.
  - e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.
4. **Recruitment:** When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minority groups in the area from which the project work force would normally be derived.
  - a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minority group applicants. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority group applicants may be referred to the contractor for employment consideration.
  - b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, he is expected to observe the provisions of that agreement to the extent that the system permits the contractor's compliance with EEO contract provisions. (The DOL has held that where implementation of such agreements have the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Executive Order 11246, as amended.)
  - c. The contractor will encourage his present employees to refer minority group applicants for employment. Information and procedures with regard to referring minority group applicants will be discussed with employees.
5. **Personnel Actions:** Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:

- a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.
  - b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.
  - c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.
  - d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with his obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of his avenues of appeal.
6. Training and Promotion:
- a. The contractor will assist in locating, qualifying, and increasing the skills of minority group and women employees, and applicants for employment.
  - b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. Where feasible, 25 percent of apprentices or trainees in each occupation shall be in their first year of apprenticeship or training. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision.
  - c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.
  - d. The contractor will periodically review the training and promotion potential of minority group and women employees and will encourage eligible employees to apply for such training and promotion.
7. **Unions:** If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use his/her best efforts to obtain the cooperation of such unions to increase opportunities for minority groups and women within the unions, and to effect referrals by such unions of minority and female employees. Actions by the contractor either directly or through a contractor's association acting as agent will include the procedures set forth below:
- a. The contractor will use best efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minority group members and women for membership in the unions and increasing the skills of minority group employees and women so that they may qualify for higher paying employment.
  - b. The contractor will use best efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.
  - c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the SHA and shall set forth what efforts have been made to obtain such information.
  - d. In the event the union is unable to provide the contractor with a reasonable flow of minority and women referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through

independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minority group persons and women. (The DOL has held that it shall be no excuse that the union with which the contractor has a collective bargaining agreement providing for exclusive referral failed to refer minority employees.) In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the SHA.

8. **Selection of Subcontractors, Procurement of Materials and Leasing of Equipment:** The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment.
  - a. The contractor shall notify all potential subcontractors and suppliers of his/her EEO obligations under this contract.
  - b. Disadvantaged business enterprises (DBE), as defined in 49 CFR 23, shall have equal opportunity to compete for and perform subcontracts which the contractor enters into pursuant to this contract. The contractor will use his best efforts to solicit bids from and to utilize DBE subcontractors or subcontractors with meaningful minority group and female representation among their employees. Contractors shall obtain lists of DBE construction firms from SHA personnel.
  - c. The contractor will use his best efforts to ensure subcontractor compliance with their EEO obligations.
9. **Records and Reports:** The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the SHA and the FHWA.
  - a. The records kept by the contractor shall document the following:
    - (1) The number of minority and non-minority group members and women employed in each work classification on the project;
    - (2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women;
    - (3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minority and female employees; and
    - (4) The progress and efforts being made in securing the services of DBE subcontractors or subcontractors with meaningful minority and female representation among their employees.
  - b. The contractors will submit an annual report to the SHA each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form FHWA-1391. If on-the-job training is being required by special provision, the contractor will be required to collect and report training data.

### III. NONSEGREGATED FACILITIES

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

- a. By submission of this bid, the execution of this contract or subcontract, or the consummation of this material supply agreement or purchase order, as appropriate, the bidder, Federal-aid construction contractor, subcontractor, material supplier, or vendor, as appropriate, certifies that the firm does not maintain or provide for its employees any segregated facilities at any of its establishments, and that the firm does not permit its employees to perform their services at any location, under its control, where segregated facilities are maintained. The firm agrees that a breach of this certification is a violation of the EEO provisions of this contract. The firm further certifies that no employee will be denied access to adequate facilities on the basis of sex or disability.

- b. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms and washrooms, restaurants and other eating areas, time clocks, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive, or are, in fact, segregated on the basis of race, color, religion, national origin, age or disability, because of habit, local custom, or otherwise. The only exception will be for the disabled when the demands for accessibility override (e.g. disabled parking).
- c. The contractor agrees that it has obtained or will obtain identical certification from proposed subcontractors or material suppliers prior to award of subcontracts or consummation of material supply agreements of \$10,000 or more and that it will retain such certifications in its files.

#### **IV. PAYMENT OF PREDETERMINED MINIMUM WAGE**

(Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural minor collectors, which are exempt.)

##### **1. General:**

- a. All mechanics and laborers employed or working upon the site of the work will be paid unconditionally and not less often than once a week and without subsequent deduction or rebate on any account [except such payroll deductions as are permitted by regulations (29 CFR 3)] issued by the Secretary of Labor under the Copeland Act (40 U.S.C. 276c) the full amounts of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment. The payment shall be computed at wage rates not less than those contained in the wage determination of the Secretary of Labor (hereinafter "the wage determination") which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor or its subcontractors and such laborers and mechanics. The wage determination (including any additional classifications and wage rates conformed under paragraph 2 of this Section IV and the DOL poster (WH-1321) or Form FHWA-1495) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers. For the purpose of this Section, contributions made or costs reasonably anticipated for bona fide fringe benefits under Section 1(b)(2) of the Davis-Bacon Act (40 U.S.C. 276a) on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of Section IV, paragraph 3b, hereof. Also, for the purpose of this Section, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs, which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in paragraphs 4 and 5 of this Section IV.
- b. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein, provided, that the employer's payroll records accurately set forth the time spent in each classification in which work is performed.
- c. All rulings and interpretations of the Davis-Bacon Act and related acts contained in 29 CFR 1, 3, and 5 are herein incorporated by reference in this contract.

##### **2. Classification:**

- a. The SHA contracting officer shall require that any class of laborers or mechanics employed under the contract, which is not listed in the wage determination, shall be classified in conformance with the wage determination.
- b. The contracting officer shall approve an additional classification, wage rate and fringe benefits only when the following criteria have been met:
  - (1) the work to be performed by the additional classification requested is not performed by a classification in the wage determination;
  - (2) the additional classification is utilized in the area by the construction industry;

- (3) the proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination; and
  - (4) with respect to helpers, when such a classification prevails in the area in which the work is performed.
- c. If the contractor or subcontractors, as appropriate, the laborers and mechanics (if known) to be employed in the additional classification or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the DOL, Administrator of the Wage and Hour Division, Employment Standards Administration, Washington, D.C. 20210. The Wage and Hour Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
  - d. In the event the contractor or subcontractors, as appropriate, the laborers or mechanics to be employed in the additional classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. Said Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary
  - e. The wage rate (including fringe benefits where appropriate) determined pursuant to paragraph 2c or 2d of this Section IV shall be paid to all workers performing work in the additional classification from the first day on which work is performed in the classification.

**3. Payment of Fringe Benefits:**

- a. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor or subcontractors, as appropriate, shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly case equivalent thereof.
- b. If the contractor or subcontractor, as appropriate, does not make payments to a trustee or other third person, he/she may consider as a part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, provided, that the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

**4. Apprentices and Trainees (Programs of the U.S. DOL) and Helpers:**

a. Apprentices:

- (1) Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the DOL, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State apprenticeship agency recognized by the Bureau, or if a person is employed in his/her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State apprenticeship agency (where appropriate) to be eligible for probationary employment as an apprentice.
- (2) The allowable ratio of apprentices to journeyman-level employees on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any employee listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate listed in the wage determination for the classification of work actually performed. In addition, any apprentice performing

work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor or subcontractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman-level hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.

- (3) Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator for the Wage and Hour Division determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.
- (4) In the event the Bureau of Apprenticeship and Training, or a State apprenticeship agency recognized by the Bureau, withdraws approval of an apprenticeship program, the contractor or subcontractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the comparable work performed by regular employees until an acceptable program is approved.

b. Trainees:

- (1) Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the DOL, Employment and Training Administration.
- (2) The ratio of trainees to journeyman-level employees on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.
- (3) Every trainee must be paid at not less than the rate specified in the approved program for his/her level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman-level wage rate on the wage determination which provides for less than full fringe benefits for apprentices, in which case such trainees shall receive the same fringe benefits as apprentices.
- (4) In the event the Employment and Training Administration withdraws approval of a training program, the contractor or subcontractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. Helpers:

Helpers will be permitted to work on a project if the helper classification is specified and defined on the applicable wage determination or is approved pursuant to the conformance procedure set forth in Section IV.2. Any worker listed on a payroll at a helper wage rate, who is not a helper under an approved definition, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed.

**5. Apprentices and Trainees (Programs of the U.S. DOT):**

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

**6. Withholding:**

The SHA shall upon its own action or upon written request of an authorized representative of the DOL withhold, or cause to be withheld, from the contractor or subcontractor under this contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to Davis-Bacon prevailing wage requirements which is held by the same prime contractor, as much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the SHA contracting officer may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

**7. Overtime Requirements:**

No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers, mechanics, watchmen, or guards (including apprentices, trainees, and helpers described in paragraphs 4 and 5 above) shall require or permit any laborer, mechanic, watchman, or guard in any workweek in which he/she is employed on such work, to work in excess of 40 hours in such workweek unless such laborer, mechanic, watchman, or guard receives compensation at a rate not less than one-and-one-half times his/her basic rate of pay for all hours worked in excess of 40 hours in such workweek.

**8. Violation:**

Liability for Unpaid Wages; Liquidated Damages: In the event of any violation of the clause set forth in paragraph 7 above, the contractor and any subcontractor responsible thereof shall be liable to the affected employee for his/her unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory) for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer, mechanic, watchman, or guard employed in violation of the clause set forth in paragraph 7, in the sum of \$10 for each calendar day on which such employee was required or permitted to work in excess of the standard work week of 40 hours without payment of the overtime wages required by the clause set forth in paragraph 7.

**9. Withholding for Unpaid Wages and Liquidated Damages:**

The SHA shall upon its own action or upon written request of any authorized representative of the DOL withhold, or cause to be withheld, from any monies payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph 8 above.

## V. STATEMENTS AND PAYROLLS

(Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural collectors, which are exempt.)

1. Compliance with Copeland Regulations (29 CFR 3):

The contractor shall comply with the Copeland Regulations of the Secretary of Labor which are herein incorporated by reference.

2. Payrolls and Payroll Records:

- a. Payrolls and basic records relating thereto shall be maintained by the contractor and each subcontractor during the course of the work and preserved for a period of 3 years from the date of completion of the contract for all laborers, mechanics, apprentices, trainees, watchmen, helpers, and guards working at the site of the work.
- b. The payroll records shall contain the name, social security number, and address of each such employee; his or her correct classification; hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalent thereof the types described in Section 1(b)(2)(B) of the Davis Bacon Act); daily and weekly number of hours worked; deductions made; and actual wages paid. In addition, for Appalachian contracts, the payroll records shall contain a notation indicating whether the employee does, or does not, normally reside in the labor area as defined in Attachment A, paragraph 1. Whenever the Secretary of Labor, pursuant to Section IV, paragraph 3b, has found that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in Section 1(b)(2)(B) of the Davis Bacon Act, the contractor and each subcontractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, that the plan or program has been communicated in writing to the laborers or mechanics affected, and show the cost anticipated or the actual cost incurred in providing benefits. Contractors or subcontractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprentices and trainees, and ratios and wage rates prescribed in the applicable programs.
- c. Each contractor and subcontractor shall furnish, each week in which any contract work is performed, to the SHA resident engineer a payroll of wages paid each of its employees (including apprentices, trainees, and helpers, described in Section IV, paragraphs 4 and 5, and watchmen and guards engaged on work during the preceding weekly payroll period). The payroll submitted shall set out accurately and completely all of the information required to be maintained under paragraph 2b of this Section V. This information may be submitted in any form desired. Optional Form WH-347 is available for this purpose and may be purchased from the Superintendent of Documents (Federal stock number 029-005-0014-1), U.S. Government Printing Office, Washington, D.C. 20402. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors.
- d. Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his/her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:
  - (1) that the payroll for the payroll period contains the information required to be maintained under paragraph 2b of this Section V and that such information is correct and complete;
  - (2) that such laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR 3;
  - (3) that each laborer or mechanic has been paid not less than the applicable wage rate and fringe benefits or cash equivalent for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.
- e. The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 2d of this Section V.
- f. The falsification of any of the above certifications may subject the contractor to civil or criminal prosecution under 18 U.S.C. 1001 and 31 U.S.C. 231.
- g. The contractor or subcontractor shall make the records required under paragraph 2b of this Section V available for inspection, copying, or transcription by authorized representatives of the SHA, the FHWA, or the DOL, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the SHA, the FHWA, the DOL, or all may, after written notice to the contractor, sponsor, applicant, or owner, take such actions as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure

to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

#### **VI. RECORD OF MATERIALS, SUPPLIES, AND LABOR**

1. On all Federal-aid contracts on the National Highway System, except those which provide solely for the installation of protective devices at railroad grade crossings, those which are constructed on a force account or direct labor basis, highway beautification contracts, and contracts for which the total final construction cost for roadway and bridge is less than \$1,000,000 (23 CFR 635) the contractor shall:
  - a. Become familiar with the list of specific materials and supplies contained in Form FHWA-47, "Statement of Materials and Labor Used by Contractor of Highway Construction Involving Federal Funds," prior to the commencement of work under this contract.
  - b. Maintain a record of the total cost of all materials and supplies purchased for and incorporated in the work, and also of the quantities of those specific materials and supplies listed on Form FHWA-47, and in the units shown on Form FHWA-47.
  - c. Furnish, upon the completion of the contract, to the SHA resident engineer on Form FHWA-47 together with the data required in paragraph 1b relative to materials and supplies, a final labor summary of all contract work indicating the total hours worked and the total amount earned.
2. At the prime contractor's option, either a single report covering all contract work or separate reports for the contractor and for each subcontract shall be submitted.

#### **VII. SUBLETTING OR ASSIGNING THE CONTRACT**

1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the State. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635).
  - a. "Its own organization" shall be construed to include only workers employed and paid directly by the prime contractor and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor, assignee, or agent of the prime contractor.
  - b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid on the contract as a whole and in general are to be limited to minor components of the overall contract.
2. The contract amount upon which the requirements set forth in paragraph 1 of Section VII is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.
3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the SHA contracting officer determines is necessary to assure the performance of the contract.
4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the SHA contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the SHA has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

## **VIII. SAFETY: ACCIDENT PREVENTION**

1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the SHA contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.
2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).
3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).

## **IX. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS**

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, the following notice shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

### **Notice To All Personnel Engaged On Federal-Aid Highway Projects**

18 U.S.C. 1020 READS AS FOLLOWS:

"Whoever being an officer, agent, or employee of the United States, or any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined not more than \$10,000 or imprisoned not more than 5 years or both."

## **X. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT**

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$100,000 or more.)

By submission of this bid or the execution of this contract, or subcontract, as appropriate, the bidder, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

1. That any facility that is or will be utilized in the performance of this contract, unless such contract is exempt under the Clean Air Act, as amended (42 U.S.C. 1857 et seq., as amended by Pub.L. 91-604), and under the Federal Water

Pollution Control Act, as amended (33 U.S.C. 1251 et seq., as amended by Pub.L. 92-500), Executive Order 11738, and regulations in implementation thereof (40 CFR 15) is not listed, on the date of contract award, on the U.S. Environmental Protection Agency (EPA) List of Violating Facilities pursuant to 40 CFR 15.20.

2. That the firm agrees to comply and remain in compliance with all the requirements of Section 114 of the Clean Air Act and Section 308 of the Federal Water Pollution Control Act and all regulations and guidelines listed thereunder.
3. That the firm shall promptly notify the SHA of the receipt of any communication from the Director, Office of Federal Activities, EPA, indicating that a facility that is or will be utilized for the contract is under consideration to be listed on the EPA List of Violating Facilities.
4. That the firm agrees to include or cause to be included the requirements of paragraph 1 through 4 of this Section X in every nonexempt subcontract, and further agrees to take such action as the government may direct as a means of enforcing such requirements.

## **XI. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION**

### **1. Instructions for Certification - Primary Covered Transactions:**

(Applicable to all Federal-aid contracts - 49 CFR 29)

- a. By signing and submitting this proposal, the prospective primary participant is providing the certification set out below.
- b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective primary participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.
- c. The certification in this clause is a material representation of fact upon which reliance was placed when the department or agency determined to enter into this transaction. If it is later determined that the prospective primary participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause of default.
- d. The prospective primary participant shall provide immediate written notice to the department or agency to whom this proposal is submitted if any time the prospective primary participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- e. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the department or agency to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- f. The prospective primary participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.
- g. The prospective primary participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," provided by the department or agency entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

- h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the nonprocurement portion of the "Lists of Parties Excluded From Federal Procurement or Nonprocurement Programs" (Nonprocurement List) which is compiled by the General Services Administration.
- i. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- j. Except for transactions authorized under paragraph f of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

**Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion — Primary Covered Transactions**

1. The prospective primary participant certifies to the best of its knowledge and belief, that it and its principals:
  - a. Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
  - b. Have not within a 3-year period preceding this proposal been convicted of or had a civil judgement rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;
  - c. Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph 1b of this certification; and
  - d. Have not within a 3-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
2. Where the prospective primary participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

**2. Instructions for Certification - Lower Tier Covered Transactions:**

(Applicable to all subcontracts, purchase orders and other lower tier transactions of \$25,000 or more - 49 CFR 29)

- a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.
- b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.
- c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.
- d. The terms "covered transaction," "debarred," "suspended," "ineligible," "primary covered transaction," "participant," "person," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the

meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations.

- e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.
- f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
- g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the Nonprocurement List.
- h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

#### **Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion — Lower Tier Covered Transactions**

1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.
2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

#### **XII. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING**

(Applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 - 49 CFR 20)

1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:
  - a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
  - b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or

employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.

2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.
3. The prospective participant also agrees by submitting his or her bid or proposal that he or she shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

**FEDERAL-AID FEMALE AND MINORITY GOALS**

In accordance with Section II, "Nondiscrimination," of "Required Contract Provisions Federal-aid Construction Contracts" the following are the goals for female utilization:

Goal for Women (applies nationwide).....(percent) 6.9

The following are goals for minority utilization:

**CALIFORNIA ECONOMIC AREA**

		<b>Goal (Percent)</b>
<b>174</b>	<b>Redding, CA:</b> Non-SMSA Counties CA Lassen; CA Modoc; CA Plumas; CA Shasta; CA Siskiyou; CA Tehama.	6.8
<b>175</b>	<b>Eureka, CA</b> Non-SMSA Counties CA Del Norte; CA Humboldt; CA Trinity.	6.6
<b>176</b>	<b>San Francisco-Oakland-San Jose, CA:</b> SMSA Counties: 7120 Salinas-Seaside-Monterey, CA CA Monterey. 7360 San Francisco-Oakland CA Alameda; CA Contra Costa; CA Marin; CA San Francisco; CA San Mateo. 7400 San Jose, CA CA Santa Clara. 7485 Santa Cruz, CA. CA Santa Cruz. 7500 Santa Rosa, CA CA Sonoma. 8720 Vallejo-Fairfield- Napa, CA CA Napa; CA Solano Non-SMSA Counties CA Lake; CA Mendocino; CA San Benito	28.9 25.6 19.6 14.9 9.1 17.1 23.2
<b>177</b>	<b>Sacramento, CA:</b> SMSA Counties: 6920 Sacramento, CA CA Placer; CA Sacramento; CA Yolo. Non-SMSA Counties CA Butte; CA Colusa; CA El Dorado; CA Glenn; CA Nevada; CA Sierra; CA Sutter; CA Yuba.	16.1 14.3
<b>178</b>	<b>Stockton-Modesto, CA:</b> SMSA Counties: 5170 Modesto, CA CA Stanislaus. 8120 Stockton, CA CA San Joaquin. Non-SMSA Counties CA Alpine; CA Amador; CA Calaveras; CA Mariposa; CA Merced; CA Tuolumne.	12.3 24.3 19.8

		<b>Goal (Percent)</b>
<b>179</b>	<b>Fresno-Bakersfield, CA</b>	
	SMSA Counties:	
	0680 Bakersfield, CA CA Kern.	19.1
	2840 Fresno, CA CA Fresno.	26.1
	Non-SMSA Counties CA Kings; CA Madera; CA Tulare.	23.6
<b>180</b>	<b>Los Angeles, CA:</b>	
	SMSA Counties:	
	0360 Anaheim-Santa Ana-Garden Grove, CA CA Orange.	11.9
	4480 Los Angeles-Long Beach, CA CA Los Angeles.	28.3
	6000 Oxnard-Simi Valley-Ventura, CA CA Ventura.	21.5
	6780 Riverside-San Bernardino-Ontario, CA. CA Riverside; CA San Bernardino.	19.0
	7480 Santa Barbara-Santa Maria-Lompoc, CA CA Santa Barbara.	19.7
	Non-SMSA Counties CA Inyo; CA Mono; CA San Luis Obispo.	24.6
<b>181</b>	<b>San Diego, CA:</b>	
	SMSA Counties	
	7320 San Diego, CA. CA San Diego.	16.9
	Non-SMSA Counties CA Imperial.	18.2

In addition to the reporting requirements set forth elsewhere in this contract the Contractor and subcontractors holding subcontracts, not including material suppliers, of \$10,000 or more, shall submit for every month of July during which work is performed, employment data as contained under Form FHWA PR-1391 (Appendix C to 23 CFR, Part 230), and in accordance with the instructions included thereon.

## FEDERAL REQUIREMENT TRAINING SPECIAL PROVISIONS

As part of the Contractor's equal employment opportunity affirmative action program, training shall be provided as follows:

The Contractor shall provide on-the-job training to develop full journeymen in the types of trades or job classification involved.

The goal for the number of trainees or apprentices to be trained under the requirements of this special provision will be 4.

In the event the Contractor subcontracts a portion of the contract work, he shall determine how many, if any, of the trainees or apprentices are to be trained by the subcontractor, provided however, that the Contractor shall retain the primary responsibility for meeting the training requirements imposed by this special provision. The Contractor shall also insure that this Training Special Provision is made applicable to such subcontract. Where feasible, 25 percent of trainees or apprentices in each occupation shall be in their first year of apprenticeship or training.

The number of trainees or apprentices shall be distributed among the work classifications on the basis of the Contractor's needs and the availability of journeymen in the various classifications within a reasonable area of recruitment. Prior to commencing work, the Contractor shall submit to the Department for approval the number of trainees or apprentices to be trained in each selected classification and training program to be used. Furthermore, the Contractor shall specify the starting time for training in each of the classifications. The Contractor will be credited for each trainee or apprentice employed by him on the contract work who is currently enrolled or becomes enrolled in an approved program and will be reimbursed for such trainees or apprentices as provided hereinafter.

Training and upgrading of minorities and women toward journeymen status is a primary objective of this Training Special Provision. Accordingly, the Contractor shall make every effort to enroll minority and women trainees or apprentices (e.g., by conducting systematic and direct recruitment through public and private sources likely to yield minority and women trainees or apprentices) to the extent such persons are available within a reasonable area of recruitment. The Contractor will be responsible for demonstrating the steps that he has taken in pursuance thereof, prior to a determination as to whether the Contractor is in compliance with this Training Special Provision. This training commitment is not intended, and shall not be used, to discriminate against any applicant for training, whether a member of a minority group or not.

No employee shall be employed as a trainee or apprentice in any classification in which he has successfully completed a training course leading to journeyman status or in which he has been employed as a journeyman. The Contractor should satisfy this requirement by including appropriate questions in the employee application or by other suitable means. Regardless of the method used the Contractor's records should document the findings in each case.

The minimum length and type of training for each classification will be as established in the training program selected by the Contractor and approved by both the Department and the Federal Highway Administration. The Department and the Federal Highway Administration will approve a program if it is reasonably calculated to meet the equal employment opportunity obligations of the Contractor and to qualify the average trainee or apprentice for journeyman status in the classification concerned by the end of the training period. Furthermore, apprenticeship programs registered with the U.S. Department of Labor, Bureau of Apprenticeship and Training, or with the State of California, Department of Industrial Relations, Division of Apprenticeship Standards recognized by the Bureau and training programs approved but not necessarily sponsored by the U.S. Department of Labor, Manpower Administration, Bureau of Apprenticeship and Training shall also be considered acceptable provided it is being administered in a manner consistent with the equal employment obligations of Federal-aid highway construction contracts. Approval or acceptance of a training program shall be obtained from the State prior to commencing work on the classification covered by the program. It is the intention of these provisions that training is to be provided in the construction crafts rather than clerk-typists or secretarial-type positions. Training is permissible in lower level management positions such as office engineers, estimators, timekeepers, etc., where the training is oriented toward construction applications. Training in the laborer classification may be permitted provided that significant and meaningful training is provided and approved by the division office. Some offsite training is permissible as long as the training is an integral part of an approved training program and does not comprise a significant part of the overall training.

Except as otherwise noted below, the Contractor will be reimbursed 80 cents per hour of training given an employee on this contract in accordance with an approved training program. As approved by the Engineer, reimbursement will be made for training of persons in excess of the number specified herein. This reimbursement will be made even though the Contractor receives additional training program funds from other sources, provided such other source does not specifically prohibit the Contractor from receiving other reimbursement. Reimbursement for offsite training indicated above may only be made to the Contractor where he does one or more of the following and the trainees or apprentices are concurrently employed on a Federal-aid project; contributes to the cost of the training, provides the instruction to the trainee or apprentice or pays the trainee's or apprentice's wages during the offsite training period.

No payment shall be made to the Contractor if either the failure to provide the required training, or the failure to hire the trainee or apprentice as a journeyman, is caused by the Contractor and evidences a lack of good faith on the part of the

Contractor in meeting the requirements of this Training Special Provision. It is normally expected that a trainee or apprentice will begin his training on the project as soon as feasible after start of work utilizing the skill involved and remain on the project as long as training opportunities exist in his work classification or until he has completed his training program. It is not required that all trainees or apprentices be on board for the entire length of the contract. A Contractor will have fulfilled his responsibilities under this Training Special Provision if he has provided acceptable training to the number of trainees or apprentices specified. The number trained shall be determined on the basis of the total number enrolled on the contract for a significant period.

Only trainees or apprentices registered in a program approved by the State of California's State Administrator of Apprenticeship may be employed on the project and said trainees or apprentices shall be paid the standard wage specified under the regulations of the craft or trade at which they are employed.

The Contractor shall furnish the trainee or apprentice a copy of the program he will follow in providing the training. The Contractor shall provide each trainee or apprentice with a certification showing the type and length of training satisfactorily completed.

The Contractor will provide for the maintenance of records and furnish periodic reports documenting his performance under this Training Special Provision.