

DEPARTMENT OF TRANSPORTATION

DES-OE MS #43
1727 30TH Street, 2ND Floor
Sacramento, CA 95816



**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

September 17, 2002

07-LA-5,10,60,101,105,134,170,405,605-VAR
07-1198U4
ACNHI-405-3(032)N

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in IN LOS ANGELES COUNTY AT VARIOUS LOCATIONS.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on September 26, 2002.

This addendum is being issued to revise the Project Plans, the Notice to Contractors and Special Provisions, the Proposal and Contract, and the Federal Minimum Wages with Modification Number 13 dated 9-6-02. A copy of the modified wage rates are available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

Project Plan Sheets 6, 17, 91, 376, 377, 378, and 397 are revised. Half-sized copies of the revised sheets are attached for substitution for the like-numbered sheets.

On Project Plan Sheet No. 2, under "Notes," in note No. 5, the wording "and loop detectors" is deleted.

On Project Plan Sheet No. 286, under "CONCRETE PAVEMENT, RAPID STRENGTH CONCRETE," the following quantities are revised: "410 m³" to "429 m³" and "1006 m³" to "1025 m³."

On Project Plan Sheet No. 287, total quantity for " CONCRETE PAVEMENT, RAPID STRENGTH CONCRETE," is revised from "1006 m³" to "1025 m³."

On Project Plan Sheet No.395, the following quantities are revised:

Under the heading "SOUND WALL (RIBBED STEEL PANEL)," "1851 m²" is revised to "596 m²" and "3458 m²" to "2203 m²."

Under the heading "SOUND WALL (MASONRY BLOCK)," the quantity of "1285 m²" is added to row "Sound Wall No.370," and total is revised from "3565 m²" to "4850 m²."

Under the heading "457 MM CAST-IN-DRILLED-HOLE CONCRETE PILLING," "387 m" is revised to "120 m" and "750 m" to "483 m."

Under the heading "406 MM CAST-IN-DRILLED-HOLE CONCRETE PILLING," "9 m" is revised to "330 m" and "102 m" to "423 m."

07-LA-5,10,60,101,105,134,170,405,605-VAR
07-1198U4
ACNHI-405-3(032)N

Project Plan Sheet No. 645 immediately following project plan sheet No. 636 is deleted.

Project Plan Sheet No. 637 is added. Half-sized copy of the added sheet is attached to the project plans.

In the Special Provisions, Section 10-1.01, "ORDER OF WORK," the wording "and loop detectors" is deleted from the nineteenth paragraph and the following paragraph is added after the tenth paragraph:

"Attention is directed to Sound Wall No 381, as shown on the plans, from station 381+20 to station 381+32.73. All construction work performed in this area shall be completed from within State right of way. Existing cypress trees adjacent to this portion of sound walls shall be protected in place. Damage to the root cutting during the pile cap excavation shall be minimized."

In the Special Provisions, Section 10-1.055, "COOPERATION," is added as follows:

"10-1.055 COOPERATION

Attention is directed to Section 7-1.14, "Cooperation," and Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications and these special provisions.

It is anticipated that work by other contractors may be in progress adjacent to or within the limits of this project during progress of the work on this contract as listed below:

- A. Contract No. 07-1178U4 to widen freeway for HOV lane on Route 405 from K P 41.2 to 48.2,
- B. Contract No. 07-937184 to widen Northbound Jefferson Blvd on ramp and Southbound Jefferson Blvd onramp on Route 405 near KP 41.4 to 42.2,
- C. Contract No. 202304 to replace La Tijera Blvd Overcrossing on Route 405 near KP 39.1.
- D. Contract No. 07- 4H2204 to widen Northbound Manchester Blvd off ramp on Route 405 near KP 37.5."

In the Special Provisions, Section 10-3.055, "0.5 MM PLASTIC SHEET," is added as follows:

"10-3.055 0.5 MM PLASTIC SHEET

The 0.5 mm plastic sheet shall be furnished and installed in the trench within roadway pavement, approximately 25 mm over new communication conduits, as shown on the plans, and as directed by the Engineer. The plastic sheet will serve as a breaking plane within the slurry cement backfill. The plastic sheet shall be manufactured from high-density polyethylene (HDPE) virgin compounds or polyvinyl chloride (PVC) virgin compounds.

Full compensation for 0.5 mm plastic sheet shall be considered as included in the contract price paid per meter for the various sizes and types of conduit involved and no separate payment will be made therefor."

In the Proposal and Contract, the Engineer's Estimate Items 81, 99 and 100 are revised as attached.

To Proposal and Contract book holders:

Replace page 7 of the Engineer's Estimate in the Proposal with the attached revised page 7 of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No. 1
Page 3
September 17, 2002

07-LA-5,10,60,101,105,134,170,405,605-VAR
07-1198U4
ACNHI-405-3(032)N

This office is sending this addendum by UPS overnight mail to Proposal and Contract book holders to ensure that each receives it.

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY:

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Office Engineer

Attachments

ENGINEER'S ESTIMATE

07-1198U4

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
81	029651	CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)	M3	1025		
82 (S)	420102	GROOVE EXISTING CONCRETE PAVEMENT	M	36 400		
83 (S)	420201	GRIND EXISTING CONCRETE PAVEMENT	M2	13 800		
84 (S)	498027	400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	M	4110		
85 (F)	510053	STRUCTURAL CONCRETE, BRIDGE	M3	18		
86	510058	STRUCTURAL CONCRETE, WALL	M3	148		
87	510060	STRUCTURAL CONCRETE, RETAINING WALL	M3	1230		
88	029652	STRUCTURAL CONCRETE (CONCRETE SLAB)	M3	80		
89	510087	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	M3	288		
90 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	488		
91 (F)	731517	MINOR CONCRETE (GUTTER)	M	421		
92	510526	MINOR CONCRETE (BACKFILL)	M3	280		
93	510800	PAVING NOTCH EXTENSION	M3	4.9		
94 (F)	511063	FRACTURED FIN TEXTURE	M2	2140		
95	511106	DRILL AND BOND DOWEL	M	171		
96	513570	CONCRETE BLOCK WALL	M2	220		
97	515020	REFINISH BRIDGE DECK	M2	507		
98 (S-F)	517961	SOUND WALL (BARRIER) (MASONRY BLOCK)	M2	3775		
99 (S-F)	029653	SOUND WALL (RIBBED STEEL PANEL) (ON PILE)	M2	2203		
100 (S-F)	518002	SOUND WALL (MASONRY BLOCK)	M2	4850		