Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	15.8/16.9	81	145

REGISTERED CIVIL ENGINEER 3-8-10 DATE

5-24-10
PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER Mai P. Bui No. C61280 Exp 6-30-11 STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

CONCRETE BARRIER

1

SHEET No.	STATION	CONCRETE BARRIER (TYPE 732 Mod)	STRUCTURAL CONCRETE BARRIER SLAB	CONCRETE BARRIER (TYPE 60R Mod)	CONCRETE BARRIER (TYPE 60C)	CONCRETE BARRIER (TYPE 60C Trans)	CONCRETE BARRIER (TYPE 60D Mod)	CONCRETE BARRIER (TYPE 60E Mod)	BAR REINFORCING STEEL
		LF	~~LF~~ CY	LF	LF	LF	LF	LF	LB
L-1	110+80.75 TO 116+00	267	84 ~~267~~ ~~58~~	253			267		7782
L-2	116+00 TO 130+00	414	131 ~~414~~ ~~90~~		437	199	77	186	12098
L-3	130+00 TO 143+00				385	181		310	
L-4	143+00 TO 156+00				1068	99			
L-5	156+00 TO 164+60	302	95 ~~302~~ ~~66~~	60	440	60			8798
SUBTOTAL					2330	539			
TOTAL		983	310 ~~983~~ ~~214~~	313	2869		344	496	28678

~~1~~ 2 1

ROADWAY ITEMS

SHEET NUMBER	ROADWAY EXCAVATION	JOINTED PLAIN CONCRETE PAVEMENT	LEAN CONCRETE BASE	CLASS 3 AGGREGATE BASE	VEGETATION CONTROL (MINOR CONCRETE)	MINOR HMA	DITCH EXCAVATION	REMOVE CURB	REMOVE MBGR	REMOVE DOUBLE METAL BEAM BARRIER	REMOVE RETAINING WALL	SEAL PAVEMENT JOINT	SEAL LONGITUDINAL ISOLATION JOINT	METAL BEAM GUARD RAILING (WOOD POST)	END ANCHOR ASSEMBLY (TYPE SFT)	ALTERNATIVE IN-LINE TERMINAL SYSTEM	REMOVE AC DIKE	PLACE HMA DIKE	END CAP (TYPE A)	TEMPORARY DRAINAGE INLET PROTECTION	TEMPORARY COVER
	CY	CY	CY	CY	SQYD	TON	CY	LF	LF	LF	LF	LF	LF	LF	EA	EA	LF	LF	EA	EA	SQYD
L-1	787	96	48	67				1039	519			366	1039							3	100
L-2	2189	394	197	275				2471	720	427	108	1475	2471							2	150
L-3	1723	390	195	273	82	0.4		1754	214	663		1117	1755	100	2	1		50	1	1	150
L-4	1662	443	222	310				2466	783	384	783	2047	2333							3	100
L-5	1218	234	117	164		0.1	75	1720	860		500	1220	1720				1000	13.3		3	100
TOTAL	7579	1557	778	1089	82	0.5	75	9450	3096	1474	1391	6225	9318	100	2	1	1000	63.3	1	12	600

2 **REVISED PER ADDENDUM No. 2 DATED OCTOBER 26, 2010**

1 **REVISED PER ADDENDUM No. 1 DATED OCTOBER 21, 2010**

SUMMARY OF QUANTITIES

Q-1

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans® OFFICE OF DESIGN A

FUNCTIONAL SUPERVISOR: SIMON KUO
CALCULATED-DESIGNED BY: STEWART STAHL
CHECKED BY: MAI BUI
REVISED BY
DATE REVISED

LAST REVISION 00-00-00
DATE PLOTTED => 26-OCT-2010
TIME PLOTTED => 10:21