

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

TTY 711

*Flex your power!
Be energy efficient!*

December 29, 2011

07-LA-710-17.2/26.4

07-202114

Project ID 0700020869

ACNH-710-1(809)N

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN LOS ANGELES COUNTY ON ROUTE 710 AT VARIOUS LOCATIONS FROM LOS ANGELES RIVER BRIDGE TO RAMONA BOULEVARD UNDERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, January 12, 2012.

This addendum is being issued to revise the Project Plans, the Notice to Bidders and Special Provisions, the Bid book, and the Federal Minimum Wages with Modification Number 35 dated 12/23/11.

Project Plan Sheets 2, 626 and 758 are revised. Copies of the revised sheets are attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 10-1.01, "ORDER OF WORK," the twenty-first paragraph is revised as follows:

"Prior to applying hot mix asphalt, the Contractor shall cover all manholes, valve and monument covers, grates, or other exposed facilities located within the area of application, using a plastic or oil resistant construction paper secured to the facility being covered by tape or adhesive. The covered facilities shall be referenced by the Contractor, with a sufficient number of control points to relocate the facilities after the hot mix asphalt has been placed. After completion of the hot mix asphalt operation, all covers shall be removed and disposed of in a manner satisfactory to the Engineer. Full compensation for covering manholes, valve and monument covers, grates, or other exposed facilities, referencing, and removing temporary cover shall be considered as included in the contract price paid per ton for hot mix asphalt, and no additional compensation will be allowed therefor."

Addendum No. 1
Page 2
December 29, 2011

07-LA-710-17.2/26.4
07-202114
Project ID 0700020869
ACNH-710-1(809)N

In the Special Provisions, Section 10-1.47, "HOT MIX ASPHALT," subsection "SUMMARY," of subsection "GENERAL," the first paragraph is revised as follows:

"This work includes producing and placing hot mix asphalt (HMA) Type A using the Quality Control / Quality Assurance process."

In the Special Provisions, Section 10-1.47, "HOT MIX ASPHALT," subsection "ASPHALT BINDER," of subsection "MATERIALS," the first paragraph is revised as follows:

"The grade of asphalt binder mixed with aggregate for HMA Type A must be PG 64-10."

In the Special Provisions, Section 10-1.47, "HOT MIX ASPHALT," subsection "AGGREGATE," of subsection "MATERIALS," the first paragraph is revised as follows:

"The aggregate for HMA Type A must comply with the 3/4" maximum, medium grading."

In the Special Provisions, Section 10-1.49, "HOT MIX ASPHALT AGGREGATE LIME TREATMENT - SLURRY METHOD," subsection "SUMMARY," of subsection "GENERAL," the second paragraph is revised as follows:

"Treat aggregate for hot mix asphalt (Type A) with lime slurry."

In the Special Provisions, Section 10-1.60, "PILING," the following paragraph is added after the third paragraph of subsection "GENERAL":

"Concrete for cast-in-place concrete piling shall be prequalified in conformance with the provisions in Section 90-9, "Compressive Strength," of the Standard Specifications."

In the Bid book, in the "Bid Item List," Item 118 is deleted as attached.

To Bid book holders:

Replace page 8 of the "Bid Item List" in the Bid book with the attached revised page 8 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No. 1
Page 3
December 29, 2011


07-LA-710-17.2/26.4
07-202114
Project ID 0700020869
ACNH-710-1(809)N

This addendum, attachments and the modified wage rates are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/07/07-202114

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



for
REBECCA D. HARNAGEL
Chief, Office of Plans, Specifications & Estimates
Office Engineer
Division of Engineering Services

Attachments

**BID ITEM LIST
07-202114**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
101 (F)	193031	PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	CY	1,435		
102	193114	SAND BACKFILL	CY	85		
103 (F)	193116	CONCRETE BACKFILL (SOLDIER PILE WALL)	CY	370		
104 (F)	193119	LEAN CONCRETE BACKFILL	CY	116		
105	021300	DITCH EXCAVATION (TYPE Z-2) (AERIALY DEPOSITED LEAD)	CY	970		
106	200001	HIGHWAY PLANTING	LS	LUMP SUM	LUMP SUM	
107	200114	ROCK BLANKET	SQYD	530		
108	203026	MOVE-IN/MOVE-OUT (EROSION CONTROL)	EA	1		
109	203031	EROSION CONTROL (HYDROSEED) (SQFT)	SQFT	31,200		
110	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM	LUMP SUM	
111	208000	IRRIGATION SYSTEM	LS	LUMP SUM	LUMP SUM	
112	260201	CLASS 2 AGGREGATE BASE	CY	1		
113	260210	AGGREGATE BASE (APPROACH SLAB)	CY	36		
114	260301	CLASS 3 AGGREGATE BASE	CY	43,600		
115	280000	LEAN CONCRETE BASE	CY	16,800		
116	021301	LEAN CONCRETE BASE (RAPID SETTING)	CY	29,600		
117	390131	HOT MIX ASPHALT	TON	10,220		
118	BLANK					
119	391007	PAVING ASPHALT (BINDER, GEOSYNTHETIC PAVEMENT INTERLAYER)	TON	3		
120	393003	GEOSYNTHETIC PAVEMENT INTERLAYER	SQYD	1,990		