

DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
OFFICE ENGINEER, MS 43
1727 30TH STREET
P.O. BOX 168041
SACRAMENTO, CA 95816-8041
FAX (916) 227-6214
TTY 711



*Flex your power!
Be energy efficient!*

July 9, 2009

07-LA-710-17.9/20.8
07-269004
SARRA-P710(014)E

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN LOS ANGELES COUNTY IN SOUTH GATE, CUDAHY, BELL GARDENS, BELL, AND CITY OF COMMERCE FROM 0.6 MILE SOUTH OF FIRESTONE BOULEVARD OVERCROSSING TO 0.2 MILE SOUTH OF SLAUSON AVENUE OVERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, July 23, 2009.

This addendum is being issued to revise the Project Plans, the Notice to Bidders and Special Provisions, the Bid book, and the Federal Minimum Wages with Modification Number 25 dated 07/03/2009.

Project Plan Sheet 273 is revised. A half-sized copy of the revised sheet is attached for substitution for the like-numbered sheet.

In the Special Provisions, Section 10-1.25, "EXISTING HIGHWAY FACILITIES," subsection "REMOVE PORTLAND CEMENT CONCRETE PAVEMENT," is added as attached.

In the Bid book, in the "Bid Item List," Items 135 and 136 are added and Item 134 is deleted as attached.

To Bid book holders:

Replace page 9 of the "Bid Item List" in the Bid book with the attached revised page 9 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No. 1
Page 2
July 9, 2009

07-LA-710-17.9/20.8
07-269004
SARRA-P710(014)E

This office is sending this addendum by GSO overnight mail to Bid book holders to ensure that each receives it. A copy of this addendum and the modified wage rates are available for the Contractors' use on the Web site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addenda.php

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Division of Engineering Services - Office Engineer

Attachments

REMOVE PORTLAND CEMENT CONCRETE PAVEMENT

Removing portland cement concrete pavement shall conform to the provisions in Section 15-3, "Removing Concrete," of the Standard Specifications.

Where no joint exists in the pavement on the line at which concrete is to be removed, a straight, neat cut with a power driven saw shall be made along the line to a minimum depth of 2 inches before removing the concrete.

The quantities of portland cement concrete pavement removed will be measured and paid for by the square yard.

No deduction will be made from any excavation quantities for the quantity of portland cement concrete pavement removed.

Full compensation for removing bituminous or other overlying material , as required, shall be considered as included in the contract price paid per square yard for remove concrete pavement and no additional compensation will be allowed therefor.

BID ITEM LIST
07-269004

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
121	850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	22,500		
122	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	8,870		
123	860090	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	LUMP SUM	LUMP SUM	
124	860889	MODIFY TRAFFIC MONITORING STATION	LS	LUMP SUM	LUMP SUM	
125	016720	MODIFY AUTOMATIC VEHICLE CLASSIFICATION STATION	LS	LUMP SUM	LUMP SUM	
126	861088	MODIFY RAMP METERING SYSTEM	LS	LUMP SUM	LUMP SUM	
127	861504	MODIFY LIGHTING AND SIGN ILLUMINATION	LS	LUMP SUM	LUMP SUM	
128	016721	COMMUNICATION SYSTEM	LS	LUMP SUM	LUMP SUM	
129	016722	CLOSED CIRCUIT TELEVISION CAMERA (LOCATION LB185)	LS	LUMP SUM	LUMP SUM	
130	016723	MODIFY CHANGEABLE MESSAGE SIGN SYSTEM (LOCATION NO. 88)	LS	LUMP SUM	LUMP SUM	
131	016724	CLOSED CIRCUIT TELEVISION CAMERA (LOCATION LB191)	LS	LUMP SUM	LUMP SUM	
132	016725	CLOSED CIRCUIT TELEVISION CAMERA (LOCATION LB198)	LS	LUMP SUM	LUMP SUM	
133	869075	SYSTEM TESTING AND DOCUMENTATION	LS	LUMP SUM	LUMP SUM	
134	BLANK					
135	150846	REMOVE CONCRETE PAVEMENT	SQYD	64,700		
136	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID: _____