

**DEPARTMENT OF TRANSPORTATION**  
DIVISION OF ENGINEERING SERVICES  
OFFICE ENGINEER, MS 43  
1727 30<sup>TH</sup> STREET  
P.O. BOX 168041  
SACRAMENTO, CA 95816-8041  
FAX (916) 227-6214  
TTY 711



*Flex your power!  
Be energy efficient!*

March 4, 2009

09-Iny,Mno-168,266-Various  
09-339404

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN INYO AND MONO COUNTIES AT VARIOUS LOCATIONS.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Wednesday, March 11, 2009.

This addendum is being issued to revise the Project Plans, the Notice to Bidders and Special Provisions, Estimate and the Bid book.

Project Plan Sheet 2 is revised as follows:

On the Typical Cross Sections detail, where existing polymer modified asphalt seal coat is described, replace "Polymer Modified Asphalt" with "Modified Binder."

Project Plan Sheet 5 is revised as follows:

In the Roadway Quantities table, the column for "Asphalt Binder (Polymer Modified) " is revised to "Modified Binder."

In the Special Provisions, Section 5-1.03,"COMPENSATION ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS," the table below the first paragraph is revised as follows:

"Item Code 370125, Asphalt Binder (Polymer Modified) " is revised to "Item Code 016115, Modified Binder."

In the Special Provisions, Section 10-1.16,"HOT-APPLIED SEAL COAT (POLYMER MODIFIED ASPHALT)," is deleted.

In the Special Provisions, Section 10-1.165,"MODIFIED BINDER SEAL COAT," is added as attached.

Addendum No. 1  
Page 2  
March 4, 2009

09-Iny,Mno-168,266-Variou  
09-339404

In the Bid book, in the "Bid Item List," Item 15 is added and Item 10 is deleted as attached.  
To Bid book holders:

Replace page 3 of the "Bid Item List" in the Bid book with the attached revised page 3 of the Bid Item List.  
The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by confirmed facsimile to all book holders to ensure that each receives it. A copy of this addendum is available for the Contractors' use on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/weekly\\_ads/addendum\\_page.html](http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html)**

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

MALCOLM DOUGHERTY  
District Director  
District 6 Central Region

Attachments

#### **10-1.165 MODIFIED BINDER SEAL COAT**

Modified binder seal coat shall consist of an application of modified asphalt and hot screenings precoated with paving asphalt. Modified binder seal coat shall conform to the provisions specified for seal coat in Section 37-1, "Seal Coats," of the Standard Specifications and these special provisions.

Attention is directed to "Order of Work" and "Damage Claims" of these special provisions.

#### **MATERIALS**

##### **Quality Control Testing**

Attention is directed to Section 6-3.02, "Testing By Contractor," of the Standard Specifications. The name of an independent testing laboratory that participates in the AASHTO Proficiency Sample Program shall be submitted to the Engineer for approval at least 10 days before beginning modified binder seal coat operations. The independent testing laboratory shall conduct quality control testing on the modified binder for all specifications listed in these special provisions, within 3 business days of sampling. The results shall be submitted to the Engineer within 7 days of the receipt of the samples. Within 10 days of beginning the modified binder seal coat operation, the Contractor's independent testing laboratory shall conduct the Vialit Test Method for aggregate in Chip Seals, French Chip for the retention requirement and submit a signed copy of a test results report to the Engineer and to:

Department of Transportation  
Division of Maintenance, Roadway Maintenance Office  
1120 N Street, MS 31  
Sacramento Ca, 95814

The report will not be considered for acceptability testing. The Vialit Test Method is available at:

<http://www.dot.ca.gov/hq/esc/ctms/index.html>

## MODIFIED BINDER

Modified asphalt binder shall conform to the following requirements:

Specification Designation	AASHTO Designation	PG76-22PM Test Requirement	PG76-22TR Test Requirement
<b>Tests on Original Binder</b>			
Specific Gravity @ 15.5 °C	T 228	Report	Report
Pounds per Gallon @ 15.5 °C		Report	Report
Gallons per Ton @ 15.5 °C		Report	Report
Solubility, Minimum %	T44	99	97.5
Percent Rubber Content, % min.	-	-	10.0
DSR, G*/sin delta @ 76° C, kPa	T 315	1.0 min.	1.0 min.
Penetration, 4° C, 200g/60s, dmm	T 49	25 min.	25 min.
Penetration, 25° C, 100g/5s, dmm	T 49	40 – 90	40 – 90
Softening Point, °C	T 53	82 min.	82 min.
Flash Point, °C	T 48	230 min.	230 min.
Rotational Viscosity @ 163° C, cps	T 316	250 – 1000	250 – 1000
Elastic Recovery, 25 °C, %	T 301	65 min.	65 min.
Chip adhesion,	ASTM D 3625	Pass	Pass
<b>Tests On Residue from RTFO</b>			
Softening Point, °C	T 53	Report	Report
Mass Loss after RTFO, wt%	T 240	1.0 max.	1.0 max.
<b>Test on PAV Residue (100° C) (AASHTO Designation PP-1)</b>			
BBR, creep stiffness @ -12° C MPa	T 313	300 max.	300 max.
BBR, m-value @ -12° C	T 313	0.300 min.	0.300 min.

A Certificate of Compliance shall be furnished to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The certificate shall certify that the material which the certificate represents conforms to the provisions specified in these special provisions. When requested by the Engineer, the Contractor shall also submit samples with the Certificates of Compliance. The Contractor shall provide the Engineer a Material Safety Data Sheet (MSDS) for each of the constituent components of the modified asphalt binder and for the completed mixture of the modified asphalt binder.

The Contractor shall provide a Certificate of Compliance for each truckload of modified binder. The Quality Control Program used by the manufacturer of each ingredient shall include a sampling and testing frequency as shown below:

- A. CRM shall be tested except for the grading requirement, at least once for every 250 tons with a minimum of once per project. CRM shall be tested for grading for every truckload delivered to the project.
- B. Polymer shall be tested at least once for every 250 tons with a minimum of once per project.
- C. Paving asphalt shall be tested at least once for every 200 tons of production with a minimum of once per project.
- D. A copy of the laboratory test results for the test parameters specified in these special provisions for CRM, paving asphalt, and polymer shall be submitted to the Engineer with the Certificate of Compliance for each truckload of individual material delivered to the project.

Certified volume or weight slips shall be delivered to the Engineer for materials supplied.

The maximum length of modified binder seal coat operations at any one location, including pilot-car-assisted traffic control shall be limited to 5 miles. The minimum space between successive seal coat operations on adjacent lanes in the same direction of travel shall be 5 miles.

Modified binder shall conform to either the PG 76-22 PM or the PG 76-22 TR specifications listed in these special provisions. The Contractor shall notify the Engineer in writing of the grade of polymer modified asphalt binders selected. No change in grade shall be made without the written approval of the Engineer.

At least 2 weeks before its intended use, the Contractor shall furnish the Engineer 4 one-quart cans filled with the modified binder proposed for use on the project. Laboratory test results for test parameters shown in these special provisions shall be provided with the modified binder.

## SCREENINGS

Screenings shall conform to the provisions in these special provisions and in Section 37-1.02, "Materials," of the Standard Specifications, except that the third, fourth, eighth, and ninth paragraphs of Section 37-1.02 shall not apply.

Stockpiling of screenings after preheating and precoating with paving asphalt will not be permitted.

Canvas or similar covers that completely cover each load of precoated screenings shall be used during hauling to minimize temperature drop of the precoated screenings.

Screenings shall conform to the following grading requirements prior to precoating with paving asphalt:

SCREENINGS GRADING REQUIREMENTS 1/2 inch Medium Maximum	
Sieve Sizes	Percentage Passing
3/4"	100
1/2"	85- 90
3/8"	0 – 30
No. 4	0 – 5
No. 8	--
No. 200	0 – 1

Screenings shall conform to the following quality requirements immediately prior to preheating:

SCREENINGS QUALITY REQUIREMENTS		
Test Parameters	California Test	Requirements
Los Angeles Rattler Loss (100 Revolutions)	211	10 Max.
Los Angeles Rattler Loss (500 Revolutions)	211	40 Max.
Film Stripping	302	25 Max.
Cleanness Value	227	80 Min.
Durability	229	52 Min.

Screenings for modified binder seal coat shall be preheated to between 260° F and 325° F and uniformly coated at a rate of 0.7-percent to one percent by weight of dry aggregate with any of the asphalts specified in the table "Performance Graded Asphalt Binder" in Section 92, "Asphalts," of the Standard Specifications. Screenings shall be coated at a central mixing asphalt concrete plant that has been approved in conformance with the requirements in California Test 109. The exact rate will be determined by the Engineer.

## **EQUIPMENT**

The equipment used by the Contractor for modified binder seal coat operations shall conform to the following:

- A. Self-propelled power brooms shall clean the existing pavement and remove loose screenings without dislodging screenings set in the modified binder. Gutter brooms or steel-tined brooms shall not be used.
- B. A minimum of 3 pneumatic-tired rollers conforming to the provisions in Section 39-3.03, "Spreading and Compacting Equipment," of the Standard Specifications, except that the rollers shall carry a minimum loading of 3,000 pounds on each wheel and an air pressure of 100 pounds per square inch  $\pm$ 5 pounds per square inch in each tire, shall compact the seal coat.
- C. A self-propelled screenings spreader, equipped with a screenings hopper in the rear, belt conveyors to carry the screenings to the front, and a spreading hopper equipped with full-width distribution auger and spread roll, shall spread the screenings. . The screenings spreader shall be capable of providing a uniform screening spread rate over the entire width of the traffic lane in one application.
- D. A self-propelled distributor truck shall be used for applying modified binder. The distributor truck shall be equipped with a heating unit, a pump or pumps that spray the modified binder within  $\pm$ 0.03-gallon per square yard of the specified rate and a fully circulating spray bar that applies the binder without a streaked or otherwise irregular pattern. The distributor truck shall be equipped with a tachometer, pressure gages, volume measuring devices, and thermometer.
- E. Trucks for hauling screenings shall be equipped so that screenings can be discharged from the tailgate. Trucks shall be equipped with a device to lock onto the hitch at the rear of the screenings spreader. Haul trucks shall be compatible with the screenings spreader so that the dump bed will not push down on the spreader when fully raised. Haul truck dump beds shall be designed so that, while dumping into the receiving hopper, screenings shall be prevented from spilling on the roadway.

## **PREPARATION FOR SEAL COAT**

Surfaces to receive modified binder seal coat shall be prepared in conformance with the provisions specified for preparing surfaces to receive asphaltic emulsion as specified in Section 37-1.04, "Preparation for Seal Coat," of the Standard Specifications.

## **APPLYING MODIFIED BINDER**

Modified binder shall be applied in conformance with the provisions specified for applying asphaltic emulsion in Section 37-1.05, "Applying Asphaltic Emulsion," of the Standard Specifications, except the second, third, fourth, and fifth paragraphs shall not apply.

Modified binder shall be applied at a rate from 0.35-gallon to 0.50-gallon per square yard. The exact rate will be determined by the Engineer. The binder shall be applied when the temperature of the binder is between 330° F and 375° F.

Modified binder shall not be applied when weather conditions are unsuitable or when the pavement is damp or wet. The pavement surface temperature shall be a minimum of 55° F where modified binder is to be applied. The atmospheric temperature shall be a minimum of 60° F and a maximum of 105° F. Modified binder shall not be applied until sufficient screenings are available to immediately cover the binder being applied.

Distributor bar height, distribution speed, and shielding materials shall be utilized to reduce the effects of wind upon spray distribution as directed by the Engineer. The Engineer will delay or reschedule work when high, gusting or dirty winds prevent or adversely affect binder or screening application operations. Necessary equipment shall be in position and ready to commence placement operations before starting.

The Contractor shall comply with Federal, State, and Local environmental laws, rules, regulations, and ordinances including, but not limited to, air quality requirements.

The modified binder application shall not be spread in excess of that which can be covered with screenings within 2 minutes.

When placing modified binder seal coat at intersections, left turn lanes, gore points, and other irregular areas, modified binder application shall not be in excess of that which can be covered with screenings within 15 minutes.

When joining edges against areas with screenings, the joint shall be swept clean of excess screenings prior to the adjacent application of modified binder. Transverse joints of this type shall be constructed by placing roofing paper across and over the end of the previous modified binder seal coat application. Once the spraying has progressed beyond the paper, the paper shall be removed immediately.

The longitudinal joint between adjacent applications of screenings shall coincide with the line between designated traffic lanes. Longitudinal joints shall be overlapped for complete coverage. The overlap shall not exceed 4 inches.

At longitudinal joints with screenings, the edge shall be broomed back and blended to eliminate differences in elevation. The joints shall be free from ridges and depressions and shall have a uniform appearance consistent with the adjacent sealed surface. Defects shall be corrected at the Contractor's expense.

Joints between areas of modified binder without screenings shall be made by overlapping modified binder distributions. The excess material shall be properly dispersed by spreading with a squeegee or rake over a larger area of freshly applied modified binder.

The application of modified binder to areas not accessible with the distributor bar on the distributor truck shall be accomplished by using pressurized hand wands or other means approved by the Engineer.

## **SPREADING SCREENINGS**

Screenings for modified binder seal coat shall be spread in conformance with the provisions specified for spreading screenings on asphaltic emulsion in Section 37-1.06, "Spreading Screenings," of the Standard Specifications, except the first, fifth, sixth, and seventh paragraphs shall not apply.

Screenings for modified binder seal coat shall be spread immediately following the application of the binder, within the range of 20 pounds to 34 pounds per square yard. The exact rate will be determined by the Engineer. . The completed spread rate shall be within 10 percent of the rate determined by the Engineer. The completed surface shall be free of gaps, ridges, depressions or other irregularities caused by the application of the modified binder seal coat.

Screenings shall be spread when the temperature of the precoated screenings is not less than 225° F and not more than 325° F after applying modified binder.

The screenings spreader shall not be more than 50 feet behind the modified binder distribution truck unless otherwise ordered by the Engineer. Trucks hauling screenings shall be kept clear of the freshly placed screenings until ready to dump screenings in the spreader equipment.

## **FINISHING**

Modified binder seal coat shall be finished in conformance with the provisions for finishing screenings spread on asphaltic emulsion in Section 37-1.07, "Finishing," of the Standard Specifications, except the second and third paragraphs of Section 37-1.07 shall not apply. In addition, the following shall apply:

- A. Removal of excess screenings shall be completed before uncontrolled traffic is permitted on the modified binder seal coat.
- B. Initial rolling of the modified binder seal coat shall consist of a minimum of one complete coverage with one or more pneumatic-tired rollers and shall begin immediately behind the screenings spreader. The distance between the rollers and the screenings spreader shall not exceed 200 feet at any time during the spreading of screenings operations.
- C. A minimum of 3 complete coverages, after the initial coverage, shall be made with pneumatic-tired rollers on the modified binder seal coat. Each coverage of the roller shall be as defined in Section 39-3.04, "Transporting, Spreading, and Compacting," of the Standard Specifications.
- D. An initial brooming shall be performed after completion of the final rolling and prior to routing public traffic on the modified binder seal coat. Removal of excess screenings shall be completed before uncontrolled traffic is permitted on the completed asphalt-rubber seal coat. Final sweeping shall be done and loose screenings shall be removed without dislodging the screenings set in the asphalt-rubber binder prior to acceptance.
- E. Sweeping shall be a multi-step operation following final rolling of the screenings. Loose screenings shall be removed from the roadway surface and abutting adjacent areas. Loose screenings shall be disposed of at least 150 feet from the nearest waterway.

## **FLUSH COAT**

Flush coat shall consist of an application of a fog seal coat followed by a sand cover to the surface of the modified binder seal coat. Flush coat shall conform to the provisions in Section 37-1, "Seal Coats," of the Standard Specifications and these special provisions.

Flush coat shall be applied to the modified binder seal coat immediately after initial brooming of the hot-applied seal coat and removal of excess screenings and prior to opening the lane to uncontrolled (not controlled with pilot cars) public traffic.

### **Fog Seal Coat**

Asphaltic emulsion (fog seal coat) shall be Grade CSS1 or CSS1h or CQS1 as directed by the Engineer.

The asphaltic emulsion (fog seal coat) shall be applied at a rate of 0.03-gallon to 0.06-gallon per square yard. The exact rate of application will be determined by the Engineer.

Attention is directed to Section 7-1.11, "Preservation Of Property," of the Standard Specifications and "Existing Highway Facilities" of these special provisions regarding protecting the highway facilities from the fog seal coat.

During flush coat operations, the surface upon which the flush coat is being applied shall be closed to public traffic. Care shall be taken to avoid tracking fog seal coat material onto existing pavement surfaces beyond the limits of construction.

### **Sand Cover**

Sand cover shall be applied immediately following application of the fog seal coat.

Sand for the sand cover shall conform to the provisions for fine aggregate grading in Section 90-3.03, "Fine Aggregate Grading," of the Standard Specifications and these special provisions. Sand shall not contain clay and shall not contain organic material.

Sand shall be spread by means of a self-propelled chip spreader equipped with a mechanical device that will spread the sand at a uniform rate over the full width of a traffic lane in a single application. Sand shall be spread at a rate of 2 pounds to 4 pounds per square yard. The exact spread rate will be determined by the Engineer.

## **MEASUREMENT AND PAYMENT**

Screenings for modified binder seal coat will be measured by the ton after preheating and precoating with paving asphalt in the same manner specified for hot mix asphalt in Section 39-5.01, "Measurement," of the Standard Specifications. Paving asphalt used for precoating screenings will be paid for as screenings (hot-applied). Modified binder for modified binder seal coat will be measured by the ton in the same manner specified for asphalt in Section 92-1.04, "Measurement," of the Standard Specifications.

The contract price paid per ton for modified binder shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in applying modified binder, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The contract price paid per ton for screenings (hot-applied) shall include full compensation for furnishing all labor, materials (including paving asphalt for precoating screenings), tools, equipment, and incidentals and for doing all the work involved in spreading the screenings, complete in place, including preheating and precoating screenings, removal of pavement markers, furnishing, placing, maintaining, and removing C6 (Loose Gravel) and W6 (35 MPH) signs and temporary supports or barricades for the signs, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Sand cover will be measured and paid for in the same manner specified for screenings in Section 37-1.08, "Measurement," and Section 37-1.09, "Payment," of the Standard Specifications.

No adjustment in compensation will be made for any increase or decrease in the quantities of asphaltic emulsion (fog seal coat) and sand cover required, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to the items of asphaltic emulsion (fog seal coat) and sand cover.

**BID ITEM LIST**  
**09-339404**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	074016	CONSTRUCTION SITE MANAGEMENT	LS	LUMP SUM	LUMP SUM	
2	074017	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM	LUMP SUM	
3	074038	TEMPORARY DRAINAGE INLET PROTECTION	EA	2		
4	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
5	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
6	128650	PORTABLE CHANGEABLE MESSAGE SIGN	LS	LUMP SUM	LUMP SUM	
7	150715	REMOVE THERMOPLASTIC PAVEMENT MARKING	SQFT	360		
8	190110	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
9	365001	SAND COVER	TON	840		
10	BLANK	BLANK	BLANK			
11	374002	ASPHALTIC EMULSION (FOG SEAL COAT)	TON	87		
12	375030	SCREENINGS (HOT-APPLIED)	TON	7,540		
13	840656	PAINT TRAFFIC STRIPE (2-COAT)	LF	464,000		
14	840666	PAINT PAVEMENT MARKING (2-COAT)	SQFT	360		
15	016115	MODIFIED BINDER	TON	880		