

FOR CONTRACT NO.: 09-343404

INFORMATION HANDOUT

MATERIALS INFORMATION

EXISTING STRUCTURAL SECTION

ROUTE: 395-Mno-36.1/40.1

Materials Handout 09-343401 Deadman CAPM

This handout contains basic information pertaining to the existing structural section on US Highway 395 within the project limits. Summarized below is a description of the existing structural section based on as-built and as awarded plans. Copies of the plans are available at the Caltrans District 9 office at 500 South Main St., Bishop CA, 93514. Please contact Stephen Winzenread at 760.872.5222 for additional information.

The existing structural section consists of the following (listed from top layer down to base):

1. 0.08' Rubberized Asphalt Concrete (Type-G)
2. 0.4' Asphalt Concrete (Type B)
3. Slurry Seal
4. 0.45' Asphalt Concrete (Type B)
5. 0.35' Class 2 Aggregate Base